SECTION 10-00121-01-PV BEGINS
STA 102+02.58

DEPT OF URBAN RENEWAL
CITY OF JACKSONVILLE

CHARLES C & REVA R KRELL

SEC 20, T15N, R10W, 3RD PM

STA 106+74.65 (SOUTH MAIN STREET)=
STA 125+00.00 (COLLEGE AVENUE)

GEORGE M STICE

PHILLIP MORRIS BEVERAGES, INC

PROPOSED PCC SIDEWALK, 4"

2 CENTERED CURVE
R1=40' - R2=120'
OFFSET=5.0'

PROPOSED ROW LINE

PROPOSED B-6.12 COMBINATION CONCRETE CURB AND GUTTER

EXISTING ROW LINE

PROPOSED 4' SANITARY MH
STA 106+74.68, 6.06' LT
L = 601.52
N INV = ±591.16
S INV = ±591.07
CONSTRUCT AROUND EX 10"
SEE SPECIAL DETAILS

MATCH LINE STA 107+50

℄ CONSTRUCTION SOUTH MAIN STREET

SOUTH MAIN STREET

BEECHER AVENUE

COLLEGE AVENUE

CITY OF JACKSONVILLE

W LUKE &
DEBORAH K FRY

JAMES B &
PATRICIA ANN BARNES

MICHAEL R WANKEL

THREE IRISHMEN AND A TOAD, INC

℄ ENT +00.0
℄ ENT +15.8
℄ ENT +64.9
℄ ENT +73.5
℄ ENT +84.7
℄ ENT +30.5
℄ ENT +53.4

89°40'07"

SEC 21, T15N, R10W, 3RD PM

GRAPHIC SCALE IN FEET

PROFILE

PROPOSED PROFILE GRADE LINE

EXISTING PROFILE GRADE LINE SOUTH MAIN STREET

590.77 (EXISTING)
+62.58
590.85 EX
+76.69
592.82
592.22
592.11 (PROPOSED)
593.38
593.33
594.53
594.43
595.69
595.53
596.89
596.64
598.02
597.74
599.03
598.84
599.96
599.92
600.87
600.96
601.84
601.97
603.03 (EXISTING)
603.08

+2.66%
+2.20%
+2.29%
+2.03%
+2.03%
+2.60%

+57.16
EL. 599.00
+47.16 EL. 600.90
+96.09 EL. 601.89
VPI STA. 106+02.36
ELEVATION 599.99
VPI STA. 107+41.09
ELEVATION 602.81

90.00' V.C.

102+00 102+50 103+00 103+50 104+00 104+50 105+00 105+50 106+00 106+50 107+00 107+50

604 602 600 598 596 594 592 590 588

FILE NAME = V:\Transportation\2893\SMAINPPL.dgn	USER NAME = jolson	DESIGNED - JRB	REVISED -
		DRAWN - JMO	REVISED -
	PLOT SCALE = 20.0000 ' / IN.	CHECKED - JRB	REVISED -
	PLOT DATE = 2/23/2011	DATE - 2/22/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CITY OF JACKSONVILLE DOWNTOWN STREETS CONSTRUCTION
SOUTH MAIN STREET PLAN & PROFILE SHEET

SCALE: 1" = 20' | SHEET NO. OF SHEETS | STA. 102+02.58 TO STA. 107+50.00

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	10-00121-01-PV	MORGAN	77	21

CONTRACT NO. 93547

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT