

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 8390	04-00084-06-PV	EFFINGHAM	139	4
FED. ROAD DIST. NO. 7	ILLINOIS			

CONTRACT #95639

1. The following rates of application have been assumed in calculating plan quantities:

Crushed Stone	2.05 Tons/CY
Bituminous Concrete	115 lbs/Inch/SY
Bituminous Materials (Prime Coat) on Aggregate Bases	0.50 Gal/SY
Nitrogen Fertilizer Nutrient	90 lbs/Acre
Phosphorus Fertilizer Nutrient	90 lbs/Acre
Potassium Fertilizer Nutrient	90 lbs/Acre
Agricultural Ground Limestone	2 Tons/Acre
Mulch, Method 2 (Procedure 1)	2 Tons/Acre
Temporary Erosion Control Seeding	100 lbs/Acre

2. Before ordering storm sewers, pipe culverts or pipe drains, the Contractor shall consult the Engineer for exact lengths.


3. The Engineer shall be the sole judge concerning curing time for the various bituminous lifts.

4. For the pay item Bituminous Materials (Prime Coat), the Contractor shall use either RC-70 or an emulsified polymer prime SS-IHP.

5. WALKS AND SLABS

A. Concrete walks, islands, and other slabs shall be in accordance with IDOT Std. Spec. Unless otherwise shown, locate sidewalk contraction joints at 5 ft on center and expansions joints at 50 ft on center, unless otherwise shown, locate contraction joints in larger slabs at 15 ft intervals in each direction, reinforced with lubricated smooth dowel bars (3/4 in. diameter, 18 in. length, at 12 in. centers).

B. Concrete walks crossing through entrances shall be constructed in accordance with the detail shown below. Monolithically constructed sidewalks will not be allowed.




DETAIL OF SIDEWALK THROUGH ENTRANCES

6. Removal of concrete pipe culverts and concrete encased clay pipe culverts will be paid for as pipe culvert removal. All other pipe culvert removal and headwall removal shall be considered included in the cost of Earth Excavation.

LEGEND

○	IRON PIN FOUND
○ 1/4	1/4" IRON PIN FOUND
○ IP	IRON PIPE FOUND
○ NGW	NAIL & WASHER FOUND
○ N	NAIL FOUND
○ PK	PK NAIL FOUND
○ RR	RAILROAD SPIKE FOUND
○ T	"T" FENCE POST FOUND
○ X	CHISELED "X" IN CONCRETE FOUND
○ DH	DRILLED HOLE IN CONCRETE FOUND
⊙	SURVEY DISC FOUND
⊘	STONE FOUND
☀	TREE (DECIDUOUS)
★	TREE (EVERGREEN)
⊙	FIRE HYDRANT
⊕	WATER METER
— v —	WATER MAIN (EXISTING)
— w —	WATER SERVICE LINE (EXISTING)
⊕	VALVE (GAS OR WATER)
⊕	GAS METER
— g —	GAS MAIN (EXISTING)
— g —	GAS SERVICE LINE (EXISTING)
⊕ C	CABLE TV PEDESTAL
— CT —	UNDERGROUND CABLE TV (EXISTING)
⊕ T	TELEPHONE PEDESTAL
⊕ T	TELEPHONE MANHOLE
— T —	TELEPHONE CABLE (EXISTING)
— t —	TELEPHONE SERVICE WIRE (EXISTING)
— ○ —	POWER POLE
⊕	POWER POLE w/LIGHT
←	GUY ANCHOR
⊕	LIGHTPOLE (EXISTING)
⊕ E	ELECTRIC PEDESTAL
— EHE —	OVERHEAD ELECTRIC (EXISTING)
— E —	UNDERGROUND ELECTRIC (EXISTING)
L/S	LANDSCAPING
⊕	FENCE POST
— x — x — x —	FENCE
⊕	MAILBOX
⊕	SIGN



MILANO & GRUNLOH ENGINEERS, LLC
 84 WEST WASHINGTON
 P.O. BOX 557
 EFFINGHAM, ILLINOIS 62401
 PHONE: (217) 347-7282
 (800) 677-2774
 FAX #: (217) 342-3433

GENERAL NOTES
 EVERGREEN AVENUE
 CITY OF EFFINGHAM, ILLINOIS
 COUNTY OF EFFINGHAM, ILLINOIS

File name: S:\DWG\05\05227\dwg\Title Sh1.dwg
 Plot date: 02/08/11 at 15:55