


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9266	06-00062-06-PV	ST. CLAIR	80	4
FHWA REG. NO. 7 ILLINOIS		PROJECT NO. RS-0163(035)		
FEDERAL AID PROJECT		CONTRACT NO. 97457		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	TRAFFIC SIGNAL
60222200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1	
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	7	7	
60224075	MANHOLES, TYPE A, 6'-DIAMETER	EACH	1	1	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	3	3	
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	2	2	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	5	5	
60240395	INLETS, TYPE B	EACH	2.0	2.0	
60403400	GRATES, TYPE A	EACH	3.0	3.0	
60500060	REMOVING INLETS	EACH	2.0	2.0	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	22.0	22.0	
60600605	CONCRETE CURB, TYPE B	FOOT	139.0	139.0	
60602500	CONCRETE GUTTER, TYPE A	FOOT	637.0	637.0	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6,450.0	6,450.0	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	288.0	288.0	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1.0	1.0	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	
63200310	GUARDRAIL REMOVAL	FOOT	325	325	
* 63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	513.0	513.0	
* 63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	4	4	
* 63302700	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6,141	6,141	
72000100	SIGN PANEL - TYPE 1	SQ FT	5		5
72000200	SIGN PANEL - TYPE 2	SQ FT	52		52
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62	62	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22,565	22,565	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	141	141	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	302	302	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	130	130	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	90	90	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	104	104	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6	
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	1		1
* 81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	92		92
* 81000500	CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL	FOOT	92		92

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	TRAFFIC SIGNAL
* 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	56		56
* 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	801		801
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	249		249
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	14		14
* 81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	59		59
* 81400100	HANDHOLE	EACH	7		7
* 81400300	DOUBLE HANDHOLE	EACH	1		1
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
* 85706000	INTERSECTION MONITOR UNIT	EACH	1		1
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	856		856
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	865		865
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1,534		1,534
* 87301804	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 1C	FOOT	288		288
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	389		389
* 87502740	TRAFFIC SIGNAL POST, ALUMINUM 20 FT.	EACH	1		1
* 87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1		1
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1		1
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3		3
* 87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	3		3
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	37		37
* 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1
* 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	5		5
* 88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		1
* 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1		1
* 88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2		2
* 88200300	TRAFFIC SIGNAL BACKPLATE, PLASTIC	EACH	6		6
* 88500515	INDUCTION LOOP DETECTOR AMPLIFIER WITH EXTENDED CALL - DELAY CALL	EACH	7		7
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	4,036		4,036
X0325592	REMOVE AND REPLACE STONE RIPRAP	CU YD	56	56	
X6028000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	1	1	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
Z0075496	CONCRETE RETAINING WALL REMOVAL	FOOT	139	139	
Z0076600	TRAINEES	HOUR	500	500	

△ 0042



* DENOTES SPECIALTY ITEM