### INDEX TO SHEETS

- COVER SHEET / INDEX TO SHEETS (CVR1)
- 2. SUMMARY OF QUANTITIES (QTY1)
- 3. SITE PLAN AND CONTROL (SPL1)
- 4. TYPICAL SECTION RWY 1/19 (TYP1)
- 5. TYPICAL SECTION BLAST PAD (TYP2)
- 6. TYPICAL SECTION RWY 7/25 (TYP3)
- TYPICAL SECTION TXY F WEST (TYP4)
- 8. TYPICAL SECTION TXY F EAST (TYP5)
- 9. TYPICAL SECTION TXY B (TYP6)

- 11. PHASING PLAN SUMMARY (PPM1)
- 12. PHASING PLAN NOTES (PPN1)
- 13. PHASING PLAN DETAILS (PPD1)
- 14. TEMPORARY RELOCATED THRESOLD (TRT1)
- 15. TEMPORARY RELOCATED THRESOLD DETAILS (TTD1)
- 16: STORMWATER POLLUTION PREVENTION PLAN (SWP1)
- 17. STORMWATER POLLUTION PREVENTION NOTES (SWN1)
- 18. STORMWATER POLLUTION PREVENTION DETAILS (SWD1)
- 19. EXISTING CONDITIONS AND REMOVALS 1 (EXC1)
- 20. EXISTING CONDITIONS AND REMOVALS 2 (EXC2) 21. EXISTING CONDITIONS AND REMOVALS - 2 (EXC3)
- 22 SANITARY SEWER ABANDONMENT PLAN (SAP1)
- 24. RUNWAY 1/19 PLAN / PROFILE (RPP2)
- 25. RUNWAY 1/19 PLAN / PROFILE (RPP3)
- 26. RUNWAY 7/25 PLAN / PROFILE (RPP4)
- 27. TAXIWAY L AND B PLAN / PROFILE (LPP1)
- 28. TAXIWAY F PLAN / PROFILE (FPP1)
- 29 TAXIWAY LAND B INTERSECTION GRADING (LIG1)
- 30. TAXIWAY F INTERSECTION GRADING (FIG1)
- 31. RUNWAY 7/25 INTERSECTION GRADING (RIG1)
- 32. JOINTING PLAN (JTP1)
- 33. JOINTING PLAN (JTP2)
- 34. JOINTING DETAILS (JTD1)
- 35. ELECTRICAL AND MARKING PLAN (EMP1)
- 36. ELECTRICAL AND MARKING PLAN (EMP2)
- 37. ELECTRICAL AND MARKING PLAN (EMP3) 38. ELECTRICAL AND MARKING NOTES (EMN1)
- 39. HOMERUM PLAN (HRP1)
- 40. ELECTRICAL DETAILS (ELD1)
- 41, ELECTRICAL DETAILS (ELD2)
- 42. FLECTRICAL DETAILS (ELD3)
- 43. ELECTRICAL DETAILS (ELD4)
- 44. ELECTRICAL DETAILS (ELD5) 45. MARKING DETAILS (MRD1)
- 46. MARKING DETAILS (MRD2)
- 47. PAPI PLAN AND DETAILS (PPD1
- 48. RUNWAY 7 PAPI MODIFICATION PLAN / DETAILS (PVM1)
- 49. GROOVING PLAN AND DETAILS (GPD1) 50. ENGINEERING INFORMATION (ENG1)
- 51. WATER MAIN ABANDONMENT PLAN (WAP1) 52. WATER MAIN PLAN AND PROFILE (WPP1)
- 53. WATERMAIN DETAILS (WMD1)
- 54. WATERMAIN DETAILS (WMD2)

## ADD, ALT, 1: TXY B, F WEST, AND RIAT RD.

- 55. AA1: SITE PLAN / CONTROL (1SP1)
- 56. AA1: TYPICAL SECTION TXY F WEST (1TY1)
- 57. AA1: TYPICAL SECTION TXY B (1TY2)
- 58. AA1: EXISTING CONDITIONS REMOVALS (1EX1)
- 59. AA1: RIAT ROAD SITE PLAN AND TYPICAL SECTION (1RR1)

## ADD. ALT. 2: TXY L, F EAST AND RWY 1/19

- 61. AA2: SITE PLAN / CONTROL (2SP1)
- 62. AA2: TYPICAL SECTION RWY 1/19 (2TY1)
- 63. AA2: TYPICAL SECTION TXY F EAST (2TY2)
- 64. AA2: TYPICAL SECTION TXY L (2TY3)
- 65. AA2: EXISTING CONDITIONS REMOVALS (2EX1)
- 66. AA2: RWY 1/19 PLAN AND PROFILE (2PP1)
- 67. AA2: JOINTING PLAN (2JT1)

# **GREATER ROCKFORD AIRPORT AUTHORITY** ROCKFORD, ILLINOIS


**CONSTRUCTION PLANS FOR** CHICAGO ROCKFORD INTERNATIONAL AIRPORT

## **REHABILITATE RUNWAY 1/19** PHASE 1

## FINAL SUBMITTAL


**ILLINOIS PROJECT: RFD-4083** A.I.P. PROJECT: 3-17-0088-XX

> **APRIL 22, 2011** (JUNE 17, 2011 LETTING)



**LOCATION MAP** 





SITE PLAN



APPROVED BY FRANZ L. OLSON

APRIL 22, 2011

## **DESIGN INFORMATION**

TOWNSHIP: 43 NORTH RANGE: 1 EAST

COUNTY: WINNEBAGO

ALP DATA: APPROACH CAT. / DESIGN GROUP: D5 DESIGN AIRCRAFT: 747-400

(MAXIMUM EQUIPMENT HEIGHT = 25')



CALL J.U.L.I.E BEFORE **EXCAVATING** 1-800-892-0123

Illinois Professional Engineering Practice Act of 1989



Aurora, Illinois Rockford, Illinois St. Louis, Mo.

SUBMITTED BY





Travis A. Strait, P.E.


4/22/11


license expires 11-30-2011


**RO019** Н BASE BID ADD ALT 1 ADD ALT 2 TXY B, TXY F WEST AND RIAT ROAD TXY F EAST, TXY L AND 300' RWY 1/19 SEQ RECORD RECORD QUANTITY RECORD RECORD CHICAGO ROCKFORD (F/S/L) QUANTITY QUANTITY (F/S/L) (F/S/L) QUANTITY (L) INTERNATIONAL AIRPORT G AR108108 1/C #8 5 KV UG CABLE LF 23,230,00 AR108158 1/C #8 5 KV UG CABLE IN UD LF 7,050.00 FRANZ L. OLSON LS ACTING EXECUTIVE DIRECTOR 6,670.00 AR110501 1-WAY CONCRETE ENCASED DUCT LF AR110502 2-WAY CONCRETE ENCASED DUCT LF 115.00 5 AR110554 EXTEND 4-WAY DUCT LF 25.00 7 AR110610 ELECTRICAL HANDHOLE EACH 12.00 AR125415 MITL-BASE MOUNTED EACH 26.00 AR125420 TAXIWAY LIGHT INPAVEMENT EACH 9.00 10 AR125444 TAXIWAY GUIDANCE SIGN, 4 CHARACTER EACH 1.00 CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS AR125515 HIRL, BASE MOUNTED EACH 16.00 11 12 AR125525 HIRL, INPAVEMENT EACH 9.00 F 13 AR125530 RUNWAY CENTERLINE LIGHT EACH 15.00 14 AR125555 THRESHOLD LIGHTS, INPAVEMENT EACH 2.00 15 AR125615 PAPI (L-880 SYSTEM) EACH 2.00 16 AR125902 REMOVE BASE MOUNTED LIGHT EACH 42.00 17 AR125903 REMOVE INPAVEMENT LIGHT EACH 26.00 18 AR125909 REMOVE VASI EACH 2.00 Chicago Rockford 19 AR125942 ADJUST BASE MOUNTED LIGHT EACH 33.00 International Airport 20 AR125943 ADJUST INPAVEMENT LIGHT EACH 67.00 21 AR125947 ADJUST REILS PAIR 1.00 Rockford, Illinois RELOCATE TAXI GUIDANCE SIGN 22 AR125964 EACH 9.00 23 AR150515 FIELD LABORATORY LS 1.00 Ε AR150520 MOBILIZATION 24 LS 1.00 25 AR150540 HAUL ROUTE LS 1.00 Greater Rockford 26 AR152410 UNCLASSIFIED EXCAVATION CY 175.00 2,400.00 Airport Authority 27 SOIL STABILIZATION FABRIC 500.00 SY 1,000.00 28 AR156510 SILT FENCE LF 2,200.00 AR156512 BALES EACH 72.00 29 POROUS GRANULAR EMBANKMENT AR208515 CY 100.00 30 100.00 AIP Proj: 3-17-0088-XX 31 AR209608 CRUSHED AGG. BASE COURSE - 8" SY 500.00 32 AR401610 BITUMINOUS SURFACE COURSE TON 11,535.00 402.00 D IL Proj: RFD-4083 33 AR401630 BITUMINOUS SURFACE TEST SECTION EACH 1.00 34 AR401640 8,335.00 BITUMIONUS PAVEMENT GROOVING SY AR401650 76,670.00 7.460.00 10,880.00 35 BITUMINOUS PAVEMENT MILLING SY 36 AR401910 REMOVE AND REPLACE BIT. PAVEMENT SY 645.00 50.00 37 AR501520 20" PCC PAVEMENT SY 46,500.00 7,250.00 10,600.00 38 AR501530 PCC TEST BATCH EACH 1.00 39 PCC PAVEMENT GROOVING 42,400.00 4,350.00 SY APPROVED AS WORKING PLAN AR602510 BITUMINOUS PRIME COAT GAL 3,717.00 41 AR603510 BITUMINOUS TACK COAT GAL 9,637.00 112,414.20 42 AR620520 PAVEMENT MARKING - WATERBORNE SF 2,595,60 43 AR620525 PAVEMENT MARKING - BLACK BORDER SF 29,293.00 1,182.00 С 44 AR760506 6" DUCTILE IRON WATER MAIN LF 5.00 45 AR760508 8" DUCTILE IRON WATER MAIN LF 430.00 46 AR760800 FIRE HYDRANT EACH 1.00 ADJUST SANITARY MANHOLE EACH 47 AR770945 1.00 ABANDON WATER VALVE 48 AR800812 EACH 49 AR800817 ABANDON WATER MAIN EACH 4.00 REV DATE DESCRIPTION 50 AR800830 CONNECT TO EXISTING WATER MAIN EACH 2.00 PROJECT NAME: 12,200.00 1,000.00 51 SOIL GUARD SY 1,785.00 52 AR800860 ADJUST PAVEMENT SENSOR EACH REHABILITATE 2.00 2-#4 XLP-USE, 1-#10 GND IN 1-1/4" UD 53 AR800864 LF 3,065.00 **RUNWAY 1/19** 54 AR800879 TEMPORARY THRESHOLD - 19 LS 1.00 PHASE 1 В 55 AR800880 **TEMPORARY THRESHOLD - 25** LS 1.00 56 AR800881 RUNWAY 7 PAPI PCU RELOCATION EACH 1.00 57 ABANDON SANITARY SEWER LF 5,780.00 58 AR800883 ABANDON SANITARY MANHOLE EACH 29.00 SUMMARY AR901510 SEEDING ACRE 2.52 0.36 0.21 59 OF QUANTITIES TOPSOILING 60 AR905530 SY 12,200.00 670.00 (QTY1) CMT-RFD CMT-RFD CMT-ARR PROJECT NO.: 10258-03-00/06 DATE: APRIL 22, 2011 Α **SUMMARY OF QUANTITIES** (QTY1) SHEET 2 OF 67 SHEETS























#### 1. APPROVED PROGRESS SCHEDULE:

Н

G

F

Ε

D

С

В

Α

PRIOR TO THE START OF CONSTRUCTION, AN APPROVED PROGRESS SCHEDULE SHALL BE EXECUTED BY THE RESIDENT ENGINEER AND THE CONTRACTOR. THIS SCHEDULE SHALL SHOW START/ STOP DATES OF ALL PHASES, INCLUDING ALL AOA WORK REQUIRING DAYTIME ONLY CLOSURES OF TAXIWAYS AND RUNWAYS. THE APPROVED PROGRESS SCHEDULE SHALL BE DISTRIBUTED TO ALL PARTIES 3 WORKING DAYS PRIOR TO START OF CONSTRUCTION.

#### 2. NOTAM (NOTICE TO AIRMEN) COORDINATION:

THE RESIDENT ENGINEER SHALL COORDINATE NOTAM AND FAA FACILITY COORDINATION WITH AIRPORT / FAA PERSONNEL.

#### 3. CONSTRUCTION SITE ACCESS AND STAGING AREA:

THE CONTRACTOR ACCESS ROAD AND STAGING AREAS SHALL BE AS SHOWN ON THE REFERENCED PLAN. THE CONTRACTOR SHALL MAINTAIN AND REPAIR THE CONSTRUCTION ACCESS ROAD AND STAGING AREA IN ITS ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE CONTRACT. ALTERNATE STAGING AREAS AND ACCESS FOR THIS AREA WILL NOT BE ALLOWED. THIS WORK AREA SHALL BE RESTRICTED FROM ACTIVE AOA AREAS WITH THE BARRICADE/FENCING PERIMETERS SHOWN.

THE ENTRANCE SHALL BE SIGNED ACCORDINGLY AS TO ALLOW ONLY CONSTRUCTION VEHICLE ACCESS AND WILL ONLY BE ACCESSIBLE DURING THE CONTRACTOR'S SCHEDULED WORK DAY. ALL SIGNAGE SHALL CONFORM TO THE CITY OF ROCKFORD AND IDOT CONSTRUCTION STANDARDS FOR VEHICLES ENTERING AND LEAVING THE SITE.

4. CONSTRUCTION EQUIPMENT FLAGGING / BEACON REQUIREMENTS: THE CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS AND HAVE BEACON (FLASHING YELLOW) LIGHTS ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION.

#### 5. GATE SECURITY:

THE GATE SHALL BE MAINTAINED, CLOSED AND LOCKED AS DIRECTED BY THE DEPUTY DIRECTOR OF OPERATIONS. SHOULD THE CONTRACTOR'S OPERATIONS REQUIRE THE GATE TO REMAIN OPEN TO PROVIDE ACCESS TO HAULING OPERATIONS, A COMPETENT GATE GUARD SHALL BE REQUIRED TO CONTROL ACCESS TO THE AIRFIELD. A \$1,000 FINE SHALL BE ASSESSED FOR ANY OCCURRENCE OF AN UNSECURE GATE THAT IS THE CONTRACTOR'S RESPONSIBILITY. AN UNSECURED GATE SHALL BE DEFINED AS ANY GATE THAT IS NOT WITHIN THE SIGHT AND PHYSICAL CONTROL OF THE CONTRACTOR'S GUARD. IN THE EVENT THAT THE GATE MAY NOT BE SECURED, THE CONTRACTOR WILL BE CHARGED FOR AIRPORT PERSONNEL TO REMAIN AT THE GATE UNTIL SECURED.

## 6. CONSTRUCTION OUTSIDE OF BARRICADED AREAS REQUIRING TAXIWAY / RUNWAY CLOSURES:

WORK OUTSIDE THE BARRICADED LINES WITHIN THE AOA AREAS SHOWN SHALL REQUIRE TEMPORARY DAYTIME ONLY CLOSURES OF THE AFFECTED TAXIWAYS OR RUNWAYS. THIS WORK SHALL BE EXPEDITED AND PRIORITIZED TO MINIMIZE CLOSURE TIME OF THE ACTIVE PAVEMENTS. CONSTRUCTION ACTIVITIES WILL NOT BE PERMITTED WITHIN 250' OF CENTERLINE ON ALL ACTIVE RUNWAYS AND WITHIN 160' OF CENTERLINE ON ALL ACTIVE TAXIWAYS. IN ADDITION, THIS WORK WILL REQUIRE ALL CREWS TO SUPPLY AND HAVE IN THEIR POSSESSION AT ALL TIMES AT LEAST ONE AIRPORT RADIO TO COMMUNICATE DIRECTLY WITH THE ATCT (AIR TRAFFIC CONTROL TOWER). THE OPERATOR OF THE AIRPORT RADIO SHALL BE FAMILIAR WITH AIRPORT RADIO PROCEDURES AND BE TUNED INTO THE GROUND CONTROL FREQUENCY AT ALL TIMES.

#### 7. UNAUTHORIZED ACCESS TO AIRFIELD:

THE CONTRACTOR SHALL RESTRICT ALL CONSTRUCTION ACTIVITIES TO THE CONSTRUCTION AREA DETAILED IN THE PHASING PLAN. ANY UNAUTHORIZED MOVEMENTS, PEDESTRIAN OR VEHICULAR, BEYOND THE CONSTRUCTION LIMITS SHOWN SHALL BE CONSIDERED AN AIRFIELD INCURSION. AIRFIELD INCURSIONS, AT THE DISCRETION OF THE AIRPORT DEPUTY DIRECTOR OF OPERATIONS, MAY BE FINED \$10,000.00 PER INCIDENT. INCURSION FINES WILL BE ASSESSED IMMEDIATELY AND TAKEN FROM MONIES DUE THE CONTRACTOR ON THE NEXT CONSTRUCTION PAYMENT.

#### CRITICAL POINTS

POINT NO.		LONGITUDE	ELEV.*	POINT NO.	- LATITUDE	LONGITUDE	ELEV.*
А	42° 12' 01.06"	89° 05' 25.21"	758.50	F	42° 12' 08.41"	89° 05' 16.38"	758.50
В	42° 11' 52.15"	89° 05' 22.49"	758.00	G	42° 12' 08.34"	89° 05' 13.33"	759.00
С	42° 11' 59.20"	89° 05' 21.60"	759.00	Н	42° 12' 21.03"	89° 05' 22.80"	759.00
D	42° 12' 03.80"	89° 05' 17.16"	760.50	ı	42° 12' 20.47"	89° 05' 14.88"	760.00
Е	42° 12' 05.55"	89° 05' 24.78"	756.50				

\* ELEVATION INCLUDES 25' ANTICIPATED EQUIPMENT HEIGHT

### ANTICIPATED PROJECT START DATE:

APPROXIMATE SCHEDULE SHOWN ASSUMING THE AVAILABILITY OF PROJECT FUNDING. THERE IS NO GUARANTEE THAT THIS PROJECT WILL BE AWARDED TO ACCOMMODATE A 2011 SCHEDULE. IF THE FUNDING IS DELAYED, IT IS POSSIBLE THAT THE PROJECT WILL NOT BEGIN UNTIL THE 2012 CONSTRUCTION SEASON. PRIOR TO THE START OF CONSTRUCTION, THE SCHEDULE WILL BE REVISED ACCORDINGLY.

PHASE	WORK AREA	ALLOWABLE WORK PERIODS	AIRPORT OPERATIONAL RESTRICTIONS	ANTICIPATED SCHEDULE	
1	RUNWAY 1/19 STA. 71+60 TO 91+15, TAXIWAY F EAST AND WEST CONNECTOR , RUNWAY 7/25 (PHASE 1 EXPEDITED) IF AWARDED ADDITIVE ALTERNATE 1 AND 2 APPLICABLE AREAS	7:00 A.M 7:00 P.M.  MAINTAIN AIRFIELD ACCESS TO T-HANGAR TENANTS DUE CONSTRUCTION VIA TAXIWAY B, TAXIWAY L AND TAXIWA NORTH OF TAXIWAY L  TAXIWAY CLOSURES INCLUDE TAXIWAY F EAST OF TAXIWAY B TO CONNECTOR F. TEMPORARY THRESHOLD RUNWAY 19		JULY 29 - OCTOBER 14, 2011 (78 CALENDAR DAYS)	
1 (EXPEDITED)	AREA WITHIN RUNWAY 7/25 RSA	7:00 A.M 7:00 P.M.	MAINTAIN AIRFIELD ACCESS TO T-HANGAR TENANTS DURING CONSTRUCTION VIA TAXIWAY B, TAXIWAY L AND TAXIWAY J NORTH OF TAXIWAY L.  TAXIWAY CLOSURES INCLUDE TAXIWAY F EAST OF TAXIWAY B, TAXIWAY J SOUTH OF TAXIWAY L.  TEMPORARY THRESHOLD RUNWAY 25	AUGUST 8 -SEPTEMBER 4, 2011 (28 CALENDAR DAYS)	
2	RUNWAY 1/19 STA. 91+15 TO 98+15, TAXIWAY B WEST CONNECTOR TAXIWAY L EAST CONNECTOR. IF AWARDED ADDITIVE ALTERNATE 1 AND 2 APPLICABLE AREAS	7:00 A.M 7:00 P.M.	MAINTAIN AIRFIELD ACCESS TO T-HANGAR TENANTS DURING CONSTRUCTION VIA TAXIWAY F AND TAXIWAY J.  TAXIWAY CLOSURES INCLUDE TAXIWAY B NORTH OF TAXIWAY F AND TAXIWAY L. TEMPORARY THRESHOLD RUNWAY 19	OCTOBER 15 - NOVEMBER 11, 2011 (28 CALENDAR DAYS)	
IF ADD ALT	IF ADD ALT #1 IS AWARDED. 14 ADDITIONAL CALENDAR WILL BE AWARDED (TOTAL PROJECT CALENDAR DAYS = 120 DAYS).				

IF ADD ALT #1 AND #2 ARE AWARDED, 31 ADDITIONAL CALENDAR DAYS WILL BE AWARDED (TOTAL PROJECT CALENDAR DAYS = 137 DAYS)

PHASING PLAN GENERAL NOTES:

1. SUGGESTED SEQUENCE OF CONSTRUCTION:

## PHASING PLAN GENERAL NOTES:

THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE NEW IMPROVEMENTS WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED WITH THE APPROVAL OF THE RESIDENT ENGINEER. HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT DEPUTY DIRECTOR OF OPERATIONS.

#### 2. STAGING AREA RESTORATION:

ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A STAGING AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT DEPUTY DIRECTOR OF OPERATIONS. THE COST OF MAINTAINING, REPAIRING SEEDING /MULCHING OR CONSTRUCTING THESE PAVEMENTS / AREAS SHALL BE INCIDENTAL TO THE CONTRACT.

#### 3. HAUL ROUTE / HAUL ROUTE RESTORATION:

THE CONTRACTOR SHALL CONSTRUCT THE HAUL ROUTE AS SHOWN IN THESE PLANS AND SHALL BE PAID FOR ONCE AS AR150540 - HAUL ROUTE. ANY OTHER HAUL ROUTE(S) SHALL BE INCIDENTAL TO AR150540. THE COST OF MAINTAINING THE HAUL ROUTE(S) SHALL BE INCIDENTAL TO AR150540. ALL HAUL ROUTE(S) INCLUDING EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT DEPUTY DIRECTOR OF OPERATIONS. THE COST OF MAINTAINING, REPAIRING SEEDING /MULCHING OR CONSTRUCTING THESE HAUL ROUTE(S) SHALL BE INCIDENTAL TO AR150540 - HAUL ROUTE.

#### 4. AIRPORT APPROVAL OF PHASING:

THE RESIDENT ENGINEER AND AIRPORT DEPUTY DIRECTOR OF OPERATIONS OR HIS DESIGNATED REPRESENTATIVE SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING SEQUENCE AS IT RELATES TO PEDESTRIAN, VEHICULAR AND AIRCRAFT OPERATIONS. AIRCRAFT OPERATIONS HAVE THE RIGHT-OF-WAY ON THE AIRFIELD. VEHICULAR TRAFFIC AND CONTRACTOR ACTIVITIES SHALL YIELD TO AIRCRAFT OPERATIONS. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE EQUIPMENT AT ANY TIME TO ALLOW AN AIRCRAFT TO PASS, THE CONTRACTOR SHALL DO SO IMMEDIATELY AT NO EXTRA COST TO THE OWNER.

#### 5. AIRFIELD PAVEMENT / SITE DEBRIS REMOVAL:

THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE EXISTING RUNWAYS AND TAXIWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE RESIDENT ENGINEER. SHOULD THE CONTRACTOR TRACK ANY DEBRIS ONTO EXISTING PAVEMENTS, THIS DEBRIS SHALL BE REMOVED IMMEDIATELY WITH A PICK UP SWEEPER. A PICK UP SWEEPER SHALL BE REQUIRED TO BE ON SITE AND OPERATE DURING ALL CONSTRUCTION OPERATION WORKING HOURS. THE CONTRACTOR SHALL PROVIDE WASTE RECEPTACLES THROUGHOUT THE WORK ZONE AND MAINTAIN SANITARY FACILITIES FOR EMPLOYEES TO USE. FACILITIES WITHIN THE HANGARS/AIRPORT BUILDINGS SHALL NOT BE USED.

(NOTES CONTINUED ON PHASING PLAN DETAILS - PPD1)

PHASING PLAN NOTES (PPN1)

RO019

R F D

CHICAGO ROCKFORD
INTERNATIONAL AIRPORT

FRANZ L. OLSON ACTING EXECUTIVE DIRECTOR



CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS

Chicago Rockford International Airport Rockford, Illinois

Greater Rockford Airport Authority

AIP Proj: 3-17-0088-XX IL Proj: RFD-4083



REHABILITATE RUNWAY 1/19 PHASE 1

SHEET TITLE:

DESIGNED:

## PHASING PLAN NOTES (PPN1)

CHECKED:

CMT-RFD CMT-RFD CMT-ARR

PROJECT NO.: 10258-03-00/06

A DATE: APRIL 22, 2011

SHEET NO. REVISION

SHEET 12 OF 67 SHEETS

7 6 5 4 3 2

PHASING PLAN GENERAL NOTES (CONT'D):

(NOTES CONTINUED ON PHASING PLAN NOTES - PPN1) 6. PROJECT LIGHTING OUTSIDE OF DAYLIGHT HOURS:

G

F

Ε

D

В

Α

LIGHTS MENTIONED ABOVE. LIGHTING SHALL BE AS APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY.

С

OF THE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS

BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY/OWNER OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING

WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS

SHALL CONSIST OF MOVEABLE POLE MOUNTED FLOODLIGHTS AND/OR

SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA.

VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER

ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT

COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL

BE COMPLETED BEFORE CONSTRUCTION IS STARTED. SEE SECTION 50-17

SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL AREA LIGHTING TO

CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER AND THE ENGINEER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE ENGINEER.

SHOULD A UTILITY COMPANY OR GOVERNMENT AGENCY BE UNABLE TO LOCATE FACILITIES, THE CONTRACTOR SHALL LOCATE THESE FACILITIES. PAYMENT FOR THIS LOCATION SHALL BE INCIDENTAL TO THE IMPROVEMENTS REQUIRING THE LOCATIONS.

PAYMENT FOR ALL AIRSIDE AND ROADWAY TRAFFIC CONTROL INCLUDING.

#### 8. TRAFFIC CONTROL PAYMENT:

7. EXISTING UTILITY COORDINATION:

BUT NOT LIMITED TO, TEMPORARY CONSTRUCTION FENCING, BARRICADES, SIGNING, AIR OPERATIONS AREA (A.O.A.) LATH AND RIBBON, ETC. SHALL BE PAID FOR AS AR800825 - TRAFFIC CONTROL AND PROTECTION. TYPE 2 BARRICADES WITH STEADY BURN RED LIGHTS SHALL BE PLACED ON 15' CENTERS AND HAVE ORANGE CONSTRUCTION FENCING BETWEEN EACH SET OF BARRICADES. TYPE 2 BARRICADES SHALL BE PLACED AS SHOWN ON THIS PLAN AND AS DIRECTED BY THE ENGINEER FOR WORK ADJACENT TO THE EXPEDITED WORK AREA. LOW PROFILE BARRICADES SHALL BE USED ON ALL PAVEMENT AREAS OR AS DIRECTED BY THE ENGINEER. WHEN NOT IN USE, THESE BARRICADES SHALL BE STORED AT THE CONTRACTOR'S STAGING AREA OR OFF SITE. ACCESS TO THE ACTIVE RUNWAY AND TAXIWAY PAVEMENTS (TOWER CONTROLLED AREAS) SHALL BE SIGNED WITH STOP SIGNS MOUNTED ON THE CLOSEST BARRICADES (2 EACH, RIGHT AND LEFT) AT THE ENTRANCE. IN ADDITION TO THE STOP SIGNS, WARNING SIGNS (2 EACH, RIGHT AND LEFT) SHALL BE MOUNTED. WARNING SIGNS SHALL STATE "TOWER CONTROL AREA / UNAUTHORIZED ACCESS SUBJECT TO FINE." ALL TYPE II AND TYPE III BARRICADES SHALL CONFORM TO IDOT STANDARD DETAIL 702001. ALL PAVEMENT DROP-OFFS GREATER THAN 24" REQUIRE TYPE II BARRICADES WITH EXTENDED LEGS. FOR AIRSIDE BARRICADE PLACEMENT, SEE SEQUENCE OF CONSTRUCTION SHEETS. FOR ROADWAY PROTECTION, SEE TEMPORARY TRAFFIC CONTROL PLAN AND GENERAL NOTES AND DETAILS SHEETS.

#### 9. DRIVERS TRAINING AND BADGING:

DRIVER'S TRAINING AND BADGING SHALL BE REQUIRED FOR THE CONTRACTOR'S SUPERVISORY PERSONNEL, OTHER CONSTRUCTION PERSONNEL CAN BE WITHIN THE AIRFIELD LIMITS PROVIDED THAT THEY ARE UNDER ESCORT AND IN THE PRESENCE OF AN AUTHORIZED SUPERVISOR. THE DRIVER'S TRAINING AND BADGING OF THE INITIAL SUPERVISORY PERSONNEL MUST BE COMPLETED PRIOR TO THE START OF CONSTRUCTION.

#### 10. DUST CONTROL REQUIREMENTS:

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE DUST CONTROL AT ALL TIMES DURING THE PROJECT DURATION. A WATER TRUCK SHALL BE REQUIRED TO BE ON SITE DURING ALL CONSTRUCTION OPERATION WORKING HOURS, UNLESS WAIVED BY THE DEPUTY DIRECTOR OF OPERATIONS. PAYMENT FOR DUST CONTROL SHALL BE INCIDENTAL TO THE CONTRACT.

#### 11. OPERATIONAL SAFETY ON AIRPORT DURING CONSTRUCTION (AC 150/5370-2E)

ALL WORK SHALL CONFORM TO AC 150/5370-2E OPERATIONAL SAFETY ON AIRPORT DURING CONSTRUCTION. THIS AC IS AVAILABLE AT www.faa.gov/arp/pdf/5370-2e.pdf.

#### 12. STAGING AREA:

THE CONTRACTOR'S MATERIAL AND EQUIPMENT, WHEN NOT IN USE, SHALL BE STORED IN THE CONTRACTOR'S STAGING AREA. ALL DELIVERIES, EQUIPMENT REFUELING, EQUIPMENT MAINTENANCE AND EQUIPMENT TRANSFERS SHALL TAKE PLACE WITHIN THE CONTRACTOR'S STAGING AREA.

#### 13. AIRFIELD LIGHTING COORDINATION:

THE CONTRACTOR SHALL BE REQUIRED TO ESTABLISH A COORDINATION PLAN WITH THE AIRPORT DEPUTY DIRECTOR OF OPERATIONS OR HIS DESIGNATED REPRESENTATIVE, REGARDING DE-ENERGIZING AND ENERGIZING OF THE AIRFIELD LIGHTING CIRCUITS AT THE START AND END OF EACH CONSTRUCTION DAY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL AIRPORT OWNED UTILITIES AND SHALL BE DONE SO AT NO EXTRA COST TO THE CONTRACT.


#### 14. WEEKLY COORDINATION MEETINGS:

WEEKLY COORDINATION MEETINGS SHALL BE REQUIRED TO DISCUSS PROJECT PROGRESS. AS A MINIMUM, PROJECT SCHEDULE AND GATE VISITOR LOGS SHALL BE DISCUSSED. REPRESENTATION BY THE PRIME CONTRACTOR IS MANDATORY.

#### 15. TEMPORARY CABLES:

ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER AIRPORT ELECTRICAL CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT ENGINEER AND AIRPORT FOR ALL PHASES. ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED INCIDENTAL TO CONTRACT.

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE SPECIAL PROVISIONS SECTION 30-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS. IT IS ANTICIPATED THE FOLLOWING PROJECTS MAY BE UNDER CONSTRUCTION CONCURRENTLY WITH THIS PROJECT: • REHABILITATE TAXIWAY J AND L



NOT TO SCALE

1. CLOSED RUNWAY MARKERS SHALL BE YELLOW.

2. MARKERS SHALL BE A MATERIAL APPROVED BY THE ENGINEER AND THE AIRPORT.

3. CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE CONSTRUCTION.

4. MARKERS SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS AS SHOWN.

5. COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

6. DURING VARIOUS PHASES OF WORK, IT WILL BE NECESSARY TO CLOSE RUNWAYS TO AIR TRAFFIC ON A TEMPORARY BASIS AS COORDINATED WITH THE AIRPORT AND TOWER PERSONNEL. THE CONTRACTOR SHALL MARK THE RUNWAYS TO BE CLOSED BY PLACING A YELLOW CROSS AT THE LOCATION AND DIMENSIONS DETAILED ON THIS SHEET OR AS DIRECTED BY THE ENGINEER AND AIRPORT. THE CROSSES ARE SHOWN ON THE RESPECTIVE RUNWAYS ACCORDING TO THE VARIOUS PHASES OF WORK AS DELINEATED IN THE SUGGESTED SEQUENCE OF CONSTRUCTION.



MULTI-BARRIER AR-2 OR APPROVED EQUAL (SEE NOTE 5) 6" TO 12" WIDE SAFETY ORANGE

**LOW PROFILE BARRICADES** 

- 1 . LOW PROFILE BARRICADES SHALL BE PLACED 15' ON CENTER AT THE EDGE OF ALL ACTIVE TAXIWAY PAVEMENTS WHERE THERE IS AN EDGE DROP-OFF GREATER THAN 3" AT THE EDGE OF THE TAXIWAY. BARRICADES SHALL BE WEIGHTED WITH A MINIMUM OF 6 SAND BAGS TO PREVENT THEM FROM BEING BLOWN OVER.
- 2. LIGHTS SHALL BE BATTERY OPERATED. LENS SHALL BE RED AND BE ABLE TO
- 3. FACING OF BARRICADE SHALL BE COVERED WITH REFLECTIVE TAPE OR PAINT.
- 4. BARRICADES TO BE PLACED WITH A MAXIMUM OF 15' SPACING BETWEEN ENDS OF BARRICADES ALONG OPERATIONAL TAXIWAY PAVEMENT ADJACENT TO CONSTRUCTION AS DIRECTED BY THE RESIDENT ENGINEER.
- 5. ALTERNATE LENSES SO THAT EVERY OTHER LENS IS ROTATED 90C
- 6. BARRICADES SHALL BE OF LOW MASS, EASILY COLLAPSIBLE UPON CONTACT WITH AN AIRCRAFT OR ANY OF IT'S COMPONENTS. AND WEIGHTED OR STURDILY ATTACHED TO THE SURFACE. IF AFFIXED TO THE SURFACE, THE BARRICADE MUST BE FRANGIBLE AT GRADE LEVEL OR AS LOW POSSIBLE, BUT NOT TO EXCEED 3 INCHES ABOVE THE GROUND
- 7. A MINIMUM 0F 60 LOW PROFILE BARRICADES SHALL BE ON SITE AT ALL TIMES. ALL COST ASSOCIATED WITH THE LOW PROFILE BARRICADES SHALE BE CONSIDERED INCIDENTAL TO THE CONTRACT.

PHASING PLAN DETAILS (PPD1)

CHICAGO ROCKFORD INTERNATIONAL AIRPOR

FRANZ L. OLSON ACTING EXECUTIVE DIRECTOR



Chicago Rockford

International Airport

Rockford, Illinois

**Greater Rockford** Airport Authority

AIP Proj: 3-17-0088-XX IL Proj: RFD-4083




**REHABILITATE** RUNWAY 1/19 PHASE 1

SHEET TITLE:

PHASING PLAN **DETAILS (PPD1)** 


CHECKED: CMT-RFD CMT-RFD CMT-ARR 10258-03-00/06 PROJECT NO.: DATE: APRIL 22, 2011

SHEET 13 OF 67 SHEETS



8 7 6 5 4 3 2 1

## RUNWAY 1/19 TEMPORARY THRESHOLD RELOCATION



Н

G

F

Ε

D

С

В


Α

TEMPORARY PAVEMENT MARKING (PAINT)	COLOR	TOTAL AREA
1 - THRESHOLD BAR (10'X150')	WHITE	1,500 S.F.
2 - NUMERALS (1,9)	WHITE	1,018 S.F.
5 - CHEVRONS (3' WIDE)	YELLOW	1,061 S.F.
6" BLACK BORDER (ALL MARKINGS)	BLACK	2,379 S.F.
	TOTAL AREA	= 5,958 S.F.
PAVEMENT MARKING REMOVALS	EXIST. DIMENSION	TOTAL AREA
12 - THRESHOLD MARKERS	5.75' X 150'	10,350 S.F.
18 - TOUCHDOWN ZONE MARKERS	6' X 75'	8,100 S.F.
2 - AIMING POINT MARKERS	30' X 150'	9,000 S.F.
17 - CENTERLINE STRIPES	3' X 120'	6,120 S.F.
2 - RUNWAY EDGE STRIPES	3' X 3,650'	21,900 S.F.
2 - NUMERALS (1,9)	(SEE DETAIL)	1,061 S.F.
6" BLACK BORDER (ALL MARKINGS)	6" BORDER	11,425 S.F.
	TOTAL AREA =	= 67,956 S.F.

(INCIDENTAL TO TEMPORARY RELOCATED THRESHOLD)

## RUNWAY 7/25 TEMPORARY THRESHOLD RELOCATION





TEMPORARY PAVEMENT MARKING (PAINT)	COLOR	TOTAL AREA
1 - THRESHOLD BAR (10'X150')	WHITE	1,500 S.F.
2 - NUMERALS (7,25)	WHITE	1,402 S.F.
5 - CHEVRONS (3' WIDE)	YELLOW	1,061 S.F.
6" BLACK BORDER (ALL MARKINGS)	BLACK	2,494 S.F.
	TOTAL AREA	= 6,457 S.F.
PAVEMENT MARKING REMOVALS	EXIST. DIMENSION	TOTAL AREA
12 - THRESHOLD MARKERS	5.75' X 150'	10,350 S.F.
18 - TOUCHDOWN ZONE MARKERS	6' X 75'	8,100 S.F.
2 - AIMING POINT MARKERS	30' X 150'	9,000 S.F.
11 - CENTERLINE STRIPES	3' X 120'	3,960 S.F.
2 - RUNWAY EDGE STRIPES	3' X 2400'	14,400 S.F.
2 - NUMERALS (2,5)	(SEE DETAIL)	1,402 S.F.
6" BLACK BORDER (ALL MARKINGS)	6" BORDER	9,040 S.F.
	TOTAL AREA =	= 56,252 S.F.

(INCIDENTAL TO TEMPORARY RELOCATED THRESHOLD)

### **GENERAL NOTES**


1. THE TEMPORARY RELOCATED THRESHOLD IS TO BE CONSTRUCTED BY THE CONTRACTOR. THE CONTRACTOR SHALL TAKE CAUTION AS TO NOT DISTURB THIS SYSTEM OR ANY OTHER EXISTING UTILITIES. SHOULD ANY UTILITY BE DISTURBED, THE CONTRACTOR SHALL REPAIR/CORRECT THE DISRUPTION IMMEDIATELY. THE CONTRACTOR IS RESPONSIBLE TO LOCATE AND PROTECT ALL EXISTING UTILITIES.

2. REMOVE YELLOW FILTERS FROM THE RUNWAY EDGE LIGHTS WITHIN THE DISPLACED PORTIONS OF RUNWAY 1/19 AND RUNWAY 7/25. INSTALL YELLOW FILTER IN EDGE LIGHTS 2000 FEET FROM TEMPORARY THRESHOLD. COST INCIDENTAL TO TEMPORARY RELOCATED THRESHOLD.

3. REMOVE RED RUNWAY CENTERLINE LIGHT FIXTURES (1,000' AT 50' CENTERS AND 2,000' AT 100' CENTERS). INSTALL RED CENTERLINE LIGHT FIXTURE CONFIGURATION 3,000' FROM RELOCATED THRESHOLDS.

4. TEMPORARY PAVEMENT MARKING AND MARKING REMOVALS SHALL BE CONSIDERED INCIDENTAL TO TEMPORARY RELOCATED THRESHOLD.

5. ALL MARKINGS SHALL CONFORM TO AC150/5340-1 (LATEST EDITION) STANDARDS FOR AIRPORT MARKINGS.



## TEMPORARY RELOCATED THRESHOLD ELECTRICAL WORK TO BE COMPLETED

- RUNWAY DISTANCE REMAINING SIGNS SHALL BE OBSCURED
- TAKE EXISTING RUNWAY EDGE LIGHTS OUT OF SERVICE WITHIN THE CLOSED PORTION OF THE RUNWAYS
- CHANGE FILTERS/FIXTURES IN EXISTING EDGE LIGHTS FOR 2000'
- CHANGE FIXTURES IN EXISTING CTL .LIGHTS FOR '3,000
- RELOCATE RED/GREEN SPLIT LENS THRESHOLD LIGHTS AND TRANSFORMERS AND PROVIDE STAKES
- CONNECT TEMPORARY THRESHOLD LIGHTS TO EXISTING CIRCUIT
- RELOCATE REILS TO TEMPORARY THRESHOLD
- INSTALL TEMPORARY JUMPERS FOR RUNWAY AND TAXIWAY CIRCUITS AS APPROVED BY THE RESIDENT ENGINEER
- \*\* COST OF ABOVE WORK AND REPLACEMENT TO ORIGINAL CONDITIONS SHALL BE CONSIDERED INCIDENTAL TO TEMPORARY RELOCATED THRESHOLD

TEMPORARY RELOCATED THRESHOLD DETAILS (TTD1)

R F D

CHICAGO ROCKFORD
INTERNATIONAL AIRPORT

FRANZ L. OLSON ACTING EXECUTIVE DIRECTOR



Chicago Rockford International Airport Rockford, Illinois

Greater Rockford Airport Authority

AIP Proj: 3-17-0088-XX IL Proj: RFD-4083



REHABILITATE RUNWAY 1/19 PHASE 1

# TEMPORARY RELOCATED THRESHOLD DETAILS

(TTD1)

DATE: APRIL 22, 2011

SHEET NO. 15


SHEET 15 OF 67 SHEETS

MOUNTING DETAILS

TEMPORARY THRESHOLD LIGHT

NOT TO SCALE

7 | 6 | 5 | 4 | 3 | 2 |



THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

#### SITE DESCRIPTION

Η

G

F

Ε

D

C

В

Α

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN-

THIS PROJECT CONSISTS OF REHABILITATING RUNWAYS, TAXIWAYS, AND CONSTRUCTING A RIAT ROAD AT THE CHICAGO ROCKFORD INTERNATIONAL AIRPORT. THE PROJECT INCLUDES GRADING, EXCAVATION, FILL, TOPSOIL PLACEMENT, PAVEMENT CONSTRUCTION, ELECTRICAL, LANDSCAPING AND OTHER MISCELLANEOUS CONSTRUCTION WORK

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS EXCAVATION AND GRADING:

- 1. PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL SUCH AS PERIMETER SILT FENCE AND INLET PROTECTION.
- 2. EXCAVATION AND EMBANKMENT WILL BE COMPLETED WITHIN THE PROJECT LIMITS.
- 3. PAVEMENT CONSTRUCTION.
- 4. FINAL GRADING AND OTHER MISCELLANEOUS ITEMS.
- 5. PLACEMENT OF PERMANENT EROSION CONTROL, SUCH AS SEEDING AND MULCHING.

#### AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 40.0 ACRES OF WHICH 6.0 ACRES WILL BE DISTURBED BY EXCAVATION, GRADING AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- 1. INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- 2. PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION

THE CONSTRUCTION SITE DRAINS INTO THE KISHWAUKEE RIVER VIA OVERLAND FLOW AND THROUGH A STORM SEWER SYSTEM

#### CONTROLS - EROSION CONTROLS AND SEDIMENT CONTROL

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION

THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE SEEDING AND MULCHING AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.

AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, INLET PROTECTION AND PERIMETER SILT FENCE SHALL BE INSTALLED AS CALLED OUT IN THE PLANS OR AS DIRECTED BY THE ENGINEER.

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES

#### DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED **ACTIVITIES** 

- 1. WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL
- 2. EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTORS EXPENSE, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.
- 3. AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:

A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON

- B. CONSTRUCT DITCHES AND PROVIDE TEMPORARY EROSION CONTROL SYSTEMS.
- C. BUILD NECESSARY EMBANKMENT AT CULVERT/STORM SEWER LOCATIONS AND THEN EXCAVATE AND PLACE PIPE.
- D. EXCAVATED AREAS AND EMBANKMENT AREAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S COST, IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS.

4 CONSTRUCTION FOLIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE

WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.

- 5. THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT DAILY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2 INCH OR GREATER OR EQUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD.
- 6. SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR UNCLASSIFIED EXCAVATION AND **EROSION CONTROL ITEMS.**
- 7. THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.


#### DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND **ESTABLISHED** 

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

#### MAINTENANCE AFTER CONSTRUCTION

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.



CONCRETE WASHOUT

NOT TO SCALE

- NOTES:

  1. CONTRACTOR SHALL DETERMINE LOCATION AND SIZE OF WASHOUT.

  2. WASHOUT SIZE AND LOCATION SHALL BE APPROVED BY THE ENGINEER.

  3. SANDBAGS SHALL BE INSTALLED TO ANCHOR THE LINING. THE NUMBER OF SANDBAGS SHALL BE DETERMINED BY THE CONTRACTOR. THE CONTRACTOR SHALL ADD SANDBAGS SO AS TO MAINTAIN ANCHORING OF THE LINING.

  4. A CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 20 FEET OF THE TEMPORARY CONCRETE WASHOUT FACILITY. AT A MINIMUM, THE SIGN SHALL READ "CONCRETE WASHOUT" IN 6" TALL LETTERS.

BELOW GROUND TEMPORARY WASHOUT

- WASHOUT" IN 6" TALL LETTERS.
  THE TEMPORARY WASHOUT FACILITY SHALL BE SURROUNDED BY SILT FENCE ON ALL
- INSPECTION SHALL OCCUR ONCE PER WEEK AND DAILY DURING CONCRETE OPERATIONS. REPAIR/REPLACEMENT OF THE FACILITY SHALL BE MADE SUCH THAT CONCRETE WASTE IS CONTAINED.
- CONTAINED.

  MEDIA SHALL BE REMOVED AND DISPOSED OF AT A LEGAL OFF-SITE LOCATION WHEN THE FACILITY HAS REACHED 50% CAPACITY.

  UPON COMPLETION OF CONCRETE OPERATIONS, THE CONCRETE WASHOUT AND ALL MATERIALS CONTAINED WITHIN SHALL BE DISPOSED OF AT A LEGAL OFF-SITE LOCATION. COST INCIDENTAL TO ITEM AR501515.

NOTES:
1. CONTRACTOR SHALL DETERMINE LOCATION AND SIZE OF WASHOUT.
2. WASHOUT SIZE AND LOCATION SHALL BE APPROVED BY THE ENGINEER.
3. A CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 20 FEET OF THE TEMPORARY AT A MINIMUM. THE SIGN SHALL READ "CONCRETE"

WASHOUT IN 6" TALL LETTERS.
INSPECTION SHALL OCCUR ONCE PER WEEK AND DAILY DURING CONCRETE OPERATIONS.
REPAIR/REPLACEMENT OF THE FACILITY SHALL BE MADE SUCH THAT CONCRETE WASTE IS

**SECTION** 

ABOVE GROUND TEMPORARY WASHOUT

- CONTAINED.

  S. MEDIA SHALL BE REMOVED AND DISPOSED OF AT A LEGAL OFF-SITE LOCATION WHEN THE FACILITY HAS REACHED 50% CAPACITY.

  6. UPON COMPLETION OF CONCRETE OPERATIONS, THE CONCRETE WASHOUT AND ALL MATERIALS CONTAINED WITHIN SHALL BE DISPOSED OF AT A LEGAL OFF-SITE LOCATION.

STORMWATER POLLUTION PREVENTION PLAN NOTES (SWN1)

CHICAGO ROCKFORD INTERNATIONAL AIRPORT

FRANZ L. OLSON ACTING EXECUTIVE DIRECTOR



CRAWFORD, MURPHY & TILLY, INC. CONSULTING ENGINEERS

Chicago Rockford International Airport Rockford, Illinois

**Greater Rockford** Airport Authority

AIP Proj: 3-17-0088-XX IL Proj: RFD-4083



REHABILITATE RUNWAY 1/19 PHASE 1

STORMWATER POLLUTION PREVENTION

PLAN NOTES (SWN1) DESIGNED: DRAWN: CMT-RFD CMT-RFD CMT-ARR

REVISION


PROJECT NO.: 10258-03-00/06


DATE: APRIL 22, 2011


SHEET 17 OF 67 SHEETS


В


6
























































8 LEGEND **ELECTRICAL NOTES: RO019** NEW LIGHTING CIRCUIT - 1/C#8, 5KV L-824 ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER AIRPORT ELECTRICAL \_\_E TYPE C IN CONCRETE ENCASED 2" PVC DUCT CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT. ENGINEER AND AIRPORT FOR ALL PHASES, ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED NEW LIGHTING CIRCUIT - 1/C#8, 5KV L-824 PAVEMENT MARKING NOTES INCIDENTAL TO CONTRACT. TYPE C IN EXISTING DUCT NEW TAXIWAY CIRCUIT - 1/C#8, 5KV L-824 AT ANY LOCATION WHERE THE PROPOSED DUCT OR CABLE ROUTE CROSSES AN EXISTING UTILITY, THE CONTRACTOR SEE DETAILS ON SHEETS MRD 1-2. TYPE C IN 3/4" UNIT DUCT SHALL HAND DIG AND LOCATE THE EXISTING UTILITY PRIOR TO TRENCHING. COST OF LOCATING ALL EXISTING UTILITIES SHALL BE INCIDENTAL TO THE CONTRACT. ALL RUNWAY MARKINGS ARE WHITE WITH A 6" 2. **EXISTING CIRCUITS** BLACK BORDER. THE LOCATION OF EXISTING UTILITIES ARE APPROXIMATE. THE CONTRACTOR SHALL OPEN THE ENTIRE TRENCH NEW PAVEMENT MARKING BETWEEN MANHOLES BEFORE ANY CONDUIT IS LAID TO ASCERTAIN THE EXISTENCE AND POSITION OF ANY OBSTRUCTIONS. 3. ALL TAXIWAY MARKINGS ARE YELLOW WITH A 6" BLACK BORDER. **EXISTING PAVEMENT MARKING** CONTRACTOR SHALL COORDINATE THE LOCATION OF THE EXISTING AND PROPOSED UTILITIES PRIOR TO INSTALLATION OF THE PROPOSED UNIT DUCTS. CONDUITS AND DUCT BANKS, ANY DAMAGES TO EXISTING UTILITIES SHALL BE REPAIRED 4. THE PAVEMENT SURFACE SHALL BE CLEAN AND NEW BASE MOUNTED MEDIUM INTENSITY IMMEDIATELY AT THE CONTRACTOR'S EXPENSE. DRY PRIOR TO MARKING. **TAXIWAY LIGHT** ADJUST EXISTING BASE MOUNTED MEDIUM CONTRACTOR SHALL CONNECT EXISTING CABLE TO PROPOSED CABLE IN SIGN/LIGHT/MANHOLE/HANDHOLE. COST OF WHEN YELLOW TAXIWAY STRIPING CROSSES INTENSITY TAXIWAY LIGHT CONNECTION INCIDENTAL TO CABLE. ANY WHITE RUNWAY STRIPING, THE TAXIWAY STRIPE SHALL BE GAPPED 6" EACH SIDE 00 EXISTING ELEVATED RUNWAY GUARD LIGHT ALL NEW CABLE UNDER EXISTING PAVEMENT TO REMAIN SHALL BE INSTALLED WITHIN EXISTING CONDUITS. EXISTING OF RUNWAY STRIPE. EXCEPT RUNWAY/RUNWAY CABLES SHALL BE REMOVED. COST OF REMOVAL SHALL BE INCIDENTAL TO NEW CABLE. HOLDING. NEW ELECTRICAL HANDHOLE CONTRACTOR SHALL CORE HOLE AND INSTALL BUSHING IN EXISTING LIGHT CAN AND CONNECT NEW 2" PVC DUCT 6. CURING COMPOUND ON CONCRETE EXISTING ELECTRICAL HANDHOLE (INCIDENTAL TO ONE WAY CONCRETE ENCASED DUCT). PAVEMENTS SHALL BE REMOVED BY WATER NEW CONDUIT/DUCT EXTENSION BLASTING OR OTHER METHODS APPROVED Z = ZIT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY THE LOCATION OF EXISTING UTILITIES. DAMAGE TO EXISTING BY THE ENGINEER PRIOR TO MARKING. EXISTING CONDUIT/DUCT UTILITIES SHALL BE REPAIRED IMMEDIATELY AT CONTRACTOR'S EXPENSE. ALL PROPOSED MARKING MAY NOT BE CALLED NEW AIRFIELD GUIDANCE LED SIGN THE ROUTING OF THE PROPOSED DUCTS AND CONDUITS ARE SHOWN FOR INFORMATION ONLY. THE EXACT ROUTING OUT FOR CLARITY. ALL MARKING WITHIN THE SHALL BE COORDINATED WITH THE RESIDENT ENGINEER. PROPOSED IMPROVEMENT LIMITS TO INCLUDE RELOCATE EXISTING AIRFIELD GUIDANCE SIGN THE ADDITIVE ALTERNATES, IF AWARDED, WILL 10. SEE DETAILS ON SHEETS ELD1-3. BE RE-MARKED. THE RESIDENT ENGINEER WILL **EXISTING AIRFIELD GUIDANCE SIGN** PROVIDE MARKING DIMENSIONS AS NEEDED. 11. ALL EXISTING UNUSED AIRFIELD LIGHTING CABLE SHALL BE REMOVED FROM THE UNIT DUCT. UNIT DUCT SHALL BE NEW BASE MOUNTED RUNWAY EDGE LIGHT ABANDONED IN PLACE, COST SHALL BE INCIDENTAL TO INSTALLATION OF NEW CABLE. ADJUST BASE MOUNTED RUNWAY EDGE LIGHT 12. INSTALLATION AND SPLICING OF FAA CONTROL CABLE SHALL BE COORDINATED WITH FAA. INSTALLATION AND SPLICING NEW INPAVEMENT LIGHT OF FAA CABLE SHALL BE IN COMPLIANCE WITH FAA STANDARD SPECIFICATIONS.  $\Theta$ ADJUST INPAVEMENT LIGHT 13. CONNECT IN-PAVEMENT 1/C#6 INSULATED GROUNDING CONDUCTOR TO GROUND ROD AT EDGE LIGHT BASE. TAXIWAY CENTERLINE LIGHTS SHALL BE INSTALLED SO THAT THE NEAREST EDGE IS MINIMUM OF 2 FEET FROM ANY CONCRETE PAVEMENT JOINT. 14. EXISTING PAVEMENT SHALL BE SAWED AND REMOVED IN ACCORDANCE WITH THE ELECTRICAL DETAILS AND NEW PVC CONDUIT INSTALLED. THE TRENCH SHALL BE BACKFILLED WITH 610 CONCRETE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND IN ACCORDANCE WITH THE ELECTRICAL DETAILS. PAVEMENT REMOVAL AND CONCRETE BACKFILL SHALL BE INCIDENTAL TO THE CONCRETE ENCASED DUCT PAY ITEM. 15. ADJUST BASE-MOUNTED AND IN-PAVEMENT LIGHT SHALL INCLUDE INSTALLATION OF REQUIRED GASKETS, EXTENSIONS, SPACER RINGS, Y-FLANGES AND MUD PLATES AS NEEDED, SEALANT, NEW L-830 ISOLATION TRANSFORMERS, L-823 CONNECTORS AND GROUNDING, EXISTING LIGHT FIXTURES AND CANS SHALL BE RE-USED. 16. NEW BASE MOUNTED AND IN-PAVEMENT LIGHT SHALL INCLUDE INSTALLATION OF NEW BASE CANS, REQUIRED GASKETS, EXTENSIONS, SPACER RINGS, Y-FLANGES AND MUD PLATES AS NEEDED, SEALANT, NEW L-830 ISOLATION TRANSFORMERS, L-823 CONNECTORS AND GROUNDING, EXISTING LIGHT FIXTURES WILL BE RE-USED. 17. CONNECT NEW CONCRETE ENCASED DUCT TO EXISTING HANDHOLE, COST SHALL BE INCIDENTAL TO NEW CONCRETE ENCASED DUCT. 18. RELOCATE EXISTING SIGN SHALL INCLUDE NEW CONCRETE FOUNDATION, NEW L-867 CAN, NEW L-830 TRANSFORMER AND GROUNDING. EXISTING SIGN SHALL BE REMOVED AND RE-INSTALLED. EXISTING FOUNDATION SHALL BE COMPLETELY 19. NEW TAXIWAY CENTERLINE LIGHT SHALL INCLUDE NEW LIGHT FIXTURE, NEW L-868 CAN, REQUIRED GASKETS, EXTENSIONS, SPACER RINGS, Y-FLANGES AND MUD PLATES AS NEEDED, GROUNDING AND NEW L-830 ISOLATION TRANSFORMERS. **ELECTRICAL AND MARKING NOTES** 20. THE CONTRACTOR SHALL INTERCEPT THE RUNWAY EDGE LIGHT CIRCUIT CONDUIT AND RUNWAY CENTERLINE CIRCUIT (EMN1) CONDUIT AND CONNECT TO THE NEW ELECTRICAL HANDHOLE. COST SHALL BE INCIDENTAL TO THE ELECTRICAL HANDHOLE.

Н

G

F

Ε

D

C

R F D

CHICAGO ROCKFORD
INTERNATIONAL AIRPORT

FRANZ L. OLSON ACTING EXECUTIVE DIRECTOR

CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS

Chicago Rockford International Airport

Rockford, Illinois

Greater Rockford Airport Authority

AIP Proj: 3-17-0088-XX IL Proj: RFD-4083

APPROVED AS WORKING PLAN
BY:

REV DATE DESCRIPTION
PROJECT NAME:

REHABILITATE RUNWAY 1/19 PHASE 1

SHEET TITLE:

ELECTRICAL AND MARKING NOTES (EMN1)

CMT-RFD CMT-RFD CMT-ARR

PROJECT NO.: 10258-03-00/06

DATE: APRIL 22, 2011

SHEET NO. 38

SHEET 38 OF 67 SHEETS

