



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 3, 2022

SUBJECT: FAP Route 681 (IL 116)
Project STP-DSSQ(974)
Section (113)RS-3
Livingston County
Contract No. 66E53
Item No. 25, June 17, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Revised page 5 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
STATUS OF UTILITIES TO BE ADJUSTED	2
PAVEMENT PATCHING	2
PERMANENT SURVEY MARKERS, TYPE I	4
FRAMES AND LIDS TO BE ADJUSTED AND WATER VALVES TO BE ADJUSTED	5
TRAFFIC CONTROL IN THE VICINITY OF A RAILROAD GRADE CROSSING	5
MAXIMUM DROP-OFFS BETWEEN ADJACENT LANES	5
TEMPORARY INFORMATION SIGNING.....	6
RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE).....	7
RIGHT OF ENTRY TO UNION PACIFIC RAILROAD PROPERTY, CONTRACT 66E53, DOT/AAR NO. 290 756 Y	8
HOT – MIX ASPHALT SURFACE REMOVAL AT THE IL 116 – UNION PACIFIC RAILROAD GRADE CROSSING, DOT/AAR NO. 290 756 Y	9
MODIFY EXISTING CONTROLLER AND CABINET.....	9
VIDEO VEHICLE DETECTION SYSTEM.....	10
PERMANENT TRAFFIC SIGNAL TIMING	20
REMOTE-CONTROLLED VIDEO SYSTEM.....	20
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION.....	22
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH:	22
PREPARATION AND RESTORATION OF SIDEWALK WORK AREAS	23
CLEANING EXISTING DRAINAGE STRUCTURES.....	23
INSTALL SIGN PANEL – TYPE 1	23
CONCRETE CURB REPAIR.....	24
CONSTRUCTION LAYOUT SPECIAL (ADA)	24
TRAFFIC CONTROL PLAN	25
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	25
BLENDED FINELY DIVIDED MINERALS (BDE).....	27
COMPENSABLE DELAY COSTS (BDE)	27
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	30
FUEL COST ADJUSTMENT (BDE)	39

FRAMES AND LIDS TO BE ADJUSTED AND WATER VALVES TO BE ADJUSTED

(Effective June 1, 2012)

Description. This work shall consist of adjusting frames and lids and water valves. This work shall be done according to the applicable portions of Section 603 of the Standard Specifications and the following.

Construction Requirements. Prior to the milling operation, the Contractor shall remove all frames and lids of manholes and water valves. After removal, the Contractor shall place a suitable metal plate over the manhole and water valve locations and backfill the area with a temporary hot-mix or cold-mix asphalt mixture. The Contractor shall then complete the milling and placement of all HMA lifts except surface course.

Prior to placing the surface course, the Contractor shall reinstall the frames and lids and water valves and adjust them to the finished pavement elevation.

The excavated area around the manholes and water valves shall be filled with Class PP-1 or PP-2 concrete.

Basis of Payment. This work will be paid at the contract unit price each for FRAMES AND LIDS TO BE ADJUSTED and WATER VALVES TO BE ADJUSTED.

TRAFFIC CONTROL IN THE VICINITY OF A RAILROAD GRADE CROSSING

(Effective August 4, 2017)

In accordance with Chapter 8 of the Manual on Uniform Traffic Control Devices (MUTCD):

When a grade crossing exists either within or in the vicinity of a temporary traffic control zone, lane restrictions, flagging (see Chapter 6E of the MUTCD), or other operations shall not be performed in a manner that would cause highway vehicles to stop on the railroad or LRT tracks, unless a flagger or uniformed law enforcement officer is provided at the grade crossing to minimize the possibility of highway vehicles stopping on the tracks, even if automatic warning devices are in place.

See Figure 6H-46 and associated notes of the MUTCD regarding the temporary traffic control in the vicinity of the railroad grade crossing.

Basis of Payment. The cost of the additional flagger and any additional signs, if necessary, will not be paid for separately, but shall be included in the cost of associated traffic control items.

MAXIMUM DROP-OFFS BETWEEN ADJACENT LANES

(Effective December 14, 2009, Revised July 31, 2020)

When the Contractor's operations cause a difference in elevation greater than 1.5 in. (38 mm) for a vertical milled face, or 2 in (50mm) for a lift of HMA resurfacing between adjacent lanes, the lane shall remain closed. The Contractor shall adjust his milling and paving operations so that all traffic lanes are open at the end of each work day.

Revised June 3, 2022