



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 7, 2022

SUBJECT: Route CH 14
Section 20-00137-00-PP
Jasper County
Contract No. 95918
Item 130
June 17, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised sheet 2 of the Plans.**
- 2. Revised the Schedule of Prices.**
- 3. Revised the Index of Sheets to the Special Provisions.**
- 4. Revised page 1 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

JASPER COUNTY
SEC. 20-00137-00-FP
COUNTY HIGHWAY 14

INDEX OF SHEETS

1	REFERENCES
1	DESCRIPTION OF WORK
1	UTILITIES
1	TRAFFIC CONTROL PLAN
1	PROCESSING SOIL-CEMENT BASE COURSE 8"
2	LR 107-4
3	LR 702



Local Public Agency	County	Section Number
Jasper County	Jasper	20-00137-00-FP

The following Special Provision supplement the "Standard Specifications for Road and Bridge Construction", adopted

January 1, 2022

, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways", and the "Manual of Test Procedures of Materials" in effect on the date of invitation of bids, and the Supplemental Specification and Recurring Special Provisions indicated on the Check Sheet included here in which apply to and govern the construction of the above named section, and in case of conflict with any parts, or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

DESCRIPTION OF WORK:

This work shall consist of the reconstruction of the existing roadway with an 8" soil-cement base course.

UTILITIES:

No utilities are affected by this construction.

TRAFFIC CONTROL PLAN (BY OTHERS):

Traffic control shall be in accordance with the applicable sections of the Standard Specifications for Road and Bridge Construction, the applicable guidelines contained in the Illinois Manual on Uniform Traffic Control Devices for Streets and Highways, these special provisions, and any special details and Highway Standards contained herein in the plans.

Special attention is called to Article 107.09 and 107.14 of the Standard Specifications for Road and Bridge Construction and the following Highway Standards, and other special provisions relating to traffic control.

1. Traffic Control Standards 701901, BLR 22.
2. The road shall be closed to thru traffic.
3. The ADT volume is anticipated to be less than 100 vehicles within the construction area.
4. The County shall install "ROAD CLOSED AHEAD" signs in permanent locations as directed by the Engineer. The signs shall be installed at each end of the project. The signs shall be installed in accordance with standard 701901.
5. The County shall be responsible for furnishing, installing, relocating and removing all traffic control devices required by the appropriate standard and as approved by the Engineer.
6. Access to all residences located within the project limits shall be maintained at all times.
7. No open or partially filled holes or trenches shall remain overnight unless protected with barricades and lights.
8. Road closed ahead signs with left or right turn symbol shall be erected along both sides of IL Rt 130 and IL Rt 49 each direction from the project termini as directed by the Engineer
9. All of the above traffic control standards shall be paid for by others.

PROCESSING SOIL-CEMENT BASE COURSE 8"

The cement content of the base course is estimated to be 8% by volume based upon test results of sample material. The bituminous cure coat shall be HFE 90. Material shall be spread @ 0.20 gal/sq yd.