

SUMMARY OF QUANTITIES			RURAL			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0005 (80% FED, 20% STATE)	0021 (100% STATE)	0021 (80% FED, 10% STATE, 10% LOCAL)
* 78000100	THERMOPLASTIC PAVEMENT MARKING -	SQ FT	123	123		
	LETTERS AND SYMBOLS					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2347	2347		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	356	356		
* 78000600	THERMOPLASTIC PAVEMENT MARKING -	FOOT	130	130		
	LINE 12"					
* 78000650	THERMOPLASTIC PAVEMENT MARKING -	FOOT	126	126		
	LINE 24"					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	74	74		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	74	74		
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	1463	1463		
* 81028310	UNDERGROUND CONDUIT, PVC, 3/4" DIA.	FOOT	32		32	
* 81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	55		55	
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	71		71	
* 81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	160		160	
* 81028400	UNDERGROUND CONDUIT, PVC, 5" DIA.	FOOT	16		16	

SUMMARY OF QUANTITIES			RURAL			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0005 (80% FED, 20% STATE)	0021 (100% STATE)	0021 (80% FED, 10% STATE, 10% LOCAL)
* 81400100	HANDHOLE	EACH	4		4	
* 81400300	DOUBLE HANDHOLE	EACH	1		1	
* 81500100	GULFBOX JUNCTION	EACH	1		1	
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	793		793	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	870		870	
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	112		112	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14	FOOT	214	13	201	
	1 PAIR					
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6	FOOT	62		62	
	2 C					
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT	FOOT	373		373	
	GROUNDING CONDUCTOR, NO. 6 1C					
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1		1	
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	5		5	
* 87601100	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED	EACH	4		4	
	STEEL, TYPE I					

* SPECIALTY ITEM

REVISED 6-1-2022 REV. - MS

MODEL: Default FILE NAME: p:\p16aroom.dat\illinois.gov\p16aroom\Documents\DOT Offices\District 7\Projects\74473\CADDData\CAD\Sheets\74473-SH-500.dgn

USER NAME = steffemk	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 3/12/2021	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**


SUMMARY OF QUANTITIES

SCALE: N/A SHEET 3 OF 5 SHEETS STA. TO STA.

F.A.P. RTE. 332	SECTION (15, 16)Z RS-2	COUNTY LAWRENCE	TOTAL SHEETS 63	SHEET NO. 5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 74473	

SUMMARY OF QUANTITIES			RURAL			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0005 (80% FED, 20% STATE)	0021 (100% STATE)	0021 (80% FED, 10% STATE, 10% LOCAL)
* 87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1			1
* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1			1
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	18			18
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3.5			3.5
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30.5			30.5
* 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2
* 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4			4
* 88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4			4
* 88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	4			4
* 88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	2			2
* 88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	14			14

SUMMARY OF QUANTITIES			RURAL			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0005 (80% FED, 20% STATE)	0021 (100% STATE)	0021 (80% FED, 10% STATE, 10% LOCAL)
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	4			4
* 88600100	DETECTOR LOOP, TYPE I	FOOT	282	58		224
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8			8
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1
* 89500120	REMOVE EXISTING SERVICE INSTALLATION	EACH	1			1
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1
89502380	REMOVE EXISTING HANDHOLE	EACH	3			3
89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	1			1
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5			5
X0326440	SURFACE REMOVAL, VARIABLE DEPTH (SPECIAL)	SQ YD	529	529		
X2600012	REMOVE AND RELOCATE SIGN PANEL AND POLE ASSEMBLY	EACH	3		3	
X4060995	TEMPORARY RAMP, SPECIAL	SQ YD	888	888		
X6061005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	28		28	



* SPECIALTY ITEM

△ REVISED 6-1-2022 REV. - MS