

LOCATION	LANE	LENGTH (FEET)	WIDTH (FEET)	CLASS A PATCHING 13"			SAW CUTS (FOOT)	PATCHING REINFORCEMENT (SQ YD)	TIE BARS (EACH)	COMMENTS
				TYPE 2	TYPE 3	TYPE 4				
				(SQ YDS)	(SQ YDS)	(SQ YDS)				
MILE PT.	DL/PL									
0.00										RESURF. JOINT
3.10	DL	12	12		16.00		72	16.00		(MILE MARKER 20)
3.70	DL	10	12	13.33			68	13.33		RTE 4 OVERPASS
3.72	DL	10	12	13.33			68	13.33		
4.80	DL	10	12	13.33			68	13.33		
4.85	DL	40	12			53.33	128	53.33	20	MARINE/ST. JACOB
5.20	DL	15	12		20.00		78	20.00		
5.40	DL	8	12	10.67			64	10.67		
6.45	DL	10	12	13.33			68	13.33		
6.50	DL	10	12	13.33			68	13.33		
6.70	DL	5	12	6.67			58	6.67		
7.53	DL	8	12	10.67			64	10.67		
7.56	DL	5	12	6.67			58	6.67		
8.00	DL	5	12	6.67			58	6.67		
8.20	DL	5	12	6.67			58	6.67		
8.65	DL	50	6			33.33	124	33.33	25	
11.00	DL	5	12	6.67			58	6.67		IL 160
11.20	DL	8	12	10.67			64	10.67		
12.20	DL	5	12	6.67			58	6.67		
12.90	DL	10	12	13.33			68	13.33		
14.47	DL	15	12		20.00		78	20.00		
15.40	DL	200	12			266.67	448	266.67	100	COUNTY LINE
EAST BOUND TOTALS				152.01	56.00	353.33	1876	561.34	145	

FILE NAME =	USER NAME = dintelman.jn	DESIGNED -	REVISED -
er:\pwwork\pwwork\dintelman.jn\d0284781	076F31-aht-plen.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 2/9/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PATCHING SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	DIST 8 PATCHING 2012-1		8	7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76F31	
*MADISON/BOND				