

90% FED.  
10% STATE

URBAN  
TOTAL  
QUANTITY

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	HIGHWAY LIGHTING	NOISE WALL
				0004	0008	0040	0040	0040	0040	0040	0021	0040
				URBAN	016-1705	016-1720	016-2024	016-1722	016-1723	016-1809	URBAN	NONE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	203	203								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	37	37								
20100500	TREE REMOVAL, ACRES	ACRE	0.75	0.75								
20101700	SUPPLEMENTAL WATERING	UNIT	6.3	6.3								
20200100	EARTH EXCAVATION	CU YD	8235	8235								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2750	2750								
20400800	FURNISHED EXCAVATION	CU YD	9510	9510								
20700220	POROUS GRANULAR EMBANKMENT	CU YD	755	755								
20800150	TRENCH BACKFILL	CU YD	2600	2600								
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SD YD	15457	15457								
21101615	TOPSOIL FURNISH AND PLACE, 4"	SD YD	23706	23706								
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	100	100								
25000210	SEEDING, CLASS 2A	ACRE	5	5								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1039	1039								

\* DENOTES SPECIALTY ITEM      \*\* DENOTES NON-PARTICIPATING ITEM

Rev. 6-2-14

FILE PATH: C:\Users\alreda\OneDrive\Documents\Final Sheets\1060W28-sh1-500.dgn



0160W28-sh1-500.dgn  
 USER NAME: alreda  
 PLOT SCALE: 2.0000 "/>

DESIGNED - NSA	REVISED -
DRAWN - NSA	REVISED -
CHECKED - AFC	REVISED -
DATE - 04/28/14	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60W28	