

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	HIGHWAY LIGHTING	NOISE WALL
				0004 URBAN	0008 016-1705	0040 016-1720	0040 016-Z024	0040 016-1722	0040 016-1723	0040 016-1809	0021 URBAN	0040 NONE
X0370164	MANHOLES TYPE A, 4' DIA., TYPE I FRAME, CLOSED LID (CITY OF CHICAGO)	EACH	2	2	A							
X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	76		76							
X2020502	BRACED EXCAVATION	CU YD	1939	710	1229							
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	8310	8310	A							
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	2257	2257								
X5012502	CONCRETE REMOVAL (SPECIAL)	CU YD	15	15								
X5210110	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 200K	EACH	18		18							
X5210120	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 250K	EACH	21		21							
X5210130	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 300K	EACH	12		12							
X5210150	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 400K	EACH	6		6							
X5210340	HIGH LOAD MULTI-ROTATIONAL BEARINGS, FIXED - 500K	EACH	6		6							
X5210350	HIGH LOAD MULTI-ROTATIONAL BEARINGS, FIXED - 600K	EACH	6		6							
X5210355	HIGH LOAD MULTI-ROTATIONAL BEARINGS, FIXED - 650K	EACH	8		8							
X550A562	TEMPORARY STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	93	93	A							

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

REV. 6-2-14

Rev.

FILE PATH: C:\Users\jordan\Documents\Projects\60W28\Sheets\60W28-11-500.dgn



0160W28-11-500.dgn
USER NAME: ajordan
PLOT SCALE: 2.0000 / 1" = 100'
PLOT DATE: 4/28/2014

DESIGNED - NSA	REVISED -
DRAWN - NSA	REVISED -
CHECKED - AFC	REVISED -
DATE - 04/28/14	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 20 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	210
CONTRACT NO. 60W28			ILLINOIS FED. AID PROJECT	