EXISTING PIPE SCHEDULE (IDOT)

DRAINAGE AND UTILITY SHEET NO.	STATION	TRENCH BACKFILL	STORM SEWER REMOVAL						VIDEO TAPING OF MAIN DRAIN	MAIN DRAIN CLEANING	TELEVISION INSPECTION OF SEWER	STORM SEWERS TO BE CLEANED					
			10"	12"	18"	21"	24"	30"				10"	12"	18"	21"	24"	30"
		CU YD	FOOT						FOOT	FOOT	FOOT	FOOT					
1	1799+15.31 to 1803+50.00	0.0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
2	1803+50.00 to 1814+00.00	18.2	0	336	327	0	0	0	0	0	222	0	82	74	0	0	0
3	1814+00.00 to 1824+00.00	137.8	0	204	0	0	31	272	1840	0	532	0	79	0	0	156	31
4	1824+00.00 to 1833+00.00	21.3	0	218	0	0	0	0	5480	2740	212	0	52	0	0	280	0
5	1833+00.00 to 1841+00.00	33.4	89	61	0	12	0	0	0	0	214	107	0	0	192	0	0
6	1841+00.00 to 1842+02.61	0.0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	ROUNDED TOTAL	210.7	89	819	327	12	31	272	7320	2740	1180	107	213	74	192	436	31

NOTES:

1. ADDITIONAL TRENCH BACKFILL QUANTITY PROVIDED ON THE DRAINAGE AND UTILITY SCHEDULE FOR THE PROPOSED STORM SEWER AND SUGGESTED STAGES OF CONSTRUCTION AND TRAFFIC CONTROL SCHEDULE FOR TEMPORARY DRAINAGE.
2. THE QUANTITY PROVIDED FOR TELEVISION INSPECTION OF SEWER CONSIST OF WORK BEFORE AND AFTER CONSTRUCTION.

EXISTING STRUCTURE SCHEDULE (CITY OF CHICAGO)

NORTHING	EASTING	REMOVING MANHOLES	REMOVING CATCH BASINS
		EACH	EACH
GREEN STREET (SOUTH LIMITS)			
1897822.53	1170813.84	1	
GREEN STREET (NORTH LIMITS)			
1898165.62	1170781.82		1
1898168.08	1170817.22		1
TOTALS		1	2

EXISTING PIPE SCHEDULE (CITY OF CHICAGO)

STATION	TRENCH BACKFILL	COMBINED SEWER REMOVAL		
		8"	12"	24"
	CU YD	FOOT		
GREEN STREET (SOUTH LIMITS)	0.0	-	36	65
GREEN STREET (NORTH LIMITS)	126.4	36	-	75
TOTALS	126.4	36	36	140

EXISTING UTILITY STRUCTURE SCHEDULE (CITY OF CHICAGO)

STATION	OFFSET	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	REMOVE EXISTING VALVE AND VAULT	COMMENTS
		(EA)	(EA)	
47+15.37	3.82' LT		1	ALIGNMENT ALONG WM; STRUCTURE PREVIOUSLY FILLED
47+18.58	0.00		1	ALIGNMENT ALONG WM RELOCATION
51+11.44	0.00		1	ALIGNMENT ALONG WM RELOCATION
51+14.95	4.52' RT	1		ALIGNMENT ALONG WM RELOCATION
TOTALS		1	3	