

90% FED.
10% STATE
URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	HIGHWAY LIGHTING	NOISE WALL
				0004 URBAN	0008 016-1705	0040 016-1720	0040 016-2024	0040 016-1722	0040 016-1723	0040 016-1809	0021 URBAN	0040 NONE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	203	203								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	37	37								
20100500	TREE REMOVAL, ACRES	ACRE	0.75	0.75								
20101700	SUPPLEMENTAL WATERING	UNIT	6.3	6.3								
20200100	EARTH EXCAVATION	CU YD	8235	8235								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2750	2750								
20400800	FURNISHED EXCAVATION	CU YD	7575	7575								
20700220	POROUS GRANULAR EMBANKMENT	CU YD	755	755								
20800150	TRENCH BACKFILL	CU YD	2600	2600								
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	15457	15457								
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	23706	23706								
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	100	100								
25000210	SEEDING, CLASS 2A	ACRE	5	5								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1039	1039								

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM

Rev 6-11-14 Rev. 6-2-14

C:\Users\vlizadahn\Desktop\Prints\Final Sheets\0160W28-sh1-500.dgn



0160W28-sh1-500.dgn
USER NAME : vlizadahn
PLOT SCALE : 2.0000 1/16"
PLOT DATE : 4/28/2014

DESIGNED - NSA	REVISIONS -
DRAWN - NSA	REVISIONS -
CHECKED - AFC	REVISIONS -
DATE - 04/28/14	REVISIONS -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SCALE: SHEET 1 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	5
CONTRACT NO. 60W28			ILLINOIS FED. AID PROJECT	

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	HIGHWAY LIGHTING	NOISE WALL
				0004 URBAN	0008 016-1705	0040 016-1720	0040 016-2024	0040 016-1722	0040 016-1723	0040 016-1809	0021 URBAN	0040 NONE
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	8535	8535								
66900205	SPECIAL WASTE DISPOSAL	CU YD										
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1								
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5								
67100100	MOBILIZATION	L SUM	1	1								
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	675	675								
70106800	CHANGEABLE MESSAGE SIGN	CAL MD	100	100								
70300100	SHORT TERM PAVEMENT MARKING	FOOT	118,448	118,448								
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	963	963								
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	469	469								
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	89230	89230								
70400100	TEMPORARY CONCRETE BARRIER	FOOT	8626	8626								
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	9323	9323								
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	18	18								
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	28	28								
72000200	SIGN PANEL - TYPE 2	SO FT	56	56								

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

Rev. 6-10-14

Rev. 6-2-14



018W28-shr-500.dgn
USER NAME * alicedehn
PLOT SCALE * 2.0000' / in.
PLOT DATE * 4/28/2014

DESIGNED - NSA
DRAWN - NSA
CHECKED - AFC
DATE - 04/28/14

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 11 OF 24 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	15
CONTRACT NO. 60W28			ILLINOIS FED. AID PROJECT	

FILE PATH: C:\Users\alicedehn\OneDrive\Projects\Final Sheets\018W28-shr-500.dgn

EARTHWORK SCHEDULE

FROM STATION	TO STATION	EARTH EXCAVATION (2020100)				REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS (20201200)				EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (EARTH EXCAVATION * 0.85)				EMBANKMENT				EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)				FURNISHED EXCAVATION (20400800)
		CU YD				CU YD				CU YD				CU YD				CU YD				
		STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	TOTAL
RAMP NW (INCLUDING PR. RETAINING WALLS 016-1720, 016-1722, & 016-1723)																						
1802+50.00	1802+75.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
1802+75.00	1803+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
1803+00.00	1803+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
1803+50.00	1804+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
1804+00.00	1804+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
1804+50.00	1805+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
1805+00.00	1805+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
1805+50.00	1806+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
1806+00.00	1806+50.00	0	13	39	0	0	2	5	0	0	11	33	0	0	0	0	0	11	33	0	0	
1806+50.00	1806+91.96	0	24	71	0	0	3	8	0	0	20	61	0	0	2	6	0	18	55	0	0	
1806+91.96	1807+00.00	0	5	15	0	0	1	2	0	0	4	13	0	0	1	2	0	4	11	0	0	
1807+00.00	1807+50.00	0	31	92	0	0	4	11	0	0	26	78	0	0	5	15	0	21	63	0	0	
1807+50.00	1808+00.00	0	30	91	0	0	4	11	0	0	26	77	0	0	7	20	0	19	58	0	0	
1808+00.00	1808+50.00	0	31	92	0	0	4	11	0	0	26	78	0	0	8	23	0	19	56	0	0	
1808+50.00	1809+00.00	0	32	96	0	0	4	11	0	0	27	82	0	0	8	23	0	20	59	0	0	
1809+00.00	1809+50.00	0	36	107	0	0	4	12	0	0	30	91	0	0	8	23	0	23	68	0	0	
1809+50.00	1810+00.00	0	38	115	0	0	4	13	0	0	33	98	0	0	7	20	0	26	77	0	0	
1810+00.00	1810+50.00	0	35	105	0	0	4	12	0	0	30	89	0	0	6	19	0	24	71	0	0	
1810+50.00	1811+00.00	0	26	78	0	0	3	9	0	0	22	66	0	0	7	20	0	15	46	0	0	
1811+00.00	1811+50.00	0	12	36	0	0	2	5	0	0	10	31	0	0	7	20	0	3	10	0	0	
1811+50.00	1812+00.00	0	2	6	0	0	0	1	0	0	2	5	0	0	15	44	0	-13	-39	0	0	
1812+00.00	1812+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	39	116	0	-39	-116	0	0	
1812+50.00	1813+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	65	195	0	-65	-195	0	0	
1813+00.00	1813+50.00	0	7	20	0	0	1	2	0	0	6	17	0	0	90	270	0	-84	-253	0	0	
1813+50.00	1813+60.00	0	3	8	0	0	1	2	0	0	2	6	0	0	11	32	0	-8	-25	0	0	
1813+60.00	1814+00.00	0	10	29	0	0	3	8	0	0	8	24	0	0	0	0	0	8	24	0	0	
1814+00.00	1814+50.00	0	12	35	0	0	4	11	0	0	10	29	0	0	0	0	0	10	29	0	0	
1814+50.00	1815+00.00	0	8	23	0	0	3	10	0	0	6	19	0	0	0	0	0	6	19	0	0	
1815+00.00	1815+50.00	0	4	13	0	0	3	8	0	0	4	11	0	0	0	0	0	4	11	0	0	
1815+50.00	1816+00.00	0	5	14	0	0	3	9	0	0	4	11	0	0	0	0	0	4	11	0	0	
1816+00.00	1816+50.00	0	4	13	0	0	4	11	0	0	4	11	0	0	0	0	0	4	11	0	0	
1816+50.00	1817+00.00	0	4	12	0	0	4	11	0	0	3	10	0	0	0	0	0	3	10	0	0	
1817+00.00	1817+50.00	0	5	14	0	0	4	12	0	0	4	11	0	0	0	0	0	4	11	0	0	
1817+50.00	1818+00.00	0	6	17	0	0	4	13	0	0	5	15	0	0	0	0	0	5	15	0	0	
1818+00.00	1818+19.17	0	3	8	0	0	2	6	0	0	2	6	0	0	0	0	0	2	6	0	0	
1818+19.17	1818+45.67	0	4	11	0	0	4	11	0	0	3	10	0	0	0	0	0	3	10	0	0	
1818+45.67	1818+50.00	0	1	2	0	0	1	3	0	0	1	2	0	0	0	0	0	1	2	0	0	
1818+50.00	1818+51.17	0	0	1	0	0	1	2	0	0	0	1	0	0	0	0	0	0	1	0	0	
1818+51.17	1818+53.67	0	1	2	0	0	1	2	0	0	0	1	0	0	0	0	0	0	1	0	0	
SUBTOTAL		0	387	1160	0	0	77	230	0	0	329	986	0	0	282	846	0	0	47	140	0	

NOT A PAY ITEM.

FURNISHED EXCAVATION IS ASSUMED TO EQUAL EMBANKMENT DUE TO THE UNCERTAINTY IN THE PERCENTAGE OF EARTH EXCAVATION THAT IS CLASSIFIED AS SPECIAL, NON-SPECIAL, AND HAZARDOUS WASTE.

NOTE: REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS WAS ESTIMATED BY TOTALING 4" OF EXISTING TOPSOIL REMOVAL, 10% OF EARTH MOVED, AND 10% OF STRUCTURAL EXCAVATION (EARTH MOVED = EARTH EXCAVATION / 0.90)

	DESIGNED - KAM DRAWN - KAM CHECKED - KCF DATE - 6/10/14	REVISED - 5/27/2014 REVISED - 6/10/2014 REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES SCALE: SHEET 3 OF 6 SHEETS STA. TO STA.	F.A.I. RTE. 90/94/290	SECTION 2013-010R	COUNTY COOK	TOTAL SHEETS 747	SHEET NO. 35
	USER NAME: m... PLOT SCALE: 1/80,000 PLOT DATE: 6/10/2014	CONTRACT NO. 60W28 ILLINOIS FED. AID PROJECT							

EARTHWORK SCHEDULE

FROM STATION	TO STATION	EARTH EXCAVATION (20200100)				REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS (20201200)				EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (EARTH EXCAVATION * 0.85)				EMBANKMENT				EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)				FURNISHED EXCAVATION (20400800)
		CU YD				CU YD				CU YD				CU YD				CU YD				
		STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	TOTAL
RAMP NW (INCLUDING PR. RETAINING WALLS 016-1720, 016-1722, & 016-1723)																						
BRIDGE OMISSION																						
1838+16.17	1838+18.17	0	0	2	0	0	0	5	0	0	0	2	0	0	0	4	0	0	0	-2	0	
1838+18.17	1838+23.67	0	0	5	0	0	0	13	0	0	0	4	0	0	26	0	0	0	0	-22	0	
1838+23.67	1838+50.00	0	0	23	0	0	0	44	0	0	0	20	0	0	136	0	0	0	0	-116	0	
1838+50.00	1838+62.56	0	0	11	0	0	0	18	0	0	0	9	0	0	50	0	0	0	0	-41	0	
1838+62.56	1838+98.00	0	0	30	0	0	0	45	0	0	0	26	0	0	91	0	0	0	0	-66	0	
1838+98.00	1839+00.00	0	0	2	0	0	0	4	0	0	0	7	0	0	4	0	0	0	0	-7	0	
1839+00.00	1839+50.00	0	0	40	0	0	0	60	0	0	0	34	0	0	71	0	0	0	0	-37	0	
1839+50.00	1840+00.00	0	0	37	0	0	0	58	0	0	0	31	0	0	67	0	0	0	0	-36	0	
1840+00.00	1840+17.00	0	0	13	0	0	0	20	0	0	0	11	0	0	24	0	0	0	0	-13	0	
1840+17.00	1840+50.00	0	0	29	0	0	0	39	0	0	0	25	0	0	52	0	0	0	0	-27	0	
1840+50.00	1841+00.00	0	0	93	0	0	0	65	0	0	0	79	0	0	62	0	0	0	0	17	0	
1841+00.00	1841+26.23	0	0	88	0	0	0	37	0	0	0	75	0	0	22	0	0	0	0	53	0	
1841+26.23	1841+50.00	0	0	114	0	0	0	35	0	0	0	97	0	0	16	0	0	0	0	81	0	
1841+50.00	1841+54.92	0	0	29	0	0	0	10	0	0	0	25	0	0	9	0	0	0	0	16	0	
1841+54.92	1841+78.17	0	0	142	0	0	0	40	0	0	0	121	0	0	72	0	0	0	0	49	0	
1841+78.17	1842+00.00	0	0	151	0	0	0	35	0	0	0	128	0	0	35	0	0	0	0	93	0	
1842+00.00	1842+02.61	0	0	21	0	0	0	5	0	0	0	18	0	0	1	0	0	0	0	17	0	
1842+02.61	1842+50.00	0	0	182	0	0	0	33	0	0	0	155	0	0	1	0	0	0	0	154	0	
SUBTOTAL		0	0	1012	0	0	0	566	0	0	0	860	0	0	743	0	0	0	0	117	0	0
INFIELD GRADING BETWEEN RAMP NW ABUTMENTS (SEE GRADING PLAN)																						
SUBTOTAL		100	955	2050	1671	126	240	573	560	85	812	1743	1420	59	1322	2687	1634	26	-510	-945	-214	5702
RAMP NW (TEMP) - NB TEMP EXIT																						
1507+53.30	1508+00.00	1	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	1	0	0	0	
1508+00.00	1508+50.00	1	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	1	0	0	0	
1508+50.00	1509+00.00	1	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	1	0	0	0	
1509+00.00	1509+50.00	1	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	1	0	0	0	
1509+50.00	1510+00.00	1	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	1	0	0	0	
1510+00.00	1510+50.00	3	0	0	0	1	0	0	0	3	0	0	0	0	0	0	0	3	0	0	0	
1510+50.00	1511+00.00	13	0	0	0	2	0	0	0	11	0	0	0	0	0	0	0	11	0	0	0	
1511+00.00	1511+50.00	45	0	0	0	5	0	0	0	38	0	0	0	0	0	0	0	38	0	0	0	
1511+50.00	1512+00.00	112	0	0	0	13	0	0	0	95	0	0	0	0	0	0	0	95	0	0	0	
1512+00.00	1512+50.00	118	0	0	0	14	0	0	0	100	0	0	0	0	0	0	0	100	0	0	0	
1512+50.00	1513+00.00	56	0	0	0	7	0	0	0	48	0	0	0	0	0	0	0	48	0	0	0	
1513+00.00	1513+50.00	28	0	0	0	4	0	0	0	24	0	0	0	0	0	0	0	24	0	0	0	
1513+50.00	1513+54.63	3	0	0	0	1	0	0	0	3	0	0	0	0	0	0	0	3	0	0	0	
SUBTOTAL		383	0	0	0	52	0	0	0	326	0	0	0	0	0	0	0	326	0	0	0	0
RAMP NW (TEMP) - WB TEMP ENTRANCE																						
1520+75.18	1521+00.00	0	0	5	0	0	0	1	0	0	0	4	0	0	0	1	0	0	0	3	0	
1521+00.00	1521+50.00	0	0	30	0	0	0	4	0	0	0	26	0	0	0	0	0	0	0	26	0	
1521+50.00	1522+00.00	0	0	55	0	0	0	7	0	0	0	47	0	0	0	0	0	0	0	47	0	
1522+00.00	1522+50.00	0	0	64	0	0	0	8	0	0	0	54	0	0	0	0	0	0	0	54	0	
1522+50.00	1523+00.00	0	0	46	0	0	0	6	0	0	0	39	0	0	0	0	0	0	0	39	0	
1523+00.00	1523+50.00	0	0	29	0	0	0	4	0	0	0	25	0	0	0	0	0	0	0	25	0	
1523+50.00	1524+00.00	0	0	38	0	0	0	5	0	0	0	32	0	0	0	0	0	0	0	32	0	
1524+00.00	1524+50.00	0	0	31	0	0	0	4	0	0	0	26	0	0	0	0	0	0	0	26	0	
1524+50.00	1525+00.00	0	0	14	0	0	0	2	0	0	0	12	0	0	0	0	0	0	0	12	0	
1525+00.00	1525+50.00	0	0	14	0	0	0	2	0	0	0	12	0	0	0	0	0	0	0	12	0	
1525+50.00	1525+90.00	0	0	7	0	0	0	1	0	0	0	6	0	0	0	0	0	0	0	6	0	
SUBTOTAL		0	0	333	0	0	0	44	0	0	0	283	0	0	1	0	0	0	0	282	0	0

* NOT A PAY ITEM.

** FURNISHED EXCAVATION IS ASSUMED TO BE EQUAL EMBANKMENT DUE TO THE UNCERTAINTY IN THE PERCENTAGE OF EARTH EXCAVATION THAT IS CLASSIFIED AS SPECIAL, NON-SPECIAL, AND HAZARDOUS WASTE.

NOTE: REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS WAS ESTIMATED BY TOTALING 4" OF EXISTING TOPSOIL REMOVAL, 10% OF EARTH MOVED, AND 10% OF STRUCTURAL EXCAVATION (EARTH MOVED = EARTH EXCAVATION / 0.90)

	USER NAME: mprank PLOT SCALE: 1/8" = 1'-0" PLOT DATE: 6/10/2014	DESIGNED - KAM DRAWN - KAM CHECKED - KCF DATE - 6/10/14	REVISED - 5/27/2014 REVISED - 6/10/2014 REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES SCALE: SHEET 4 OF 6 SHEETS STA. TO STA.	F.A.I. RTE. 90/94/290 SECTION 2013-010R COUNTY COOK TOTAL SHEETS 747 SHEET NO. 36 CONTRACT NO. 60W28 ILLINOIS FED. AID PROJECT
--	---	--	--	---	---	--

EARTHWORK SCHEDULE

FROM STATION	TO STATION	EARTH EXCAVATION (20200100)				REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS (20201200)				EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (EARTH EXCAVATION * 0.85)				EMBANKMENT				EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)				FURNISHED EXCAVATION (20400800)			
		CU YD				CU YD				CU YD				CU YD				CU YD				CU YD			
		STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4	STG 1	STG 2	STG 3	STG 4
RAMP SW (TEMP)																									
3501+92.41	3502+00.00	0	0	1	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	0	1	0	
3502+00.00	3502+26.39	0	0	6	0	0	0	1	0	0	0	5	0	0	0	0	0	0	0	0	0	0	5	0	
3502+26.39	3502+50.00	0	0	10	0	0	0	2	0	0	0	9	0	0	0	0	0	0	0	0	0	0	9	0	
3502+50.00	3502+87.80	0	0	23	0	0	0	3	0	0	0	20	0	0	0	0	0	0	0	0	0	20	0		
3502+87.80	3503+00.00	0	0	7	0	0	0	1	0	0	0	6	0	0	0	0	0	0	0	0	0	6	0		
3503+00.00	3503+50.00	0	0	21	0	0	0	3	0	0	0	18	0	0	0	1	0	0	0	0	0	17	0		
3503+50.00	3504+00.00	0	0	11	0	0	0	2	0	0	0	9	0	0	0	1	0	0	0	0	0	8	0		
3504+00.00	3504+50.00	0	0	10	0	0	0	2	0	0	0	9	0	0	0	0	0	0	0	0	0	9	0		
3504+50.00	3505+00.00	0	0	4	0	0	0	1	0	0	0	3	0	0	0	0	0	0	0	0	0	3	0		
3505+00.00	3505+05.20	0	0	3	0	0	0	1	0	0	0	3	0	0	0	0	0	0	0	0	0	3	0		
3505+05.20	3505+35.52	0	0	4	0	0	0	1	0	0	0	3	0	0	0	0	0	0	0	0	0	3	0		
3505+35.52	3505+35.71	0	0	3	0	0	0	1	0	0	0	3	0	0	0	0	0	0	0	0	0	3	0		
3505+35.71	3505+50.00	0	0	1	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	1	0		
3505+50.00	3506+00.00	0	0	5	0	0	0	1	0	0	0	4	0	0	0	0	0	0	0	0	0	4	0		
3506+00.00	3506+50.00	0	0	1	0	0	0	1	0	0	0	1	0	0	0	0	0	0	0	0	0	1	0		
3506+50.00	3507+00.00	0	0	2	0	0	0	1	0	0	0	2	0	0	0	0	0	0	0	0	0	2	0		
3507+00.00	3507+50.00	0	0	2	0	0	0	1	0	0	0	2	0	0	0	0	0	0	0	0	0	2	0		
3507+50.00	3508+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
3508+00.00	3508+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
3508+50.00	3509+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
3509+00.00	3509+50.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
3509+50.00	3509+64.30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
SUBTOTAL		0	0	114	0	0	0	24	0	0	0	97	0	0	0	2	0	0	0	0	0	95	0	0	
PR. RETAINING WALL 016-1809 ("P-CIR-SW" STATIONING)																									
1322+49.13	1322+75.00	4	4	4	0	16	16	16	0	3	3	3	0	45	45	45	0	-42	-42	-42	0				
1322+75.00	1323+00.00	8	8	8	0	14	14	14	0	7	7	7	0	103	103	103	0	-97	-97	-97	0				
1323+00.00	1323+25.00	9	9	9	0	14	14	14	0	7	7	7	0	124	124	124	0	-116	-116	-116	0				
1323+25.00	1323+50.00	1	1	1	0	12	12	12	0	1	1	1	0	117	117	117	0	-116	-116	-116	0				
1323+50.00	1323+75.00	1	1	1	0	12	12	12	0	1	1	1	0	112	112	112	0	-111	-111	-111	0				
1323+75.00	1324+00.00	0	0	0	0	11	11	11	0	0	0	0	0	102	102	102	0	-102	-102	-102	0				
1324+00.00	1324+11.41	0	0	0	0	6	6	6	0	0	0	0	0	41	41	41	0	-41	-41	-41	0				
1324+11.41	1324+25.00	0	0	0	0	6	6	6	0	0	0	0	0	46	46	46	0	-46	-46	-46	0				
1324+25.00	1324+50.00	0	0	0	0	10	10	10	0	0	0	0	0	78	78	78	0	-78	-78	-78	0				
1324+50.00	1324+75.00	0	0	0	0	9	9	9	0	0	0	0	0	69	69	69	0	-69	-69	-69	0				
1324+75.00	1325+00.00	0	0	0	0	9	9	9	0	0	0	0	0	67	67	67	0	-67	-67	-67	0				
1325+00.00	1325+11.96	0	0	0	0	4	4	4	0	0	0	0	0	35	35	35	0	-35	-35	-35	0				
1325+11.96	1325+13.70	0	0	0	0	1	1	1	0	0	0	0	0	5	5	5	0	-5	-5	-5	0				
1325+13.70	1325+18.70	0	0	0	0	2	2	2	0	0	0	0	0	10	10	10	0	-10	-10	-10	0				
SUBTOTAL		23	23	23	0	85	85	85	0	20	20	20	0	644	644	644	0	-624	-624	-624	0			1873	
TOTAL		507	1365	4693	1671	263	401	1522	560	431	1161	3989	1420	703	2248	4923	1634	-272	-1088	-935	-214			7575	
ROUNDED TOTAL			8235				2750				7000			9510				-2510						7575	

NOT A PAY ITEM.

FURNISHED EXCAVATION IS ASSUMED TO EQUAL EMBANKMENT DUE TO THE UNCERTAINTY IN THE PERCENTAGE OF EARTH EXCAVATION THAT IS CLASSIFIED AS SPECIAL, NON-SPECIAL, AND HAZARDOUS WASTE.

NOTE: REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS WAS ESTIMATED BY TOTALING 4" OF EXISTING TOPSOIL REMOVAL, 10% OF EARTH MOVED, AND 10% OF STRUCTURAL EXCAVATION (EARTH MOVED = EARTH EXCAVATION / 0.90)



DESIGNED - KAM
 DRAWN - KAM
 CHECKED - KCF
 DATE - 6/10/14

REVISED - 5/27/2014
 REVISED - 6/10/2014
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 5 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	37
CONTRACT NO. 60W28				
ILLINOIS FED. AID PROJECT				