

CONSTR. CODE
STP - RUR
80%FED - 20%STATE
ROADWAY
0005
RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
20400800	FURNISHED EXCAVATION	CU YD	40	40
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	115	115
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	66,153	66,153
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	29	29
40600525	LEVELING BINDER (HAND METHOD), N50	TON	49	49
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	10,976	10,976
40600990	TEMPORARY RAMP	SQ YD	381	381
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	9,672	9,672
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	516	516
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3656	3656
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	98,004	98,004
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	7,079	7,079
* 66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	3	3
67100100	MOBILIZATION	L SUM	1	1

* SPECIALTY ITEM


FILE NAME =	USER NAME = calderoni	DESIGNED -	REVISED -
pw\plnroom.dot.illinois.gov\PIDOT\Documents\IDOT Offices\District 3\Projects\0366050\Drawings\0366054-sht-500.dgn		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
587	(17,18RS-2	LASALLE	22	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 66D54	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				STP - RUR	
				80%FED - 20%STATE	
				ROADWAY	
		0005		RURAL	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	384	384	
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	28166	28166	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2490	2490	
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1210	1210	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	42	42	
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	33031	33031	
∅ Z0076600	TRAINEES	HOUR	2000	2000	
Z0034105	MATERIAL TRANSFER DEVICE	TON	20,580	20,580 	
∅ Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	2000	2000	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

* SPECIALTY ITEM

∅ 0042

FILE NAME =	USER NAME = calderoni	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
pw\planroom.dot.illinois.gov\PIDOT\Documents\IDOT Offices\District 3\Projects\0366050\Drawings\0366054-shr-S00.dgn	DRAWN	REVISIONS	587			(17,18)RS-2	LASALLE	22	5	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 66D54							
PLOT DATE = 5/24/2019	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
SCALE:		SHEET NO. OF SHEETS		STA. TO STA.		REV. 6/25/19 REV 6/17/19 REV. 6/6/19				

MAINLINE SCHEDULE

STA. TO STA.	LENGTH	WIDTH	HMA SURF REM 3 3/4" (MAINLINE)	HMA SURF CSE N50 MIX C 1.75"	LVL BIND N50 1L-9.5 2"	LONG JOINT SEAL (1 APP)	LEVEL BINDER (HM)	MIX JTS, CRACKS & FLGWYS	BIT MAT'L TACK COAT	AGG SHLD WEDGE SHLDR TY B	TEMP RAMP	
	FT	FT	SQ YD	TONS	TONS	FOOT	TONS	TON	POUND	TONS	SQ YD	
577+05	578+98	193	27	579.0	56.7	64.8	193	0.29	0.17	390.8	13.7	23
RAILROAD OMISSION												
579+08	608+13	2905	27	8,715.0	854.1	976.1	2905	4.36	2.61	5,882.6	206.8	23
BRIDGE OMISSION 608+13 TO 610+07												
610+07	637+08	2701	27	8,103.0	794.1	907.5	2701	4.05	2.43	5,469.5	192.3	23
BRIDGE OMISSION 637+08 TO 639+71												
639+71	683+00	4329	27	12,987.0	1272.7	1454.5	4329	6.49	3.90	8,766.2	308.1	23
683+00	908+40	22540	27	67,620	6626.8	7573.4	22540	33.81	20.29	45,643.5	5348	23
TOTALS		32,668		98,004	9604	10,976	32,668	49	29	66,153	7079	113

* LONG JOINT SEAL UNDER CENTERLINE SURFACE LIFT

SIDEROAD SCHEDULE

STA	SIDE	LOCATION	MATERIAL	LENGTH	WIDTH	AREA	HMA SURF REM 1 1/2"	INC HMA SURF	TEMP RAMP	BIT MAT TACK CT	FURN EXCAV **	LANDSCAPING (FOR ESTIMATING)				
												EROS CNTRL BLANKET	SEED CL 2A	FERTILIZER		
				FOOT	FOOT	SQ YD	SQ YD	TON	SQ YD	POUND	CU YD	SQ YD	ACRE	POUND	POUND	POUND
577+93	LT	E 12TH RD	HMA	30	36	226.7	226.7	19.0	20.0	102.0	2.8	27	0.006	0.5	0.5	0.5
582+43	RT	E 12TH RD	HMA	30	54	303.3	303.3	25.5	30.0	136.5	2.2	21	0.004	0.4	0.4	0.4
624+30	LT	E 1251ST RD	HMA	85	25	566.7	566.7	47.6	13.9	255.0						
624+30	RT	E 1251ST RD	HMA	30	45	291.7	291.7	24.5	25.0	131.3	3.5	33	0.007	0.6	0.6	0.6
662+83	LT	GREENBRIAR RD	HMA	30	35	208.3	208.3	17.5	19.4	93.8	2.3	22	0.004	0.4	0.4	0.4
673+75	RT	E 1344TH RD	HMA	33	22	159.5	159.5	13.4	12.2	71.8	2.8	27	0.006	0.5	0.5	0.5
675+83	LT	RAVE ST	HMA	30	45	275.0	275.0	23.1	25.0	123.8						
683+00	LT	UNION ST/N 45TH RD	HMA	30	50	345.0	345.0	29.0	27.8	155.3	4.5	44	0.009	0.8	0.8	0.8
699+22	LT	E 14TH RD	HMA	30	30	196.7	196.7	16.5	16.7	88.5	2.8	27	0.006	0.5	0.5	0.5
699+32	RT	E 14TH RD	HMA	30	30	196.7	196.7	16.5	16.7	88.5	2.8	27	0.006	0.5	0.5	0.5
784+91	RT	E 1550TH RD	HMA	30	26	190.0	190.0	16.0	14.4	85.5	2.7	26	0.005	0.5	0.5	0.5
784+91	LT	E 1550TH RD	HMA	30	18	130.0	130.0	10.9	10.0	58.5	3.5	33	0.007	0.6	0.6	0.6
824+60	RT	E 1629TH RD	HMA	30	12	123.3	123.3	10.4	6.7	55.5	2.6	25	0.005	0.5	0.5	0.5
837+77	LT	E 1659TH RD	HMA	30	13	115.0	115.0	9.7	7.2	51.8	2.1	20	0.004	0.4	0.4	0.4
850+93	RT	E 1675TH RD	HMA	30	22	183.3	183.3	15.4	12.2	82.5	2.9	28	0.006	0.5	0.5	0.5
863+99	LT	E 17TH RD	HMA	30	20	145.0	145.0	12.2	11.1	65.3	2.4	23	0.005	0.4	0.4	0.4
TOTALS							3,656	307	268	1,645	40	382	0.08	7	7	7

** FURNISHED EXCAVATION AREAS TO BE SEEDED AND FERTILIZED AS DIRECTED BY THE RESIDENT. SEEDING, FERTILIZER AND EROSION CONTROL BLANKET ITEMS ARE INCLUDED IN THE COST OF FURNISHED EXCAVATION. REFER TO RESTORATION OF WORK AREA SPECIAL PROVISION.

US RTE. 34 LOCATION: E 12TH RD AT EARLVILLE TO IL 23 (S) LASALLE COUNTY

GPS NUMBER	DESCRIPTION	EXISTING MONUMENT TYPE	PROPOSED MONUMENT TYPE	MONUMENT RECORD TO BE RECORDED	RESPONSIBILITY
	E QUARTER CORNER SECTION 24, T36N, R2E, 3RD PM	BRASS DISK	TYPE 1	YES	1
	S QUARTER CORNER SECTION 15, T36N, R3E, 3RD PM	PK NAIL	TYPE 1	YES	1
	SW CORNER SECTION 13, T36N, R3E, 3RD PM *(LOCATED NORTH OF US RTE. 34 AT E 17TH RD. WILL REQUIRE INSPECTION TO DETERMINE LOCATION AND IF MONUMENT FALLS WITHIN CONSTRUCTION LIMITS)	UNKNOWN	*TYPE 1	YES	1

MISSING POINT NUMBERS WILL BE ASSIGNED. PRE CONSTRUCTION TIES ARE NOT REQUIRED. UNKNOWN MONUMENTS SET BY OTHERS MAY EXIST. IF FOUND, THE R.E. WILL DIRECT PLATS AND PLANS TO GPS ANY MONUMENT SUBJECT TO DESTRUCTION FROM THE RESURFACING WORK FOR THE PURPOSE OF RESETTING IT AFTER JOB COMPLETION. THE R.E. WILL DIRECT PLATS AND PLANS TO SEARCH FOR ADDITIONAL MONUMENTS IF THE CONSTRUCTION LIMITS ARE EXPANDED. UPON PAVING COMPLETION, THE R.E. WILL DIRECT PLATS AND PLANS TO STAKE THE LOCATIONS FOR TYPE 1 MONUMENT CORING. PLATS AND PLANS WILL PREPARE AND RECORD THE REQUIRED MONUMENT RECORDS.

RESPONSIBILITY:

- 1) RESIDENT TO RE-ESTABLISH MONUMENT (PAY ITEM REQUIRED. PERMANENT SURVEY MARKER, TYPE 1)
- 2) PLATS AND PLANS TO RE-ESTABLISH MONUMENT