



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 14, 2016

SUBJECT: FAU 6800 (US 150)  
Section 05-00500-19-GS / 50VB (Galesburg)  
Knox County  
Contract No. 89417  
Item 74  
July 29, 2016 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised page iii of the Index of Special Provisions.**
- 2. Revised page 38A of the Special Provisions.**
- 3. Revised sheet 13 of the Plans.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.  
Acting Bureau Chief of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger, P.E.".

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

RAILROAD FLAGGER.....	33
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.....	33
SIDEWALK REMOVAL .....	33
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES.....	34
RAILROAD TRACK REMOVAL.....	38A
PRELIMINARY SITE INVESTIGATION (PSI) REPORT.....	38A
NON-SPECIAL WASTE DISPOSAL .....	38A
ELECTRICAL SPECIAL PROVISIONS.....	39
ORNAMENTAL LIGHT UNIT, COMPLETE .....	39
LIGHTING CONTROLLER, BASE MOUNTED, 240 VOLT, 100 AMP (DUAL) .....	40
UNDERPASS LUMINAIRE (SPECIAL) .....	40
LUMINAIRE (SPECIAL).....	45
CCTV CAMERA INSTALLATION SPECIAL PROVISIONS.....	46
CONTRACT GUARANTEE .....	46
SYSTEM IMPLEMENTATION, EQUIPMENT INTEGRATION AND SUPPORT .....	46
LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES .....	47
CAT 5 ETHERNET CABLE .....	47
CLOSED-CIRCUIT TELEVISION DOME CAMERA.....	48
SUPPORT EQUIPMENT AND MAINTENANCE .....	53
FIBER OPTIC ETHERNET DROP AND REPEAT SWITCH.....	54
GROUNDING OF ITS STRUCTURES .....	57
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125 MM12F SM24F.....	57
FIBER OPTIC FUSION SPLICE .....	63
TERMINATION OF FIBER OPTIC CABLES WITH FUSION SPLICED ST CONNECTORS .....	66
TRAFFIC SIGNAL SPECIAL PROVISIONS .....	68
LOCATION OF UNDERGROUND STATE/CITY MAINTAINED ELECTRICAL FACILITIES ....	68
CONTRACT GUARANTEE .....	68
OPERATION OF EXISTING TRAFFIC SIGNALS .....	69
FULL-ACTUATED CONTROLLER AND TYPE IV CABINET .....	69
INDUCTIVE LOOP DETECTOR.....	70
TRAFFIC SIGNAL LED MODULE SPECIFICATIONS .....	71



## **RAILROAD TRACK REMOVAL**

This work shall consist of the removal and disposal of the existing railroad tracks in advance of the bridge change out. BNSF will cut the rail in 40 foot sections to be removed. The contractor will be responsible to provide labor and equipment to remove the track panels from the ballast and dispose of as noted below:

- Tracks #1 and #2: The removed track panel (rail and ties) shall become the property of the contractor and shall be removed and disposed of off BNSF right-of-way.
- Track #3: The track panel (rail and ties) will be salvaged. The track panels shall be delivered to 535 Quincy Street, Cameron, Illinois 61423. BNSF will be able to assist with unloading of the track panels.

Basis of Payment: This work shall be paid for at the contract unit price per foot for RAILROAD TRACK REMOVAL which shall be payment in full for all labor, tools and equipment necessary to complete the work.

## **PRELIMINARY SITE INVESTIGATION (PSI) REPORT**

An electronic copy of the Preliminary Site Investigation (PSI) Report is available for the contractor to review.

[http://www.ci.galesburg.il.us/city\\_initiatives/city\\_construction/](http://www.ci.galesburg.il.us/city_initiatives/city_construction/)

Once you go to the link, the two documents are on the right hand side of the page under "Documents" labeled as follows:

"Final PSI Report for the East Main Street Underpass"

"Exhibits for PSI Report for the East Main Street Underpass"

## **NON-SPECIAL WASTE DISPOSAL**



This work shall be performed in general accordance with applicable portions of Section 202 and Section 669 of the Standard Specifications.

When the soil analytical tests indicate that detected levels of contaminants exceed the minimum levels, the contractor will be responsible for the excavation, transportation and proper disposal of contaminated material in general accordance with applicable portions of Section 202 and Section 669 of the Standard Specifications.

Basis of Payment: This work shall be paid for at the contract unit price per cubic yard for NON-SPECIAL WASTE DISPOSAL which shall be payment in full for all labor, tools and equipment necessary to excavate, transport and dispose of the material.