

SUMMARY OF QUANTITIES

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	URBAN 90% FED. 10% STATE CONSTRUCTION TYPE CODE	
			TOTAL QUANTITIES	016-0519 SFTY-2A
20200100	EARTH EXCAVATION	CU YD	60	60
20700220	POROUS GRANULAR EMBANKMENT	CU YD	118	118
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	185	185
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	270	270
* 25000210	SEEDING, CLASS 2A	ACRE	0.06	0.06
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6	6
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6	6
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6	6
* 25100630	EROSION CONTROL BLANKET	SQ YD	270	270
* 28000400	PERIMETER EROSION BARRIER	FOOT	761	761
28000510	INLET FILTERS	EACH	4	4
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B, 6"	SQ YD	495	495
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	281	281
40600300	AGGREGATE (PRIME COAT)	TON	6	6
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	49	49
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	190	190
50300300	PROTECTIVE COAT	SQ YD	2,808	2,808
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	120	120
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1735	1735
44000100	PAVEMENT REMOVAL	SQ YD	389	389
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	1,939	1,939
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	627	627
44000600	SIDEWALK REMOVAL	SQ FT	2,335	2,335
44000700	APPROACH SLAB REMOVAL	SQ YD	498	498
44003100	MEDIAN REMOVAL	SQ FT	3,494	3,494
44004250	PAVED SHOULDER REMOVAL	SQ YD	58	58

* INDICATES SPECIALTY ITEMS

CODED PAY ITEM NUMBER	PAY ITEM	UNIT	URBAN 90% FED. 10% STATE CONSTRUCTION TYPE CODE	
			TOTAL QUANTITIES	016-0519 SFTY-2A
50102400	CONCRETE REMOVAL	CU YD	60.2	60.2
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1	1
50157300	PROTECTIVE SHIELD	SQ YD	1,545	1,545
50200100	STRUCTURE EXCAVATION	CU YD	185	185
50300225	CONCRETE STRUCTURES	CU YD	71.7	71.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	822.2	822.2
50300260	BRIDGE DECK GROOVING	SQ YD	1,404	1,404
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1
50500505	STUD SHEAR CONNECTORS	EACH	10,536	10,536
50501130	STRUCTURAL STEEL REPAIR	POUND	6,020	6,020
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	24	24
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1	1
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	181,980	181,980
50800515	BAR SPLICERS	EACH	1042	1042
50900105	ALUMINUM RAILING, TYPE L	FOOT	509	509
51100490	AGGREGATE SLOPE WALL 9"	SQ YD	165	165
51205200	TEMPORARY SHEET PILING	SQ FT	260	260
51500100	NAME PLATES	EACH	1	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	143	143
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12	12
52100030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	12	12
52100520	ANCHOR BOLTS, 1"	EACH	48	48
58700300	CONCRETE SEALER	SQ FT	942	942
59000200	EPOXY CRACK INJECTION	FOOT	63	63
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	86	86
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	1	1

* INDICATES SPECIALTY ITEMS

Rev.