

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY J000-2A	Y031-1F SIGNAL	Y030-1E LIGHTING	Y031-3D PREEMPTORS	100% VILLAGE OF ELK GROVE	CODE NO	ITEM	UNIT		ROADWAY J000-2A	Y031-1F SIGNAL	Y030-1E LIGHTING	Y031-3D PREEMPTORS	100% VILLAGE OF ELK GROVE
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	330	330				70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10					
20400800	FURNISHED EXCAVATION	CU YD	1281	1281				70400100	TEMPORARY CONCRETE BARRIER	FOOT	1000	1000					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	2351	2351				*72000100	SIGN PANEL - TYPE 1	SO FT	15		15				
25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5				*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	800	800					
25000300	SEEDING, CLASS 3	ACRE	0.5	0.5				*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	100	100					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90				*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90				*78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	610	610					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90				*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1400	1400					
25200200	SUPPLEMENTAL WATERING	UNIT	25	25				*78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	60	60					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60	60				*78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1650	1650					
28000305	TEMPORARY DITCH CHECKS	FOOT	200	200				*78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	150	150					
28000400	PERIMETER EROSION BARRIER	FOOT	800	800				*78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	500	500					
35200600	EARTH EXCAVATION	CU YD	275	275				*78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	150	150					
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SO YD	960	960				*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20					
42001300	PROTECTIVE COAT	SO YD	1460	1460				78300100	PAVEMENT MARKING REMOVAL	SO FT	800	800					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	650	650				*81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	536		536				
44000100	PAVEMENT REMOVAL	SO YD	410	410				*81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	153		153				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	200	200				*81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	10		10				
44000600	SIDEWALK REMOVAL	SO FT	560	560				*81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	36		36				
44003100	MEDIAN REMOVAL	SO FT	2600	2600				*81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	41		41				
44004250	PAVED SHOULDER REMOVAL	SO YD	350	350				*81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	300		300				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	190	190				*81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	519		519				
48300505	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	SO YD	370	370				*81400100	HANDHOLE	EACH	2		2				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3				*81400200	HEAVY-DUTY HANDHOLE	EACH	2		2				
60107600	PIPE UNDERDRAINS 4"	FOOT	800	800				*81400300	DOUBLE HANDHOLE	EACH	3		3				
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	100	100				*81603203	UNIT DUCT, 600V, 3-1C NO. 2, 1/C NO. 4 GROUND, (EPR-TYPE RHW), 1 1/2" DIA. POLYETHYLENE	FOOT	1200		1200				
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	1	1													
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	200	200													
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SO FT	2600	2600													
63500105	DELINEATORS	EACH	16	16													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1													

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = kellers	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>I-290 SB EXIT RAMP TO BIESTERFIELD ROAD SUMMARY OF QUANTITIES</b>	F.A.T. RTE. 290	SECTION 0101-311 HBK-1	COUNTY COOK	TOTAL SHEETS 44	SHEET NO. 3		
g:\p\work\PI\DOT\KELLERS\0155790\PI4009-Desig.dgn	DRAWN -	REVISED -	SCALE:			SHEET NO. OF SHEETS STA.	TO STA.	CONTRACT NO. 60J32				
PLOT SCALE = 50,000' / 1" IN.	CHECKED -	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT									
PLOT DATE = 5/7/2010	DATE -	REVISED -										