



INTERCONNECT SCHEDULE OF QUANTITIES		
PAY ITEM	UNIT	QUANTITY
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1961
WIRELESS INTERCONNECT (COMPLETE)	EACH	1
REMOVE FIBER OPTIC CABLE FROM CONDUIT	FOOT	1984

NOTE:
 1. THE PROPOSED RADIO ANTENNA SHALL BE MOUNTED ON THE EXISTING MAST ARM POLE NEAREST TO THE CONTROLLER. THIS WORK SHALL BE PAID FOR AS "WIRELESS INTERCONNECT (COMPLETE)."

NOTE:
 THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

FILE NAME = #FILES#	USER NAME = #USER#	DESIGNED - BRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INTERCONNECT SCHEMATIC IL ROUTE 53 (BIESTERFIELD RD.)			F.A.I. RTE. 290	SECTION 0101-311 HBK-1	COUNTY COOK	TOTAL SHEETS 44	SHEET NO. 24
	PLOT SCALE = #SCALE#	DRAWN - OJT	REVISED -		NOT TO SCALE	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				
	PLOT DATE = #DATE#	CHECKED - JJE	REVISED -									
		DATE - 04/22/2010	REVISED -									