

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			TOTAL QUANTITY 100% STATE	CONSTRUCTION TYPE CODE
			Y007	DRAINAGE QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	3	3
20101000	TEMPORARY FENCE	FOOT	811	811
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	48	48
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	48	48
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	48	48
20200100	EARTH EXCAVATION	CU YD	54	54
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100
20400800	FURNISHED EXCAVATION	CU YD	779	779
20800150	TRENCH BACKFILL	CU YD	18	18
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3813	3813
25000210	SEEDING, CLASS 2A	ACRE	0.8	0.8
25100630	EROSION CONTROL BLANKET	SQ YD	3813	3813
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	78.8	78.8
28000400	PERIMETER EROSION BARRIER	FOOT	129	129
28000500	INLET AND PIPE PROTECTION	EACH	4	4
28100127	STONE RIPRAP, CLASS B4	SQ YD	15	15
28200200	FILTER FABRIC	SQ YD	15	15
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	815	815
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	815	815
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	94	94
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4	4
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1	1
55038200	STORM SEWERS TO BE CLEANED 24"	FOOT	78	78
67100100	MOBILIZATION	L SUM	1	1
60207000	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
66410300	CHAIN LINK FENCE REMOVAL	FOOT	830	830

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			TOTAL QUANTITY 100% STATE	CONSTRUCTION TYPE CODE
			Y007	DRAINAGE QUANTITY
66410700	CHAIN LINK GATES (SPECIAL)	EACH	1	1
66400560	CHAIN LINK FENCE, 6' (SPECIAL)	FOOT	868	868
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	95	95
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	25	25
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	455	455
Z0055905	TEMPORARY CONSTRUCTION FENCE	FOOT	569	569
X0976500	END SECTIONS TO BE REMOVED	EACH	2	2
Z0013798	CONSTRUCTION LAYOUT	LSUM	1	1

FILE NAME = P:\2009\ME0906_Ver-Vor-Ph11\CADD\W013_IL38\Shets\03-DIG0K16-sh1-IL38-500.DGN
 USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.705.0110 voice, 630.839.2566 fax
 WWW.MPS-IL.COM
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 6/1/2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 38
AT PECK ROAD**

SUMMARY OF QUANTITIES

F.A.P. RTE. 347	SECTION 4 R-T	COUNTY KANE	TOTAL SHEETS 20	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60K16	

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

P:\2009\ME0906_Ver-Vor-Ph11\CADD\W013_IL38\Shets\03-DIG0K16-sh1-IL38-500.DGN