

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	228	228						70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
25200110	SODDING, SALT TOLERANT	SO YD	228	228						70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
25200200	SUPPLEMENTAL WATERING	UNIT	3	3						70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9492	9492					
35800200	AGGREGATE BASE REPAIR	TON	100	100						70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	666	666					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	46	46						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	33021	33021					
40600300	AGGREGATE (PRIME COAT)	TON	229	229						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3948	3948					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	86	86						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	607	607					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	2359	2359						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	478	478					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3164	3164					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	573	573					*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	666	666					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	463	463					*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33021	33021					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5604	5604					*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3948	3948					
42001300	PROTECTIVE COAT	SO YD	333	333					*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	607	607					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	22	22					*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	478	478					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	57183	57183					*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	715	715					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	22	22						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	572	572					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1500	1500					*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1250	1250					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	2068	2068					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4						
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	865	865					X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	7	7						
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	479	479					Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	105	105						
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	500	500															
Δ 55039700	STORM SEWERS TO BE CLEANED	FOOT	200	200															
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	10	10															
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	90	90															
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2															
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2															
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1500	1500															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															

Δ NON-PARTICIPATING
* SPECIALTY ITEMS