

SPECIALTY ITEMS	SPECIAL PROVISION	PAY ITEM #	PAY ITEM	UNIT	SOUTH LOT QUANTITY	NORTH LOTS QUANTITY	COMPASS LOT QUANTITY	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
									ROADWAY 100-2A	LIGHTING Y030-1E
		20200100	EARTH EXCAVATION	CU YD	1,202	1,073	4,687	6,962	6,962	0
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	121	108	469	698	698	0
	*	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	121	108	469	698	698	0
		20800150	TRENCH BACKFILL	CU YD	19	7	60	86	86	0
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	265	288	1,329	1,882	1,882	0
o	*	25200850	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	798	898	2,998	4,694	4,694	0
o	*	25300700	TRANSPLANTED SALVAGED SHRUBS	EACH	25	25	0	50	50	0
		28000400	PERIMETER EROSION BARRIER	FOOT	833	779	1,818	3,430	3,430	0
		28000510	INLET FILTERS	EACH	7	4	17	28	28	0
	*	28101400	RIPRAP	SQ YD	36	0	0	36	36	0
		28200200	FILTER FABRIC	SQ YD	36	0	0	36	36	0
		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1,929	2,371	2,736	7,036	7,036	0
		35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	1,929	2,371	2,736	7,036	7,036	0
		40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	675	830	958	2,463	2,463	0
		40800300	AGGREGATE (PRIME COAT)	TON	5	6	7	18	18	0
		40800982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	342	54	89	485	485	0
		40803080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	270	332	384	986	986	0
		40803335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	163	200	230	593	593	0
		42000100	PORTLAND CEMENT CONCRETE PAVEMENT 6"	SQ YD	0	0	45	45	45	0
	*	42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	551	484	3,914	4,949	4,949	0
		42400800	DETECTABLE WARNINGS	SQ FT	6	0	12	18	18	0
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	373	77	133	583	583	0
		44000600	SIDEWALK REMOVAL	SQ FT	596	0	451	1,047	1,047	0
	*	44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	0	0	148	148	148	0
		550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	0	0	197	197	197	0
		60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SQ YD	0	0	534	534	534	0
	*	60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	0	0	765	765	765	0
	*	60202710	CATCH BASINS, TYPE A, 4' DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	0	0	4	4	4	0
	*	60209510	CATCH BASINS, TYPE C, WITH SPECIAL FRAME AND GRATE	EACH	0	0	5	5	5	0
	*	60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	1	1	0	2	2	0
	*	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2	3	7	7	0
	*	60804200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	1,111	1,242	3,486	5,839	5,839	0
	*	66411900	TEMPORARY FENCE (SPECIAL)	FOOT	833	779	1,821	3,233	3,233	0
		67100100	MOBILIZATION	L SUM	0	0	0	1	1	0
		70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	0	0	0	1	1	0
		72000100	SIGN PANEL - TYPE 1	SQ FT	31.75	6.25	6.25	44.25	44	0
	*	72400900	REMOVE SIGN PANEL	EACH	1	0	0	1	1	0
		72900100	METAL POST - TYPE A	FOOT	36	33	174	243	243	0
o		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	810	1,129	5,343	7,282	7,282	0
o		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	59	0	0	59	59	0
o		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	27	16	12	55	55	0
o	*	78000100	PAVEMENT MARKING REMOVAL	SQ FT	0	150	0	50	50	0
o		81000400	CONDUIT IN TRENCH, 1 1/4" DIA., GALVANIZED STEEL	FOOT	0	100	2,000	2,100	0	2,100
o		81400100	HANDHOLE	EACH	0	1	17	18	0	18
o		81900200	TRENCH BACKFILL FOR ELECTRICAL WORK	FOOT	0	100	2,000	2,100	0	2,100
o	*	83600100	LIGHT POLE FOUNDATION	EACH	0	1	16	17	0	17
o	*	84700200	REMOVAL OF POLE FOUNDATION	EACH	0	1	0	1	0	1
o		A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2	7	11	11	0
o		A2004616	TREE, GLEDITSIA TRIACANTHOS INERMIS (THORNLESS COMMON HONEYLOCUST), 2" CALIPER, BALLED AND BURLAPPED	EACH	1	1	4	6	6	0
o		A2005420	TREE, LIRIODENDRON TULIPIFERA (TULIP TREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	1	1	2	4	4	0
o		A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2	14	18	18	0
o		A2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	1	1	2	4	4	0
o		A2007620	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	4	9	15	15	0
o		A2007820	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	1	1	2	4	4	0
o		A2008453	TREE ULMUS ACCOLADE (HYBRID ELM), 3" CALIPER, BALLED AND BURLAPPED	EACH	2	2	9	13	13	0
o		A20056G3	TREE, QUERCUS MACROCARPA (BURR OAK), CONTAINER GROWN, 3-GALLON	EACH	1	1	3	5	5	0
o		C2C11026	SHRUB, SYRINGA PATULA MISS KIM (MISS KIM MANCHURIAN LILAC), 30" HEIGHT, 5-GALLON CONTAINER	EACH	25	25	40	90	90	0
o		D2002772	EVERGREEN, PINUS NIGRA (AUSTRIAN PINE) 6' HEIGHT, BALLED AND BURLAPPED	EACH	0	0	4	4	4	0
o		D2002972	Evergreen Pine Shrubs (EASTERN WHITE PINE) 6' HEIGHT, BALLED AND BURLAPPED	EACH	0	0	4	4	4	0
o		D2000090	Evergreen Pines Balsam (BALSAM FIR) 6' HEIGHT, BALLED AND BURLAPPED	EACH	0	0	4	4	4	0
o		D2000100	Evergreen Pines Amurica (SERBIAN SPRUCE) 6' HEIGHT, BALLED AND BURLAPPED	EACH	0	0	4	4	4	0
o	*	X0321309	CONCRETE PAD	SQ YD	0	0	20	20	20	0
o	*	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	251	134	167	552	552	0
o	*	X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	1	1	2	4	4	0
o	*	X0323857	EXISTING LIGHT POLE FOUNDATION ADJUSTMENT	EACH	2	0	0	2	0	2
o	*	X0324182	ELECTRICAL CABLE IN CONDUIT, TRIPLEX NO. 6, 2-1C AND NO. 8, 1-1C	FOOT	0	100	2,176	2,276	0	2,276
o	*	X2110104	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	798	898	2,998	4,694	4,694	0
o	*	X0001249	ORNAMENTAL FENCE	FOOT	0	46	320	366	366	0
o	*	X0007275	LIGHTING UNIT A, COMPLETE	EACH	0	0	10	10	0	10
o	*	X0007276	LIGHTING UNIT B, COMPLETE	EACH	0	0	6	6	0	6
o	*	X0005690	STORM SEWER, DUCTILE IRON PIPE, CLASS 5212"	FOOT	68	29	0	97	97	0
o	*	X0006834	ELECTRICAL CONNECTION TO EXISTING LIGHTING SYSTEM	EACH	0	0	1	0	1	0
o	*	X0008327	AERIAL MOUNTED PARKING STALL NUMBER SIGNS	EACH	0	0	86	86	86	0
o	*	X0007160	AGGREGATE BASE COURSE, SPECIAL	SQ YD	0	0	8,400	8,400	8,400	0
o	*	X0008336	POROUS CONCRETE PAVEMENT, 6"	SQ YD	0	0	8,400	8,400	8,400	0
o	*	X0008330	BIOSWALE	SQ YD	0	0	1,386	1,386	1,386	0
o	*	X0008331	FARE COLLECTION MACHINE	EACH	0	0	2	2	2	0
o	*	X0008332	FARE COLLECTION MACHINE SHELTER	L SUM	0	0	1	1	1	0
o	*	X0008333	GROUND MOUNTED PARKING STALL NUMBER SIGNS	EACH	32	33	105	170	170	0
o	*	X0008334	HANDICAP STALL RESTRIPING AND SIGNAGE	EACH	0	8	0	8	8	0
o	*	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	0	1	0	1	1	0
o	*	Z0017100	DOWEL BARS	EACH	0	0	2,000	2,000	2,000	0

PLANS PREPARED BY: 	SURVEY - DJG	DESIGNED - DJG	REVISED - 10/05/09 PER BLRS
	UTILITIES - JC	DRAWN - DJG	REVISED - 12/03/09 VOG
	CHECKED - DJG	CHECKED - LVA	REVISED -
	DATE - 04-23-09	DATE - 09-17-09	REVISED -

**VILLAGE OF GLENVIEW
PROJECT E 08-56**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 3 OF 24 SHEETS

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
NA	08-00169-00-PK	COOK	24	3
			CONTRACT NO. 63360	
ILLINOIS FED. AID PROJECT				