

SUMMARY OF QUANTITIES

ROADWAY 1000-2A					
SP	DDOT PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	PARTICIPATING
	25000110	SEEDING, CLASS 1A	ACRE	0.03	0.03
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,100	1,100
	40600300	AGGREGATE (PRIME COAT)	TON	30	30
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	145	145
	40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	10	10
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,350	1,350
	42001300	PROTECTIVE COAT	SQ YD	50	50
	42400800	DETECTABLE WARNINGS	SQ FT	60	60
	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	9,450	9,450
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	750	750
	44006600	SIDEWALK REMOVAL	SQ FT	500	500
	42400200	PC CONCRETE SIDEWALK 5"	SQ FT	500	500
	44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	5	5
	44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	15	15
	44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	25	25
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
	60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	41	41
	60406500	FRAMES AND LIDS, SPECIAL	EACH	2	2
	67100100	MOBILIZATION	L SUM	1	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	700	700
△	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150

ROADWAY 1000-2A					
SP	DDOT PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	PARTICIPATING
△	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,700	5,700
△	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	930	930
△	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	290	290
△	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	100	100
△	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100
△	88600600	DETECTOR LOOP REPLACEMENT	FOOT	324	324
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	130	130
	Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	100	100

△ SPECIALTY ITEMS

PLOT DATE = 08/19/09
 USER NAME = RUSBY
 PLOT SCALE = 8/SCALE
 FILE NAME = 07FILEP

Burns & McDonnell
 1431 OPUS PLACE, SUITE 400
 DOWNERS GROVE, IL 60515
 PHONE: (630) 724-3200
 FAX: (630) 724-3201
 WEB: WWW.BURNSMCD.COM

DESIGNED - RB	REVISED -	REVISED -
CHECKED - JMT	REVISED -	REVISED -
DRAWN - RB	REVISED -	REVISED -
CHECKED - 08/19/09	REVISED -	REVISED -

**VILLAGE OF GLENVIEW
 GLENVIEW ROAD RESURFACING
 PROJECT (EAST)**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1297	09-00173-00-RS	LAKE	15	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63361	