



- NOTES:
1. REMOVE AND REPLACE SIDEWALK IN WHOLE PANELS. A LENGTH OF 10 FEET IS ASSUMED AT ALL LOCATIONS.
 2. SIZE AND LOCATION OF DETECTOR LOOPS SHALL BE FIELD VERIFIED. REPLACEMENT SHALL BE INSTALLED IN ACCORDANCE WITH IDOT DISTRICT ONE STANDARD TS-07 FOR DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING. SEE SHEET 17.
 3. RESURFACING IS PAID FOR AS HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 2 1/2".
 4. RESURFACING EXTENDS 10 FEET DOWN THE SIDE STREETS UNLESS OTHERWISE NOTED.

PLOT DATE = #DATE#
 USER NAME = #USER#
 PLOT SCALE = #SCALE#
 FILE NAME = #FILE#

Burns & McDonnell
 1431 OPUS PLACE, SUITE 400
 DOWNERS GROVE, IL 60515
 PHONE: (630) 724-3200
 FAX: (630) 724-3201
 WEB: WWW.BURNSMCD.COM

DESIGNED - RB	REVISED -	REVISED -
CHECKED - JMT	REVISED -	REVISED -
DRAWN - RB	REVISED -	REVISED -
CHECKED - 08/19/09	REVISED -	REVISED -

**VILLAGE OF GLENVIEW
 GLENVIEW ROAD RESURFACING
 PROJECT (EAST)**

PROPOSED RESURFACING PLAN
 SCALE: 1"=30' SHEET NO. 1 OF 5 SHEETS STA. 10+00.00 TO STA. 32+50.00

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1297	09-00173-00-RS	LAKE	16	5
CONTRACT NO. 63361			ILLINOIS FED. AID PROJECT	