



WHITEHALL AVENUE

WOLF ROAD

ADDISON CREEK

NOTES:

- CONTRACTOR SHALL DISCONNECT AND CUT EXISTING TRAFFIC SIGNAL CABLES AND CONDUIT TO A MINIMUM OF 1' BELOW GRADE AND ABANDON. CONTRACTOR MAY ELECT TO REMOVE CABLES AND SALVAGE AT NO ADDITIONAL COST TO THE OWNER. WORK INCLUDED IN COST FOR REMOVING HANDHOLE.
- EXISTING CONCRETE HANDHOLE SHALL BE REMOVED AND DISPOSED OF ACCORDING TO SECTION 895 IN THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION. THE HANDHOLE SHALL BE COMPLETELY REMOVED, BACKFILLED WITH IDOT APPROVED MATERIAL AND THE SURFACE RESTORED TO SURROUNDING CONDITIONS.

LEGEND:

- PAVEMENT REMOVAL
- EXISTING PAVEMENT SURFACE OVER BRIDGE DECK AND SIDEWALK TO BE REMOVED
- HOT-MIX ASPHALT SURFACE REMOVAL, 2"
- SIDEWALK REMOVAL
- CONCRETE CURB AND GUTTER REMOVAL
- FENCE REMOVAL (PAID FOR AS CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED)

FILE NAME =	USER NAME = PRAZALAN	DESIGNED - AMP	REVISED -
\\NORTHLAKE\940032HR204\Civil\rem_940032hr204.sht		DRAWN - EDT	REVISED -
PLOT SCALE = 10"		CHECKED - MEW	REVISED -
PLOT DATE = 11/30/2009		DATE - 09/30/09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**EXISTING CONDITIONS AND REMOVAL PLAN
WHITEHALL AVENUE**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
---	09-00071-00-BR	COOK	31	7
			CONTRACT NO. 63437	
ILLINOIS FED. AID PROJECT				