

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONST. CODE I000 TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3634
40600300	AGGREGATE (PRIME COAT)	TON	76
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD) IL-4.75, N50	TON	1523
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	185
40600990	TEMPORARY RAMP	SQ YD	51
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4073
42400800	DETECTABLE WARNINGS	SQ FT	54
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	36334
44000195	HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL	SQ YD	276
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1457
44000600	SIDEWALK REMOVAL	SQ FT	623
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	4
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	41
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	291
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	724
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2
60260100	INLETS TO BE ADJUSTED	EACH	29
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	31
67100100	MOBILIZATION	L SUM	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	623

Δ SEE SPECIAL PROVISIONS

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONST. CODE I000 TOTAL QUANTITY
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4356
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	213
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21375
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1552
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	255
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	194
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1455
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	213
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21375
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1552
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	255
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	194
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	410
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	410
Δ * 81400115	HANDHOLE TO BE ADJUSTED	EACH	1
Δ * 88600600	DETECTOR LOOP REPLACEMENT	FOOT	634
Δ X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52
Δ XX006425	RESTORATION	SQ YD	336
Δ Z0004538	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 10"	SQ YD	275
Δ Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

Δ SEE SPECIAL PROVISIONS

* SPECIALTY ITEMS

Plotted: May 20, 2010 @ 2:11 PM By: Larry Nolan - Tab: 03 Quantities - 22x34

COPYRIGHT © 2010 ENGINEERING ENTERPRISES, INC.



Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
630.466.6700 / www.eeiweb.com

CITY OF ELGIN

NO.	DATE	REVISIONS

**BIG TIMBER ROAD
LAPP IMPROVEMENTS**

SUMMARY OF QUANTITIES

DATE: MARCH 2010
PROJECT NO: EG0908
FILE: EG0908-CVR
SHEET **3** OF **20**

Path: H:\S\B\K\PROJ\EG0908\DWG\FINAL_ENG\EG0908-CVR