

FUNDING CODE YO31-1F(80% CMAQ / 20% DUPAGE COUNTY)

PAY CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITIES	FUNDING CODE															
				75TH STREET INTERCONNECT	75TH ST & RANCHVIEW DR	75TH ST & GREENE RD	75TH ST & ILL RTE E3	75TH ST & WOODRIDGE DR	75TH ST & JAMES AVE	COUNTY FARM ROAD INTERCONNECT	COUNTY FARM RD & BIRCHBARK TR	COUNTY FARM RD & LIES RD	COUNTY FARM RD & KELLY DR	COUNTY FARM RD & ARMY TRAIL RD	COUNTY FARM RD & ILLINOIS CENTRAL RR	COUNTY FARM RD & SCHICK RD	ARMY TRAIL & SPRING VALLEY DR	ARMY TRAIL & WOODLAKE DR	
67100100	MOBILIZATION	L SUM	1	0.11	0.06	0.06	0.06	0.06	0.06	0.11	0.06	0.06	0.06	0.06	0.06	0.06	0.06		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.11	0.06	0.06	0.06	0.06	0.06	0.11	0.06	0.06	0.06	0.06	0.06	0.06	0.06		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.11	0.06	0.06	0.06	0.06	0.06	0.11	0.06	0.06	0.06	0.06	0.06	0.06	0.06		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.11	0.06	0.06	0.06	0.06	0.06	0.11	0.06	0.06	0.06	0.06	0.06	0.06	0.06		
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	24383	12557						11826									
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	20					20											
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1798	834						1164									
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	27					27											
81019100	CONDUIT PUSHED, 6" DIA., GALVANIZED STEEL	FOOT	120											120					
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	120	120															
81300720	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 12" X 8"	EACH	2	2															
81400100	HANDHOLE	EACH	49	22						27									
81400200	HEAVY-DUTY HANDHOLE	EACH	8	8															
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	24383	12557						11826									
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	4										4						
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	12		1	1	1	1	1		1	1	1	1	1	1	1		
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	6				1	1			1	1	1				1		
88400100	TRANSCEIVER - FIBER OPTIC	EACH	9		1	1	1	1			1	1	1	1	1		1		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	45				45												
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT	EACH	11					4	4					3					
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	2					2											
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 36 FT	EACH	3										3						
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16					16											
87900200	DRILL EXISTING HANDHOLE	EACH	16		1	2	2	2	1		1	2	1		1	1	2		
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	12					6	6										
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2					2											
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4						4										
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	6					4	2										
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2						2										
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	10					2	4				4						
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	5					2	1				2						
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	16					6	10										
88500100	INDUCTIVE LOOP DETECTOR	EACH	66				12	10	10		8	8	10				8		
88800100	PEDESTRIAN PUSH BUTTON	EACH	28					6	6				8				8		
88500100	RELOCATE EXISTING SIGNAL HEAD	EACH	9										9						
89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	4					2					2						
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	7				1	1	1		1	1	1				1		
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1644					804	240				800						
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	11		1	1	1	1	1		1	1	1	1	1	1	1		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	4					4											
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	31330	15890						15440									
X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	3								1		1			1			
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	7		1	1	1	1	1				1			1	1		
X8820020	UNINTERRUPTIBLE POWER SUPPLY	EACH	3					1	1				1						
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	852		56	45	71	165		21		273	120		25	32	44		
X0325705	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	14		1	1	1	1	3	1	1	1	1	1	1	1	1		
XX003865	REBUILD EXISTING HANDHOLE TO DOUBLE HANDHOLE	EACH	1					1											
XX006654	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	31330	15890						15440									
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1											1					

*SPECIALTY ITEMS

REVISIONS	
NO.	DATE

DUPAGE COUNTY DIVISION OF TRANSPORTATION
SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 4/23/10

DRAWN BY: IN
DESIGNED BY: IN
CHECKED BY: IN