

GENERAL NOTES
(Revised May 13, 2009)

ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE PRESENCE OF DEPARTMENT-OWNED UNDERGROUND ELECTRICAL CABLE WITHIN THE LIMITS OF THE PROPOSED IMPROVEMENT. THE CONTRACTOR SHALL REQUEST THE ILLINOIS DEPARTMENT OF TRANSPORTATION IN OTTAWA (815-434-8417) TO LOCATE THE UNDERGROUND FACILITIES, PROVIDING A MINIMUM OF 72 HOURS NOTICE. THE DEPARTMENT IS NOT A MEMBER OF THE JOINT UTILITY-LOCATING INFORMATION FOR EXCAVATORS (JULIE) SYSTEM.

ALL DAMAGE TO DEPARTMENT OWNED UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE. THIS SHALL INCLUDE ALL TEMPORARY REPAIRS REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS. SPLICING OF ELECTRIC CABLE SHALL NOT BE ALLOWED. ELECTRIC CABLE SHALL BE REPLACED FROM POLE TO POLE OR CONTROLLER.

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

SUMMARY OF QUANTITIES

		FUND CODE TYPE:		L01E
		CONSTRUCTION CODE TYPE:		Y007
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	90% FED. 10% STATE ROADWAY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	105	105
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16	16
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9
* 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	9	9
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	64	64
25000300	SEEDING, CLASS 3	ACRE	0.1	0.1
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	466	466
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10
50200100	STRUCTURE EXCAVATION	CU YD	220	220
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	36	36
59000200	EPOXY CRACK INJECTION	FOOT	35	35
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	33	33
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	1	1
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	97	97
67100100	MOBILIZATION	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30
70400100	TEMPORARY CONCRETE BARRIER	FOOT	420	420
78300100	PAVEMENT MARKING REMOVAL	SQ FT	84	84
* X0326725	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 6"	FOOT	250	250
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	60	60
X7010820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	LSUM	1	1
* X7030100	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III	FOOT	1825	1825
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1
Z0073700	TEMPORARY WALL BRACING SYSTEM	L SUM	1	1
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	1	1
XX007265	WALL RESTRAINING ANCHORS	EACH	14	14

*SPECIALTY ITEMS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: Tom Bussil
ACTING DISTRICT STUDIES & PLANS ENGINEER

DATE: _____

EXAMINED BY: Hubert Jung
DISTRICT CONSTRUCTION ENGINEER

Wayne P. Peltz
DISTRICT MATERIALS ENGINEER

Bruce Tucker
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = braboygc	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pw\work\p\dot\braboygc\d0179153\d366	23-sht-details.dgn	DRAWN -	REVISED -			-57-	(46-3)-1-2	KANKAKEE	10	2	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	REVISED -			CONTRACT NO. 66A23					
PLOT DATE = May 13, 2010 - 12:43:53 PM	DATE -	REVISED -	REVISED -			ILLINOIS FED. AID PROJECT					

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____