

STAGE CONSTRUCTION ITEMS							
LOCATION		TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS NRD,TL3	WORK ZONE PVT MK REMOVAL(1)	PAVEMENT MARKING REMOVAL(2)	WET REFLECTIVE PREFORMED PLASTIC PVT MKS-LINE 6" (3)	WET TEMP PVT MK TAPE, TYPE III-4"
STA	LENGTH	FOOT	EACH	SQ FT	SQ FT	FOOT	WHITE FOOT
SBL	212+75 TO 231+00	1825		608	84.0	250.0	1825.0
SBL	226+80 TO 231+00	420	420.0	1			
<b>TOTALS</b>		<b>420.0</b>	<b>1.0</b>	<b>608.0</b>	<b>84.0</b>	<b>250.0</b>	<b>1825.0</b>

(1) WK ZONE PVT MK REMOVAL IS TO REMOVE THE WET TEMP PVT MK TAPE  
(2) PAVEMENT MARKING REMOVAL IS TO REMOVE EXISTING PAVEMENT MARKINGS PRIOR TO STAGE CONSTRUCTION  
(3) FOR PERMANENT USE TO BE PLACE AT CENTERLINE AT JOB COMPLETION

FILE NAME =	USER NAME = braboygo	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cd:\pw\work\p\dot\braboygo\d0179153\ad368423-sht-details.dgn	DRAWN -	REVISED -	57			(46-3) I-2	KANKAKEE	10	3	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 66A23							
PLOT DATE = May 13, 2010 - 12:44:35 PM	DATE -	REVISED -	SCALE: _____			SHEET NO. ____ OF ____ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT		