

SUMMARY OF QUANTITIES

LOCATION OF WORK: FAS 1514 (IL 10)
 CHAMPAIGN COUNTY
 S.N.010-8135
 STA. 336+00.00
 TO
 STA. 342+00.00
 RURAL 2-LANE
 80% FED 20% STATE
 Y007

LOCATION OF WORK: FAS 1514 (IL 10)
 CHAMPAIGN COUNTY
 S.N.010-8135
 STA. 336+00.00
 TO
 STA. 342+00.00
 RURAL 2-LANE
 80% FED 20% STATE
 Y007

CONSTRUCTION TYPE CODE:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY
20700220	POROUS GRANULAR EMBANKMENT	CU YD	140.0
21400100	GRADING AND SHAPING DITCHES	FOOT	340.0
25000200	SEEDING, CLASS 2	ACRE	0.10
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10.0
25100115	MULCH, METHOD 2	ACRE	0.10
25100630	EROSION CONTROL BLANKET	SQ YD	25.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10.0
28000305	TEMPORARY DITCH CHECKS	FOOT	100.0
28000400	PERIMETER EROSION BARRIER	FOOT	415.0
28000500	INLET AND PIPE PROTECTION	EACH	6.0
28100201	STONE RIPRAP, CLASS A1	TON	55.0
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	200.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	65.0
40600300	AGGREGATE (PRIME COAT)	TON	0.25
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	2.0
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	104.0

CODE NO	ITEM	UNIT	TOTAL QUANTITY
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	20.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
51500100	NAME PLATES	EACH	1.0
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	2.0
54020802	PRECAST CONCRETE BOX CULVERT 8' X 2' (M273)	FOOT	40.0
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	185.0
61101016	STORM SEWERS PROTECTED, CLASS A, 14"	FOOT	80.0
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	2.0
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	1.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	500.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2.0
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	500.0
X6660410	REMOVE RIGHT-OF-WAY MARKERS	EACH	1.0
XX005655	STORM SEWER REMOVAL UNDER 18"	FOOT	80.0
• SPECIALTY ITEMS			