SUMMARY OF QUANTITITES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	MAINLINE, SIDEROADS 100% STATE I000	PARKING LANES 100% STATE Y025
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	17	17	
31101300	SUB-BASE GRANULAR MATERIAL, TYPE B 5"	SQ YD	7	7	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19.9	19.7	0.2
40600300	AGGREGATE (PRIME COAT)	TON	107	105	2
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600990	TEMPORARY RAMP	SQ YD	807	807	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5,304	5,237	67
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	557	557	
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SY YD	17	17	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	282	282	
44000100	PAVEMENT REMOVAL	SQ YD	17	17	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	51,069	50,470	599
44000600	SIDEWALK REMOVAL	SQ FT	282	282	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	761	761	
44004250	PAVED SHOULDER REMOVAL	SQ YD	492	492	
44200140	PAVEMENT PATCHING TYPE I, 12 INCH	SQ YD	15	15	
44200144	PAVEMENT PATCHING TYPE II, 12 INCH	SQ YD	196	196	

*-20RS-7, 21-6, 104RS, 105RS-4
**- 325, 42

FILE NAME = c:\pw_work\PWIDOT\LAUGHLINRL\d0105356\D72C52-sht-S00.dgn	USER NAME = laughlinrl	DESIGNED - RTS	REVISED -
		DRAWN - RTS	REVISED -
	PLOT SCALE = 135.0000 ' / IN.	CHECKED - MEB	REVISED -
	PLOT DATE = Mar-26-2010 11:52:58AM	DATE - 3-10-10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 1 OF 3 SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	MONTGOMERY	60	3
		CONTRACT NO. 72C52		
		ILLINOIS FED. AID PROJECT		