

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 6"		
LOCATION (STATION OR ROAD)	DESCRIPTION	QUANTITY (FOOT)
IL RT. 16 / IL RTE. 127		
33+40.00 TO 34+30.00	6' SKIP - 2' DASH LINE, WHITE	32.0
38+38.75 TO 39+58.00	6' SKIP - 2' DASH LINE, WHITE	30.0
39+58.00 TO 41+17.33	LEFT TURN LANE LINE, WHITE	157.3
41+27.33	PEDESTRIAN CROSSWALK (2 @ 42.4'), WHITE	84.8
WOOD STREET (EAST)	PEDESTRIAN CROSSWALK (32.0', 30.5'), WHITE	62.5
WOOD STREET (WEST)	PEDESTRIAN CROSSWALK (31.5', 24.0'), WHITE	55.5
PLEASANT STREET	PEDESTRIAN CROSSWALK (22.5', 20.0'), WHITE	42.5
SUB-TOTALS =		464.6
IL RTE. 16		
43+86	PEDESTRIAN CROSSWALK (2 @ 36.4'), WHITE	72.8
44+00, RIGHT	PEDESTRIAN CROSSWALK (20.8' & 19.6'), WHITE	40.4
44+00, LEFT	PEDESTRIAN CROSSWALK (20.8' & 20.1'), WHITE	40.9
44+33.45 TO 45+71.63	TURN LANE LINE, WHITE	138.2
45+71.63 TO 46+71.88	6' SKIP - 2' DASH LINE, WHITE	26.0
ROUNTREE STREET (NORTH)	PEDESTRIAN CROSSWALK (31.5', 38.0'), WHITE	69.5
ROUNTREE STREET (SOUTH)	PEDESTRIAN CROSSWALK (32.0', 37.0'), WHITE	69.0
CHASE STREET	PEDESTRIAN CROSSWALK (29.5', 35.0'), WHITE	64.5
PRESTON STREET	PEDESTRIAN CROSSWALK (23.0', 25.0'), WHITE	48.0
ECCLES STREET (SOUTH)	PEDESTRIAN CROSSWALK (26.0', 30.5'), WHITE	56.5
LEVA STREET	PEDESTRIAN CROSSWALK (31.0', 31.0'), WHITE	62.0
ANNA STREET	PEDESTRIAN CROSSWALK (28.0', 32.5'), WHITE	60.5
VIRGINIA STREET (SOUTH)	PEDESTRIAN CROSSWALK (26.5', 37.0'), WHITE	63.5
PARK STREET	PEDESTRIAN CROSSWALK (36.5', 42.5'), WHITE	79.0
CENTRE STREET	PEDESTRIAN CROSSWALK (28.0', 37.0'), WHITE	65.0
SUB-TOTALS =		955.8
IL RTE. 127		
00+54.80 TO 01+84.10	RIGHT TURN LANE LINE, WHITE	129.3
01+84.10 TO 03+40.00	6' SKIP - 2' DASH LINE, WHITE	39.0
12+87.73 TO 14+33.73	6' SKIP - 2' DASH LINE, WHITE	36.5
14+33.73 TO 15+56.87	LEFT TURN LANE LINE, WHITE	123.1
16+65.00	PEDESTRIAN CROSSWALK (49.5' & 47.0'), WHITE	96.5
16+73.64 TO 17+98.76	LEFT TURN LANE LINE, WHITE	125.1
17+98.76 TO 19+52.60	6' SKIP - 2' DASH LINE, WHITE	38.5
21+94.90 TO 23+22.85	6' SKIP - 2' DASH LINE, WHITE	32.0
23+22.85 TO 24+24.56	LEFT TURN LANE LINE, WHITE	101.7
25+08.40 TO 26+09.50	LEFT TURN LANE LINE, WHITE	101.1
26+09.50 TO 26+80.50	6' SKIP - 2' DASH LINE, WHITE	18.0
50+36.41 TO 51+45.18	LEFT TURN LANE LINE, WHITE	108.8
51+45.18 TO 52+73.12	6' SKIP - 2' DASH LINE, WHITE	128.0
52+73.12 TO 53+75.00	LEFT TURN LANE LINE, WHITE	25.5
54+47.15 TO 56+44.30	RIGHT TURN LANE LINE, WHITE	197.2
56+44.30 TO 58+08.91	6' SKIP - 2' DASH LINE, WHITE	41.2
EAST TREMONT STREET	PEDESTRIAN CROSSWALK (35.5', 41.0'), WHITE	76.5
WEST TREMONT STREET	PEDESTRIAN CROSSWALK (22.5', 28.5'), WHITE	51.0
SUMMER STREET (EAST)	PEDESTRIAN CROSSWALK (32.5', 41.0'), WHITE	73.5
SUMMER STREET (WEST)	PEDESTRIAN CROSSWALK (33.5', 43.0'), WHITE	76.5
JEFFERSON LANE	PEDESTRIAN CROSSWALK (21.5', 25.0'), WHITE	46.5
EAST FAIRGROUNDS AVENUE	PEDESTRIAN CROSSWALK (49.5', 60.5'), WHITE	110.0
VANDALIA STREET	PEDESTRIAN CROSSWALK (47.0', 64.5'), WHITE	111.5
ROUNTREE STREET	PEDESTRIAN CROSSWALK (62.5', 79.0'), WHITE	141.5
HILLTOP ROAD	PEDESTRIAN CROSSWALK (40.0', 55.5'), WHITE	95.5
SUB-TOTALS =		2,124
GRAND TOTAL = 3,544.4 FEET		

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 24"		
LOCATION (STATION OR ROAD)	DESCRIPTION	QUANTITY (FOOT)
IL RTE. 16 / IL RTE. 127		
WOOD STREET (EAST)	STOP BAR, WHITE	16.0
WOOD STREET (EAST)	STOP BAR, WHITE	11.0
TILSON STREET	STOP BAR, WHITE	10.0
MILL STREET	NO WORK	0
PLEASANT STREET	STOP BAR, WHITE	11.0
STA. 41+17.33	STOP BAR, WHITE	25.0
SUB-TOTALS =		73.0
IL RTE. 16		
STA. 44+00.00, RT. TURN LANE	STOP BAR, WHITE	17.4
STA. 44+12.96, LT. TURN LANE	STOP BAR, WHITE	10.5
ROUNTREE STREET (NORTH)	STOP BAR, WHITE	13.0
ROUNTREE STREET (SOUTH)	STOP BAR, WHITE	13.0
CHASE STREET	STOP BAR, WHITE	13.0
LAKEVIEW DRIVE	NO WORK	0
CRITTENDEN STREET	NO WORK	0
PRESTON STREET	STOP BAR, WHITE	12.0
ECCLES STREET (NORTH)	NO WORK	0
ECCLES STREET (SOUTH)	STOP BAR, WHITE	12.0
LEVA STREET	STOP BAR, WHITE	14.0
ANNA STREET	STOP BAR, WHITE	13.0
VIRGINIA STREET (NORTH)	NO WORK	0
VIRGINIA STREET (SOUTH)	STOP BAR, WHITE	12.0
ALLEY	NO WORK	0
PARK STREET	STOP BAR, WHITE	16.0
CENTRE STREET	STOP BAR, WHITE	12.0
SUB-TOTALS =		157.9
IL RTE. 127		
STA. 00+40.00, RT. TURN LANE	STOP BAR, WHITE	17.4
STA. 00+54.80	STOP BAR, WHITE	11.8
EAST TREMONT STREET	STOP BAR, WHITE	13.0
WEST TREMONT STREET	STOP BAR, WHITE	10.0
SUMMER STREET (EAST)	STOP BAR, WHITE	12.0
SUMMER STREET (WEST)	STOP BAR, WHITE	12.0
JEFFERSON LANE	STOP BAR, WHITE	10.0
STA. 15+56.87	STOP BAR, WHITE	31.7
STA. 16+73.64	STOP BAR, WHITE	30.5
EAST FAIRGROUNDS AVENUE	STOP BAR, WHITE	12.0
WEST FAIRGROUNDS AVENUE	STOP BAR, WHITE	13.0
VANDALIA STREET	STOP BAR, WHITE	10.0
ROUNTREE STREET	STOP BAR, WHITE	20.0
EAST MECHANIC STREET	STOP BAR, WHITE	22.0
HILLTOP ROAD	STOP BAR, WHITE	12.0
IDA STREET	STOP BAR, WHITE	11.0
HUBER STREET	STOP BAR, WHITE	10.0
FIRST STREET	STOP BAR, WHITE	12.0
EAST WILLOW AVENUE	STOP BAR, WHITE	12.0
SENATOR MILLER DRIVE	STOP BAR, WHITE	32.0
SUB-TOTALS =		285.2
MAIN STREET	STOP BAR, WHITE	16.0
GRAND TOTAL = 532.1 FEET		

FILE NAME =	USER NAME = laughlinc1	DESIGNED - RTS	REVISED -
c:\pwork\PW100\LAUGHLIN\ld0105356\72C52-ah\schedule.dgn		DRAWN - RTS	REVISED -
		CHECKED - RTS	REVISED -
		DATE - 3-10-10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES			
SCALE	SHEET NO.	OF	SHEETS
	6	OF 8	SHEETS
	STA.		TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**		MONTGOMERY	60	19
CONTRACT NO. 72C52				
ILLINOIS FED. AID PROJECT				