

CONTRACT NO. 72052

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
315	(22B)-1	HANCOCK	13 3
STA.		TO STA.	
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT			

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% STATE
			SFTY-2A
			TOTAL QTY
5012400	CONCRETE REMOVAL	CU YD	1.6
50157300	PROTECTIVE SHIELD	SQ YD	50
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1.6
50501140	STRUCTURAL STEEL REPAIR	L SUM	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	106
50900705	HANDRAIL REMOVAL	L SUM	1
50901760	PIPE HANDRAIL	FOOT	68
67100100	MOBILIZATION	L SUM	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1
X7010825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423 (SPECIAL)	L SUM	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	250
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	250
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP 315 (IS 136)  
SECTION (22B)-1  
HANCOCK COUNTY

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY