

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% STATE
			1000
			TOTAL QTY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8.3
40600300	AGGREGATE (PRIME COAT)	TON	43.4
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600990	TEMPORARY RAMP	SQ YD	37.3
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	2,427
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	21,667
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	150
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	500
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	150
48101200	AGGREGATE SHOULDERS, TYPE B	TON	296
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION , STANDARD 701201	L SUM	1

QUANTITIES
FAP 317 (U.S. 24)
SECTION 4 RS-9
ADAMS COUNTY