

MIXTURE REQUIREMENTS  
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT

	INTERSTATE RESURFACING AND RECONSTRUCTION		
	STABILIZED SUBBASE HOT-MIX ASPHALT	POLYMERIZED HMA SURFACE COURSE	HOT-MIX ASPHALT SHOULDERS
PG GRADE	PG 64-22	SBS PG 70-22	PG 64-22
DESIGN AIR VOIDS	4.0% @ Ndes=30	4.0% @ Ndes=105	4.0% @ Ndes=30
MIXTURE COMPOSITION	IL-19.0L	IL-9.5	IL-19.0L
FRICTION AGGREGATE	N/A	MIXTURE D	N/A

**INDEX OF SHEETS**

9 TITLE SHEET  
10-11 GENERAL NOTES, INDEX OF SHEETS AND STANDARDS  
12-13 SUMMARY OF QUANTITIES  
14 TYPICAL SECTIONS - EXISTING  
15 TYPICAL SECTIONS - PROPOSED  
16-17 SCHEDULE OF QUANTITIES  
18-19 HORIZONTAL CONTROLS AND TIE POINTS  
20-21 PLAN AND PROFILE  
22-27 MAINTENANCE OF TRAFFIC CONSTRUCTION DETAILS  
28-29 EROSION AND SEDIMENT CONTROL PLANS  
30-31 REMOVAL PLANS  
32 MISCELLANEOUS DETAILS  
33-90 STRUCTURE PLANS  
91-124 CROSS SECTIONS - I 70

**IDOT HIGHWAY STANDARDS**

280001-05 TEMPORARY EROSION CONTROL SYSTEMS  
420001-07 PAVEMENT JOINTS  
420601-05 24' (7.2 M) PCC PAVEMENT  
420701-02 PAVEMENT FABRIC  
421001-02 BAR REINFORCEMENT FOR CRC PAVEMENT  
421101-07 24' (7.2 M) CRC PAVEMENT  
482006-03 HMA SHOULDER ADJACENT TO RIGID PAVEMENT  
515001-03 NAME PLATE FOR BRIDGES  
542301-02 PRECAST REINFORCED CONCRETE FLARED END SECTION  
542606-01 REINFORCED CONCRETE PIPE TEE  
601001-03 SUB-SURFACE DRAINS  
601101-01 CONCRETE HEADWALL FOR PIPE DRAIN  
604101-01 MEDIAN INLET FOR 600 MM (24") REINFORCED CONCRETE PIPE  
630001-08 STEEL PLATE BEAM GUARDRAIL  
630301-05 SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS  
631011-06 TRAFFIC BARRIER TERMINAL, TYPE 2  
631031-08 TRAFFIC BARRIER TERMINAL, TYPE 6  
635006-03 REFLECTOR AND TERMINAL MARKER PLACEMENT  
635011-02 REFLECTOR MARKER AND MOUNTING DETAILS  
642001-01 SHOULDER RUMBLE STRIPS  
667101-01 PERMANENT SURVEY MARKERS  
701400-04 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY  
701401-05 LANE CLOSURE, FREEWAY/EXPRESSWAY  
701402-07 LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH BARRIER  
701426-03 LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION, FOR SPEEDS > 45 MPH  
701901-01 TRAFFIC CONTROL DEVICES  
704001-06 TEMPORARY CONCRETE BARRIER  
780001-02 TYPICAL PAVEMENT MARKINGS  
781001-03 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS  
000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS  
001001-02 AREAS OF REINFORCEMENT BARS  
001006 DECIMAL OF AN INCH AND A FOOT

FILE NAME =	USER NAME = paul	DESIGNED - JWS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES, STANDARDS, AND INDEX OF SHEETS</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
PLOT SCALE = 100.0000' / IN.						CHECKED - BRM	REVISED -	70	(25-3)B	EFFINGHAM	1416	10
PLOT DATE = 3/16/2010						DATE - 05-05-09	REVISED -	<b>CONTRACT NO. 74296</b>				
								FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				