

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM LINE 11

BEAM LINE 12

Location	Station	Offset	Theoretical Grade Elevations	Theor. Grade Elev. Adj. For Dead Ld. Deflection	Theor. Grade Elev. Adj. For Dead Ld. Deflection & Grinding
Bk. W. ABUT.	2001+48.52	14.00	527.96	527.96	527.98
CL EXP. JT.	2001+50.59	14.00	527.97	527.97	527.99
CL BRG. W. ABUT.	2001+51.68	14.00	527.97	527.97	527.99
A	2001+61.68	14.00	528.02	528.03	528.05
B	2001+71.68	14.00	528.07	528.09	528.11
C	2001+81.68	14.00	528.12	528.15	528.17
D	2001+91.68	14.00	528.17	528.20	528.22
E	2002+01.68	14.00	528.22	528.25	528.27
F	2002+11.68	14.00	528.27	528.29	528.31
G	2002+21.68	14.00	528.32	528.33	528.35
W. CL BRG. PIER 1	2002+33.85	14.00	528.37	528.37	528.39
CL PIER 1	2002+34.85	14.00	528.38	528.38	528.40
E. CL BRG. PIER 1	2002+35.85	14.00	528.38	528.38	528.40
H	2002+44.85	14.00	528.42	528.43	528.45
I	2002+54.85	14.00	528.46	528.47	528.49
J	2002+64.85	14.00	528.49	528.51	528.53
K	2002+74.85	14.00	528.52	528.55	528.57
L	2002+84.85	14.00	528.55	528.57	528.59
M	2002+94.85	14.00	528.58	528.60	528.62
N	2003+04.85	14.00	528.60	528.61	528.63
W. CL BRG. PIER 2	2003+17.10	14.00	528.63	528.63	528.65
CL PIER 2	2003+18.10	14.00	528.63	528.63	528.65
E. CL BRG. PIER 2	2003+19.10	14.00	528.63	528.63	528.65
O	2003+28.10	14.00	528.64	528.67	528.69
P	2003+38.10	14.00	528.66	528.72	528.74
Q	2003+48.10	14.00	528.67	528.76	528.78
R	2003+58.10	14.00	528.68	528.78	528.80
S	2003+68.10	14.00	528.68	528.80	528.82
T	2003+78.10	14.00	528.68	528.82	528.84
U	2003+88.10	14.00	528.68	528.81	528.83
V	2003+98.10	14.00	528.68	528.79	528.81
W	2004+08.10	14.00	528.67	528.77	528.79
X	2004+18.10	14.00	528.66	528.74	528.76
Y	2004+28.10	14.00	528.65	528.70	528.72
Z	2004+38.10	14.00	528.64	528.66	528.68
W. CL BRG. PIER 3	2004+43.10	14.00	528.63	528.63	528.65
CL PIER 3	2004+44.10	14.00	528.63	528.63	528.65
E. CL BRG. PIER 3	2004+45.10	14.00	528.63	528.63	528.65
AA	2004+54.10	14.00	528.61	528.62	528.64
AB	2004+64.10	14.00	528.59	528.60	528.62
AC	2004+74.10	14.00	528.56	528.58	528.60
AD	2004+84.10	14.00	528.53	528.56	528.58
AE	2004+94.10	14.00	528.50	528.52	528.54
AF	2005+04.10	14.00	528.47	528.49	528.51
AG	2005+14.10	14.00	528.43	528.44	528.46
W. CL BRG. PIER 4	2005+26.35	14.00	528.38	528.38	528.40
CL PIER 4	2005+27.35	14.00	528.38	528.38	528.40
E. CL BRG. PIER 4	2005+28.35	14.00	528.37	528.37	528.39
AH	2005+37.35	14.00	528.34	528.34	528.36
AI	2005+47.35	14.00	528.29	528.31	528.33
AJ	2005+57.35	14.00	528.25	528.27	528.29
AK	2005+67.35	14.00	528.20	528.23	528.25
AL	2005+77.35	14.00	528.15	528.17	528.19
AM	2005+87.35	14.00	528.10	528.12	528.14
AN	2005+97.35	14.00	528.05	528.06	528.08
CL BRG. E. ABUT.	2006+10.51	14.00	527.98	527.98	528.00
CL EXP. JT.	2006+11.60	14.00	527.98	527.98	528.00
BK. E. ABUT.	2006+13.69	14.00	527.97	527.97	527.99

Location	Station	Offset	Theoretical Grade Elevations	Theor. Grade Elev. Adj. For Dead Ld. Deflection	Theor. Grade Elev. Adj. For Dead Ld. Deflection & Grinding
Bk. W. ABUT.	2001+48.52	20.75	527.85	527.85	527.87
CL EXP. JT.	2001+50.59	20.75	527.86	527.86	527.88
CL BRG. W. ABUT.	2001+51.68	20.75	527.87	527.87	527.89
A	2001+61.68	20.75	527.92	527.93	527.95
B	2001+71.68	20.75	527.97	527.99	528.01
C	2001+81.68	20.75	528.02	528.04	528.06
D	2001+91.68	20.75	528.07	528.10	528.12
E	2002+01.68	20.75	528.12	528.14	528.16
F	2002+11.68	20.75	528.17	528.19	528.21
G	2002+21.68	20.75	528.22	528.23	528.25
W. CL BRG. PIER 1	2002+33.85	20.75	528.27	528.27	528.29
CL PIER 1	2002+34.85	20.75	528.27	528.27	528.29
E. CL BRG. PIER 1	2002+35.85	20.75	528.28	528.28	528.30
H	2002+44.85	20.75	528.31	528.32	528.34
I	2002+54.85	20.75	528.35	528.37	528.39
J	2002+64.85	20.75	528.39	528.41	528.43
K	2002+74.85	20.75	528.42	528.44	528.46
L	2002+84.85	20.75	528.45	528.47	528.49
M	2002+94.85	20.75	528.47	528.49	528.51
N	2003+04.85	20.75	528.50	528.51	528.53
W. CL BRG. PIER 2	2003+17.10	20.75	528.52	528.52	528.54
CL PIER 2	2003+18.10	20.75	528.52	528.52	528.54
E. CL BRG. PIER 2	2003+19.10	20.75	528.52	528.52	528.54
O	2003+28.10	20.75	528.54	528.57	528.59
P	2003+38.10	20.75	528.55	528.61	528.63
Q	2003+48.10	20.75	528.56	528.65	528.67
R	2003+58.10	20.75	528.57	528.68	528.70
S	2003+68.10	20.75	528.58	528.70	528.72
T	2003+78.10	20.75	528.58	528.71	528.73
U	2003+88.10	20.75	528.58	528.71	528.73
V	2003+98.10	20.75	528.57	528.69	528.71
W	2004+08.10	20.75	528.57	528.67	528.69
X	2004+18.10	20.75	528.56	528.64	528.66
Y	2004+28.10	20.75	528.55	528.60	528.62
Z	2004+38.10	20.75	528.53	528.55	528.57
W. CL BRG. PIER 3	2004+43.10	20.75	528.52	528.52	528.54
CL PIER 3	2004+44.10	20.75	528.52	528.52	528.54
E. CL BRG. PIER 3	2004+45.10	20.75	528.52	528.52	528.54
AA	2004+54.10	20.75	528.50	528.51	528.53
AB	2004+64.10	20.75	528.48	528.50	528.52
AC	2004+74.10	20.75	528.46	528.48	528.50
AD	2004+84.10	20.75	528.43	528.45	528.47
AE	2004+94.10	20.75	528.40	528.42	528.44
AF	2005+04.10	20.75	528.36	528.38	528.40
AG	2005+14.10	20.75	528.33	528.34	528.36
W. CL BRG. PIER 4	2005+26.35	20.75	528.28	528.28	528.30
CL PIER 4	2005+27.35	20.75	528.27	528.27	528.29
E. CL BRG. PIER 4	2005+28.35	20.75	528.27	528.27	528.29
AH	2005+37.35	20.75	528.23	528.24	528.26
AI	2005+47.35	20.75	528.18	528.20	528.22
AJ	2005+57.35	20.75	528.15	528.17	528.19
AK	2005+67.35	20.75	528.10	528.12	528.14
AL	2005+77.35	20.75	528.05	528.07	528.09
AM	2005+87.35	20.75	528.00	528.01	528.03
AN	2005+97.35	20.75	527.95	527.96	527.98
CL BRG. E. ABUT.	2006+10.51	20.75	527.88	527.88	527.90
CL EXP. JT.	2006+11.60	20.75	527.87	527.87	527.89
BK. E. ABUT.	2006+13.69	20.75	527.86	527.86	527.88

TOP OF SLAB ELEVATIONS
STRUCTURE NO. 025-0107

DESIGNED	B.B.
CHECKED	A.C.S.
DRAWN	W.J.S.
CHECKED	C.J.F. & B.B.



**BERNARDIN
LOCHMUELLER &
ASSOCIATES, INC.**

3 Oak Drive
Maryville, IL 62442-2685
Local (618) 298-4665
Fax 618-298-4666

SHEET NO. 17	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	70	(25-3)B	EFFINGHAM	1416	49
58 SHEETS	SN 025-0107		CONTRACT NO. 74296		
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT 70		