

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				100% STATE BRIDGE 025-0001 X271	100% STATE BRIDGE 025-0018 X271	
	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	240		240	
	POROUS GRANULAR EMBANKMENT	CU YD	235		235	
	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	40	40		
	AGGREGATE (PRIME COAT)	TON	1	1		
	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	412	412		
	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	111	111		
	TEMPORARY RAMP	SQ YD	49	49		
	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	41	41		
	PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	975	975		
	PAVEMENT FABRIC	SQ YD	975	975		
	PAVED SHOULDER REMOVAL	SQ YD	950	950		
	HOT-MIX ASPHALT SHOULDERS	TON	11	11		
	CONCRETE REMOVAL	CU YD	92.5	44	48.5	
	SLOPE WALL REMOVAL	SQ YD	418	59	359	
	PROTECTIVE SHIELD	SQ YD	416	244	172	
	STRUCTURE EXCAVATION	CU YD	36	24	12	
	CONCRETE STRUCTURES	CU YD	93.4	49.8	43.6	
	RUBBED FINISH	SQ FT	737	323	414	
	CONCRETE SUPERSTRUCTURE	CU YD	125	42.9	82.1	
	BRIDGE DECK GROOVING	SQ YD	732	652	80	
	PROTECTIVE COAT	SQ YD	1018	819	199	
	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	17305	7466	9839	
	JACK AND REMOVE EXISTING BEARINGS	EACH	26	18	8	
	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1		
	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1		1	
	REINFORCEMENT BARS, EPOXY COATED	POUND	32680	12170	20510	
	BAR SPLICERS	EACH	117	86	31	
	SLOPE WALL 4 INCH	SQ YD	400	48	352	
	PREFORMED JOINT STRIP SEAL	FOOT	150	91	59	
	NEOPRENE EXPANSION JOINT 2"	FOOT	232	111	121	
	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	26	18	8	
	ANCHOR BOLTS, 1"	EACH	36	36		
	ANCHOR BOLTS, 1 1/4"	EACH	134	72	62	
	ANCHOR BOLTS, 1 1/2"	EACH	16		16	
	CONCRETE SEALER	SQ FT	3400	1938	1462	
	MOBILIZATION	L SUM	0.04	0.02	0.02	
	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	0.04	0.02	0.02	
	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	0.5		0.5	
	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2	1	1	
	SHORT-TERM PAVEMENT MARKING	FOOT	24	24		
	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	282	282		
	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	35	35		
	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	112	112		
	TEMPORARY CONCRETE BARRIER	FOOT	400	400		

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				100% STATE BRIDGE 025-0001 X271	100% STATE BRIDGE 025-0018 X271	
	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400	400		
	SEISMIC RESTRAINER	EACH	28	12	16	
	MATERIAL TRANSFER DEVICE	TON	41	41		
	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	862	388	474	
	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1		
	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1		1	
	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	591	591		
	CONCRETE BRIDGE DECK SCARIFICATION (1/2 INCH)	SQ YD	652	652		
	CONSTRUCTION LAYOUT	L SUM	0.04	0.02	0.02	
	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	25	14	11	
	DRAINAGE SYSTEM	L SUM	1		1	
	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1		
	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1		
	UN SOUND CONCRETE REMOVAL	SQ YD	15.8	10.8	5	