

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5, 135RS-6	ST. CLAIR	762	25
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH

LOCATION			SIDE (RT/LT)	PCC SIDEWALK 4 INCH (SQ FT)
STA.	TO	STA.		
418+48	-	420+36	RT	990
418+43.4	-	422+13	LT	1304.1
TOTAL				2294.1

HMA SHOULDER 8"

LOCATION			HMA SHOULDERS, 8IN (SQ YD)
STA.	TO	STA.	
IL 158			
367+25.70	-	373+00	523.3
373+00	-	388+00	1138.9
388+00	-	391+25	234.4
437+50	-	447+00	887.8
447+00	-	462+00	1533.4
462+00	-	477+00	1327.8
477+00	-	492+00	1316.7
492+00	-	507+00	1366.7
507+00	-	522+00	1366.7
522+00	-	537+00	1366.7
537+00	-	552+00	1366.7
552+00	-	562+00	911.1
576+00	-	581+00	455.6
581+00	-	596+00	1366.7
596+00	-	610+00	1275.6
610+00	-	625+00	1366.7
625+00	-	640+00	1366.7
640+00	-	655+00	1366.7
655+00	-	670+00	1321.1
670+00	-	671+89.58	105.5
673+72.12	-	685+00	2005.1
685+00	-	698+00	2311.1
TOTAL			26,284.5

HMA BINDER COURSE

LOCATION			AREA (SQ YD)	HMA BINDER COURSE, IL 19, N70 (TON)
STA.	TO	STA.		
IL 158				
385+00	-	388+00	146.1	98.2
388+00	-	403+00	464.4	312.1
418+54	-	432+00	1824.6	1226.1
432+00	-	447+00	1192.2	801.2
447+00	-	462+00	1552.2	1043.1
462+00	-	477+00	1411.1	948.3
477+00	-	492+00	289.1	194.3
492+00	-	507+00	1527.8	1026.7
596+00	-	610+00	758.9	510.0
610+00	-	625+00	1021.7	686.6
656+00	-	670+00	6122.6	4500.0
670+00	-	671+89.58	788.9	530.1
673+72.12	-	685+00	1779.7	1196.0
685+00	-	700+00	1862.2	1251.4
TOTAL				14324.0

AGGREGATE SHOULDERS, TYPE A 6"

LOCATION			AGGREGATE SHOULDERS, 6IN (SQ YD)
STA.	TO	STA.	
IL 158			
367+25.70	-	373+00	432.1
373+00	-	388+00	1184.4
388+00	-	389+00	77.4
437+50	-	447+00	730.0
447+00	-	462+00	654.4
462+00	-	477+00	684.5
477+00	-	492+00	792.7
492+00	-	507+00	1366.7
507+00	-	522+00	1184.4
522+00	-	537+00	1366.7
537+00	-	552+00	1366.7
552+00	-	562+00	911.1
576+00	-	581+00	455.6
581+00	-	596+00	1275.6
596+00	-	610+00	1230.0
610+00	-	625+00	1366.7
625+00	-	640+00	1366.7
640+00	-	655+00	1366.7
655+00	-	670+00	1366.7
670+00	-	671+89.58	112.0
TOTAL			19,291.1

HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 14"

LOCATION	HMA PAVEMENT (FULL DEPTH), 14" (SQ YD)
KROPP ROAD	1005
CONCORDIA CHURCH ROAD	2667
TOTAL	3672

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP ROUTE 809
 SECTION (133,134)RS-5, 135RS-6
 ST. CLAIR COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____