CONTRACT NO. 76A47

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	30
STA. _____ TO STA._____				
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

ENTRANCE CULVERT SCHEDULE

LOCATION (STA)	SIDE (LT/RT)	PIPE CULVERTS, CLASS A TYPE 1				PIPE CULVERTS, CLASS C TYPE 1			
			15" (FOOT)	18" (FOOT)	24" (FOOT)	12" (FOOT)	15" (FOOT)	18" (FOOT)	24" (FOOT)
370+51.51	RT						58		
370+59.61	LT		37						
371+24.40	LT		26						
371+95.15	LT						25		
372+78.33	RT						54		
373+94.21	LT						70		
375+00.00	LT		46						
376+20.00	LT		30						
377+15.45	RT		62						
379+44.96	RT		56						
379+82.98	LT		55						
381+10.00	LT						38		
383+30.47	LT						55		
386+10.50	LT						44		
438+33.00	RT		65						
439+68.72	RT						60		
441+21.00	LT		51						
442+25.00	LT		47						
445+67.39	LT						40		
450+20.98	RT		115						
455+50.88	RT		40						
456+15.00	RT		38						
458+27.34	RT						36		
460+14.30	LT						54		
462+84.85	LT						37		
465+59.71	RT						34		
485+46.92	LT		41						
493+54.20	LT						35		
496+54.46	LT		41						
496+60.79	RT		56						
497+95.73	RT						58		
516+06.36	RT		46						
526+44.44	RT		33						
528+76.00	RT						46		
530+70.96	LT							59	
535+66.82	RT							45	
536+59.59	RT							51	
543+43.10	RT								52
544+89.14	LT			63					
546+26.85	RT				40				
546+98.10	LT				42				
548+38.24	RT				42				
548+80.58	LT								45
579+81.76	RT							99	
581+39.91	LT								44
581+89.49	RT								39

ENTRANCE CULVERT SCHEDULE (CONT)

LOCATION (STA)	SIDE (LT/RT)	PIPE CULVERTS, CLASS A TYPE 1				PIPE CULVERTS, CLASS C TYPE 1			
			15" (FOOT)	18" (FOOT)	24" (FOOT)		15" (FOOT)	18" (FOOT)	24" (FOOT)
582+82.96	RT								42
588+62.91	RT						60		
599+36.32	LT							36	
600+31.99	RT						34		
600+33.27	LT							36	
601+72.62	LT							37	
605+27.94	RT						58		
608+04.76	LT						32		
608+96.00	LT						37		
617+33.84	LT						34		
617+31.45	RT						42		
625+26.38	LT						33		
630+37.84	LT		32						
634+74.57	LT						42		
637+11.87	RT						55		
654+58.93	RT							36	
671+43.70	RT		39						
678+17.41	RT		36						
678+93.59	RT		40						
682+75.00	RT		65						
683+78.00	RT		40						
685+21.91	RT		31						
685+99.00	RT		38						
687+75.00	RT		75						
688+91.06	RT		33						
689+27.51	RT		42						
689+48.96	LT						35		
691+12.76	LT						40		
692+29.46	LT						38		
693+08.38	LT						39		
693+83.00	LT						72		
695+32.70	RT		56						
696+58.84	LT						34		
697+69.00	LT		54						
	TOTAL		1466	63	124		1528	300	222

THIS SCHEDULE FOR ENTRANCE CULVERTS ONLY. ADDITIONAL QUANTITIES FOR THE SAME PAY ITEMS MAY BE FOUND ON THE DRAINAGE DETAILS SHEETS.

Rev. Sheet 12-21-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 809
SECTION (133,134)RS-5, 135RS-6
ST. CLAIR COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 12/1/2009
FILE NAME = c:\pw_work\PWIDOT\K0RLASAL\d0ms51269\sch0019026.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = $$REF$