

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	133,134RS-5,135RS-6	ST. CLAIR	762	34
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

TYPE B PATCHING SCHEDULE

STATION	LENGTH (FT)	WIDTH (FT)	T-II SQ YD	T-III SQ YD	T-IV SQ YD	SAW CUT FEET	DOWEL BARS EACH	TIE BARS, .75 IN EACH	PAVE. FABRIC SQ YD
EB 377+81.70	20.00	11.00			24.4	74	18	12	24.4
WB 377+81.70	20.00	11.00			24.4	74	18	12	24.4
EB 377+90.00	6.00	11.00	7.3			46	18		
WB 377+90.00	6.00	11.00	7.3			46	18		
EB 380+45.70	6.00	11.00	7.3			46	18		
WB 380+45.70	6.00	11.00	7.3			46	18		
EB 383+09.70	12.00	11.00	14.7			58	18		
WB 383+09.70	12.00	11.00	14.7			58	18		
EB 385+73.70	20.00	11.00			24.4	74	18		24.4
WB 385+73.70	20.00	11.00			24.4	74	18		24.4
EB 390+00.00	80.00	11.00			97.8	194	18	42	97.8
EB 393+65.70	12.00	11.00	14.7			58	18		
WB 393+65.70	12.00	11.00	14.7			58	18		
EB 398+93.70	6.00	11.00	7.3			46	18		
WB 398+93.70	6.00	11.00	7.3			46	18		
EB 404+21.70	6.00	11.00	7.3			46	18		
WB 404+21.70	6.00	11.00	7.3			46	18		
EB IL 163	120.00	11.00			146.7	274	18	62	146.7
WB 405+25.00	6.00	11.00	7.3			46	18		
EB 406+00	20.00	11.00			24.4	74	18	12	24.4
WB 406+00	20.00	11.00			24.4	74	18	12	24.4
WB 406+85.70	20.00	10.00			22.2	71	16	12	22.2
EB 414+77.70	60.00	11.00			73.3	154	18	32	73.3
EB 417+41.70	8.00	11.00	9.8			50	18		
WB 417+41.70	8.00	11.00	9.8			50	18		
EB 420+05.70	6.00	11.00	7.3			46	18		
WB 420+05.70	6.00	11.00	7.3			46	18		
EB 425+33.70	6.00	11.00	7.3			46	18		
WB 425+33.70	6.00	11.00	7.3			46	18		
EB 426+10	10.00	11.00	12.2			54	18		
WB 426+10	10.00	11.00	12.2			54	18		
EB 427+97.70	100.00	11.00			122.2	234	18	52	122.2
EB 430+08.90	15.00	11.00		18.3		64	18		18.3
WB 430+08.90	15.00	11.00		18.3		64	18		18.3
EB 452+50	300.00	11.00			366.7	634	18	152	366.7
EB 467+57.70	8.00	11.00	9.8			50	18		
WB 467+57.70	8.00	11.00	9.8			50	18		
EB 472+85.70	20.00	11.00			24.4	74	18	12	24.4
WB 472+85.70	20.00	11.00			24.4	74	18	12	24.4
EB 483+41.70	8.00	11.00	9.8			50	18		
WB 483+41.70	8.00	11.00	9.8			50	18		
EB 488+69.70	10.00	11.00	12.2			54	18		
WB 488+69.70	10.00	11.00	12.2			54	18		
EB 493+97.70	8.00	11.00	9.8			50	18		
WB 493+97.70	8.00	11.00	9.8			50	18		
EB 499+25.70	8.00	11.00	9.8			50	18		
WB 499+25.70	8.00	11.00	9.8			50	18		
EB 507+17.70	12.00	11.00	14.7			58	18		
WB 507+17.70	12.00	11.00	14.7			58	18		
EB 512+45.70	15.00	11.00		18.3		64	18		18.3
WB 512+45.70	8.00	11.00	9.8			50	18		
EB 515+09.70	6.00	11.00	7.3			46	18		
WB 515+09.70	6.00	11.00	7.3			46	18		

CONTINUED ON NEXT PAGE

PLOT DATE = 8/28/2009
 FILE NAME = c:\pva\cort\pva\pva\DOT\KARL ASAL\cma51265\shwb182a.dgn
 PLOT SCALE = 82.5412 / IN
 REFERENCE = REF#

REVISIONS		DATE
NAME		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP ROUTE 809
 SECTION (133,134)RS-5, 135RS-6
 ST. CLAIR COUNTY

SCALE: VERT. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____