CONTRACT NO. 76A47

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	35
STA. _____	TO STA._____			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

TYPE B PATCHING SCHEDULE (CONT)

STATION	LENGTH (FT)	WIDTH (FT)	T-II SQ YD	T-III SQ YD	T-IV SQ YD	SAW CUT FEET	DOWEL BARS EACH	TIE BARS, .75 IN EACH	PAVE. FABRIC SQ YD
EB 570+53.70	6.00	11.00	7.3			46	18		
WB 570+53.70	6.00	11.00	7.3			46	18		
EB 599+57.70	6.00	11.00	7.3			46	18		
WB 599+57.70	6.00	11.00	7.3			46	18		
EB 610+13.70	6.00	11.00	7.3			46	18		
WB 610+13.70	6.00	11.00	7.3			46	18		
EB 615+41.70	10.00	11.00	12.2			54	18		
WB 615+41.70	10.00	11.00	12.2			54	18		
EB 620+25	6.00	11.00	7.3			46	18		
WB 620+25	10.00	11.00	12.2			54	18		
EB 620+90	6.00	11.00	7.3			46	18		
WB 620+90	10.00	11.00	12.2			54	18		
EB 636+53.70	8.00	11.00	9.8			50	18		
WB 636+53.70	8.00	11.00	9.8			50	18		
EB 655+01.70	6.00	11.00	7.3			46	18		
EB 655+50.00	6.00	11.00	7.3			46	18		
WB 655+01.70	50.00	11.00			61.1	134	18	27	61.1
EB 657+65.70	8.00	11.00	9.8			50	18		
WB 657+65.70	8.00	11.00	9.8			50	18		
EB 662+65.70	12.00	11.00	14.7			58	18		
EB 675+32.24	8.00	11.00	9.8			50	18		
WB 675+32.24	8.00	11.00	9.8			50	18		
EB 680+60.24	6.00	11.00	7.3			46	18		
WB 680+60.24	6.00	11.00	7.3			46	18		
EB 685+88.24	6.00	11.00	7.3			46	18		
WB 685+88.24	6.00	11.00	7.3			46	18		
EB 409+00	120.00	11.00			146.7	274	18	62	146.7
Antidpated Failures 40%			231.7	22.0	492.9	2310.0	575	200	425
TOTAL			811.1	77.0	1725.1	8085	2013	713	1711.8

HMA SURFACE REMOVAL 1 1/2"

LOCATION STA.	LOCATION STREET NAME	HMA SURFACE REMOVAL 1 1/2" (SQ YD)
394+49.22	N. TYLER	31.2
394+51.63	S. TYLER	41.2
398+19.91	N. LAFAYETTE	47.9
398+17.49	S. LAFAYETTE	33.0
401+13.86	N. JACKSON	49.2
401+15.50	S. JACKSON	43.6
404+16.31	S. MONROE	41.2
404+16.31	N. MONROE	43.4
407+15.98	N. MAIN	37.8
407+18.45	S. MAIN	44.7
410+14.15	S. JEFFERSON	46.0
410+15.64	N. JEFFERSON	44.6
413+64.75	S. BREESE	52.4
413+68.06	N. BREESE	50.8
417+22.99	N. MULLBERRY	51.5
700+33.68 (LT)	AARON DR.	75.5
710+88.10 (LT)	DIANNE DR.	78.5
712+01.73 (RT)	OPTIMIST DR.	85.1
716+56.92 (LT)		104.8
717+84.89 (RT)		52.8
726+77.07 (RT)		118.2
	TOTAL	1,173.4

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 809
SECTION (133,134)RS-5, 135RS-6
ST. CLAIR COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 8/28/2008
FILE NAME = c:\pwworking\IDOT\KARLASAL\dms51269\schd21902a.dgn
PLOT SCALE = 52.9412 ' / IN.
REFERENCE = REF