

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	37
STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT		

SEEDING SCHEDULE

LOCATION	AREA		TEMP. EROS. CONTROL SEEDING (POUND)	SEEDING, CLASS 2 (ACRE)	SODDING (SQ YD)	NITROGEN FERTILIZER NUTIRENT (POUND)	PHOSPHORUS FERTILIZER NUTIRENT (POUND)	POTASSIUM FERTILIZER NUTIRENT (POUND)	MULCH METHOD 2 (ACRE)	COMMENTS
	LEFT (SQ YD)	RIGHT (SQ YD)								
IL 158										
367+25 TO 373+00	801	882	219		1,683	21	21	21		
373+00 TO 388+00	2,908	2,795	742		5,703	71	71	71		
388+00 TO 403+00	786	516	169		1,302	16	16	16		
403+00 TO 418+00										
418+00 TO 432+00	1,176	1,365	331		2,541	32	32	32		
432+00 TO 447+00	1,881	1,719	469		3,600	45	45	45		SODD ENDS 443+00
432+00 TO 447+00	761	1,152	249	0.40		36	36	36	0.40	
447+00 TO 462+00	2,825	3,573	833	1.32		119	119	119	1.32	
462+00 TO 477+00	1,968	3,075	656	1.04		94	94	94	1.04	
477+00 TO 492+00	1,976	1,785	490	0.78		70	70	70	0.78	
492+00 TO 507+00	3,226	3,217	839	1.33		120	120	120	1.33	
507+00 TO 522+00	2,910	2,760	738	1.17		105	105	105	1.17	
522+00 TO 537+00	3,360	2,962	823	1.31		118	118	118	1.31	
537+00 TO 552+00	3,394	3,455	892	1.42		127	127	127	1.42	
552+00 TO 567+00	2,053	1,728	492	0.78		70	70	70	0.78	
567+00 TO 581+00	983	892	244	0.39		35	35	35	0.39	
581+00 TO 596+00	2,084	3,243	693	1.10		99	99	99	1.10	
596+00 TO 610+00	3,187	3,541	876	1.39		125	125	125	1.39	
610+00 TO 625+00	2,192	2,328	588	0.93		84	84	84	0.93	
625+00 TO 640+00	2,199	3,206	704	1.12		101	101	101	1.12	
640+00 TO 655+00	3,228	2,984	809	1.28		116	116	116	1.28	
655+00 TO 670+00	20,831	3,706	3194	5.07		456	456	456	5.07	
670+00 TO 685+00	1,317	2,588	508	0.81		73	73	73	0.81	
685+00 TO 700+00	2,452	3,404	762	1.21		109	109	109	1.21	
700+00 TO 714+00	645	397	136	0.22		19	19	19	0.22	
TOTAL =			16455	23	14829	2259	2259	2259	23	

FRAMES AND GRATES TO BE ADJUSTED

LOCATION (STA.)	F&G TO BE ADJUSTED (EACH)
STA. 391+88 RT	2
STA. 394+77 RT	1
STA. 398+51 RT	1
STA. 409+85 RT	1
STA. 409+86 LT	1
STA. 410+41 RT	1
STA. 410+41 LT	1
STA. 413+39 LT	1
STA. 413+39 RT	1
STA. 415+79 RT	1
TOTAL	11

ADDITIONAL WORK REQUIRED BEYOND SPECIFICATIONS OUTLINED IN ARTICLE 603, SHALL BE PAID FOR ACCORDING TO ARTICLE 109.

STORM SEWER, CLASS A, TYPE I 18"

LOCATION *STRUCTURE ID'S	S.S., CLASS A, TYPE 1, 18" (FT)
7M - 8M	62
8M - 9M	32
9M - 10M	65
10M - 11M	60
11M - 12M	119
12M - 13M	28
13M - 14M	131
14M - 15M	45
15M - 16M	67
16M - 17M	117
CONCORDIA CHURCH ROAD	64
TOTAL	790

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAP ROUTE 809  
 SECTION (133,134)RS-5, 135RS-6  
 ST. CLAIR COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_