

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	40
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT _____		

LOCATION			SHORT-TERM PAVEMENT MARKING	
			WHITE EDGE & LANE LINE	YELLOW CENTER LINE
STATION	TO	STATION	FOOT	FOOT
IL 158				
367+25.70	TO	373+00	46	115
373+00	TO	386+36	107	267
386+36	TO	396+27	94	198
396+27	TO	403+00	54	135
403+00	TO	418+54	125	311
418+54	TO	432+00	120	491
432+00	TO	440+09	65	324
440+09	TO	445+37	42	106
445+37	TO	460+61	134	560
460+61	TO	474+42	116	541
474+42	TO	490+19	126	316
490+19	TO	502+82	111	430
502+82	TO	522+00	154	186
522+00	TO	537+00	120	300
537+00	TO	556+47	76	190
556+47	TO	562+00	45	111
576+00	TO	583+74	62	155
583+74	TO	591+77	65	248
591+77	TO	604+39	101	253
604+39	TO	617+50	128	430
617+50	TO	623+50	48	120
623+50	TO	638+09	117	146
638+09	TO	643+85	46	115
643+85	TO	654+30	94	374
654+30	TO	669+15	131	441
669+15	TO	689+34	162	808
689+34	TO	697+19	44	247
697+19	TO	707+45	82	205
707+45	TO	726+00	157	784
Krupp Road			18	
Stonebridge				
Buffwood				
Cedar Creek/Krista Ln.				
Mine Haul Road				
Concordia Church Road			39	
Woodridge Estates				
SUB-TOTALS			2829	8907
TOTAL			11736	

DETECTABLE WARNINGS				
LOCATION	LT/RT	TYPE	DETECTABLE WARNINGS	COMMENTS
(STA)			(SQ FT)	
418+63.36	RT	PE	12	
418+90.44	RT	PE	12	
419+00.57	LT	PE	12	
419+56.26	RT	PE	12	
420+70.19	LT	SR	12	N KOSSUTH ST
420+70.19	RT	SR	12	S KOSSUTH ST
421+36.16	RT	CE	12	
422+14.65	RT	CE	12	
422+30.66	LT	CE	12	
422+66.00	RT	CE	12	
423+30.75	RT	CE	12	
423+40.79	LT	CE	12	
423+85.00	RT	CE	12	
423+91.22	LT	PE	12	
424+73.50	RT	PE	12	
424+88.40	LT	PE	12	
425+52.22	RT	PE	12	
425+69.96	LT	PE	12	
426+27.40	RT	PE	12	
427+26.72	RT	CE	12	
427+27.09	LT	SR	12	N BALTZ ST
428+52.71	RT	CE	12	
429+55.38	LT	PE	12	
429+74.72	RT	CE	12	
433+08.18	RT	SR	12	REGENCY PL
435+12.94	LT	SR	12	WHEATRIDGE DR
437+30.48	LT	CE	6	
437+35.14	RT	PE	6	
TOTAL			324	

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP ROUTE 809
 SECTION (133,134)RS-5, 135RS-6
 ST. CLAIR COUNTY
 SCALE: VERT. _____
 DATE: _____ HORIZ. _____
 DRAWN BY _____
 CHECKED BY _____