

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	133,134RS-5,135RS-6	ST. CLAIR	762	48
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PRECAST CONC. BOX CULVERT 2' X 1.5'

LOCATION STA.	SIDE (RT/LT)	PRECAST CONC BOX CULV. (2X1.5) (FOOT)
382+44.64	LT	3.6
386+32.04	LT	2.5
386+32.04	RT	3.6
388+47	RT	7
388+45	LT	8
687+54	LT	11
687+45	RT	13.2
TOTAL		48.9

PRECAST CONC. BOX CULVERT 2' X 2'

LOCATION STA.	SIDE (RT/LT)	PRECAST CONC BOX CULV. (2X2) (FOOT)
629+97.73	LT	6.3
629+97.73	RT	7.2
647+48.58	LT	4.5
TOTAL		18

PRECAST CONC. BOX CULVERT 10' X 6'

LOCATION STA.	SIDE (RT/LT)	PRECAST CONC BOX CULV. (10X6) (FOOT)
591+73	LT	19
592+58	RT	18
TOTAL		37

PRECAST CONC. BOX CULVERT 3' X 1.5'

LOCATION STA.	SIDE (RT/LT)	PRECAST CONC BOX CULV. (3X1.5) (FOOT)
503+47	LT	6
503+44	RT	14.1
TOTAL		20.1

PRECAST CONC. BOX CULVERT 6' X 8'

LOCATION STA.	SIDE (RT/LT)	PRECAST CONC BOX CULV. (6X8) (FOOT)
477+69.06	LT	9.3
477+46.38	RT	11.2
TOTAL		20.5

PRECAST CONC. BOX CULVERT 7' X 6'

LOCATION STA.	SIDE (RT/LT)	PRECAST CONC BOX CULV. (7X6) (FOOT)
468+96.82	LT	14.8
468+96.82	RT	16.7
TOTAL		31.5

GUARDRAIL REMOVAL

LOCATION (STA. - STA.)	SIDE (RT/LT)	GUARDRAIL REMOVAL (FOOT)
581+58 - 586+50	LT	492
582+94 - 584+08	RT	116
584+38 - 585+65	RT	128
586+78 - 587+52	LT	76
590+98 - 594+89	LT	391
TOTAL		1203

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP ROUTE 809
 SECTION (133,134)RS-5, 135RS-6
 ST. CLAIR COUNTY
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____