CONTRACT NO. 76A47

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	56
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SIGN SCHEDULE

LOCATION	EXISTING STATION	EXISTING OFFSET	EXISTING SIGN	EXISTING SIZE	EXISTING POST	EXISTING DESCRIPTION	REMOVE SIGN PANEL TYPE 1 SQ FT	REMOVE SIGN PANEL TYPE 2 SQ FT	REMOVE SIGN PANEL TYPE 3 SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE A SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE B SQ FT	REMOVE GROUND MOUNTED SIGN SUPPORT EACH	PROPOSED STATION	PROPOSED OFFSET	PROPOSED SIGN	PROPOSED SIZE	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT	RELOCATE SIGN PANEL ASSEMBLY TYPE A SQ FT	RELOCATE SIGN PANEL ASSEMBLY TYPE B SQ FT	WOOD SIGN SUPPORT FT	ACTION
1	365+64.23	26.87	R2-1	24 X 30	WOOD POST	SPEED LIMIT 35																REMAIN IN PLACE
2	366+68.72	45.33	D3-1	24 X 6	METAL PIPE	STREET SIGN "M.O. STATION"																REMAIN IN PLACE
			D3-1	30 X 6		STREET SIGN "S. ILLINOIS ST."																REMAIN IN PLACE
3	367+03.30	34.32	R1-1	30 X 30	WOOD POST	STOP SIGN																REMAIN IN PLACE
4	367+32.98	48.44	N/A	6' X 4'	STEEL SUPPORT	MALLO'S BAKERY																REMAIN IN PLACE
			N/A	6' X 4'		HOT CROSS BUNS DAILY																REMAIN IN PLACE
			N/A	6' X 4'		MILLSTADT FAMILY CHIROPRACTIC																REMAIN IN PLACE
			N/A	6' X 4'		OFFICE SPACE FOR LEASE																REMAIN IN PLACE
5	367+75.81	49.99	N/A	5' X 4'	2 STEEL SUPPORT'S	FARMERS TAN BILLBOARD																REMAIN IN PLACE
			N/A	5' X 2'-9"		CHANGEABLE MESSAGE SIGN																REMAIN IN PLACE
6	369+32.47	35.37	N/A	7'-10" X 3'-7"	2 WOOD POSTS	WELCOME TO MILLSTADT SIGN					36.1	2										REMOVE
			N/A	48 X 24		SISTER CITY GROSS-BIEBERAU HESSEN GERMANY																REMOVE
7	369+64.74	30.81	N/A	18 X 24	METAL POST	HOME LAND SECURITY				8		1	369+65	35' RT	N/A	18 X 24			8		19	REMOVE AND RELOCATE
			N/A	24 X 18		D.A.R.E. SIGN									N/A	24 X 18						REMOVE AND RELOCATE
			N/A	14 X 20		VETERANS OF FOREIGN WARS SIGN									N/A	14 X 20						REMOVE AND RELOCATE
8	372+12.19	46.48	N/A	10' X 6'	STEEL SUPPORT	CURTIS COLLISION CENTER BILLBOARD																REMAIN IN PLACE
9	373+54.30	33.59	N/A	8'-7" X 4'	2 WOOD POST'S	CURTIS AUTO SALES			34.3			2										REMOVE
10	376+37.33	31.53	R2-1	24 X 30	WOOD POST	SPEED LIMIT 30	5					1	376+37	35' RT	R2-1	24 X 30	5				15.5	NEW SIGN PANEL AND WOOD POST
11	376+49.21	42.45	R8-31	12 X 18	METAL POST	NO PARKING FIRE LANE	1.5					1										REMOVE
12	376+73.63	40.95	R8-31	12 X 18	METAL POST	NO PARKING FIRE LANE	1.5					1										REMOVE
13	377+41.30	38.09	R1-1	30 X 30	METAL POST	STOP SIGN					10.8	1										REMOVE
			N/A	12 X 18		PRIVATE DRIVE NO THRU TRAFFIC																REMOVE
			N/A	12 X 18		DISTRIBUTION OF CIRCULARS IS PROHIBITED ON THIS PROPERTY																REMOVE
			N/A	12 X 18		PRIVATE DRIVE NO THRU TRAFFIC																REMOVE
14	377+94.56	52.41	N/A	8' X 3'	2 STEEL SUPPORT'S	V.F.W. BILLBOARD																REMAIN IN PLACE
			N/A	12' X 4'		CHANGEABLE MESSAGE SIGN																REMAIN IN PLACE
15	379+60.00	38.70	R1-1	30 X 30	METAL POST	STOP SIGN					10.8	1										REMOVE
			N/A	12 X 18		PRIVATE DRIVE NO THRU TRAFFIC																REMOVE
			N/A	12 X 18		DISTRIBUTION OF CIRCULARS IS PROHIBITED ON THIS PROPERTY																REMOVE
			N/A	12 X 18		PRIVATE DRIVE NO THRU TRAFFIC																REMOVE
16	380+72.57	41.98	D3-1	28 X 6	METAL PIPE	STREET SIGN "VETERAN'S DR"				2.4		1										REMOVE
			D3-1	30 X 6		STREET SIGN "S. ILLINOIS ST."																REMOVE
17	381+36.72	38.75	R1-1	30 X 30	WOOD POST	STOP SIGN	6.3					1	381+46	30' RT	R1-1	30 X 30	6.3				15	NEW SIGN PANEL AND WOOD POST
18	383+05.60	25.36	D3-1	18 X 6	METAL PIPE	STREET SIGN "W. WHITE ST"				2		1										REMOVE
			D3-1	30 X 6		STREET SIGN "S. ILLINOIS ST"																REMOVE
19	383+05.16	27.39	R1-1	30 X 30	WOOD POST	STOP SIGN	6.3					1	383+02	30' RT	R1-1	30 X 30	6.3				15	NEW SIGN PANEL AND WOOD POST
20	383+97.70	27.84	N/A	6' X 3'	STEEL SUPPORT	K & D MOTORS BILLBOARD																REMAIN IN PLACE
21	384+43.08	19.26	W1-1R	30 X 30	TEL. STEEL W0/SLEEVE	RIGHT TURN AHEAD	6.3					1	384+43	30' RT	W1-1R	30 X 30	6.3				15.5	NEW SIGN PANEL AND WOOD POST
22	385+57.91	28.29	R2-1	24 X 30	TEL. STEEL W/SLEEVE	SPEED LIMIT 30	5					1	385+58	35' RT	R2-1	24 X 30	5				15.5	NEW SIGN PANEL AND WOOD POST
23	386+88.89	19.97	R1-1	30 X 30	WOOD POST	STOP SIGN	6.3					1	386+97	30' RT	R1-1	30 X 30	6.3				14.5	NEW SIGN PANEL AND WOOD POST
24	387+11.04	19.70	S4-1102	24 X 36	WOOD POST	SCHOOL SPEED ZONE AHEAD				8.3		1	387+11	30' RT	S4-1102	24 X 36	6				16.5	NEW SIGN PANEL AND WOOD POST
			R2-1101	18 X 18		20 M P H									R2-1101	18 X 18	2.3					NEW SIGN PANEL AND WOOD POST
25	387+11.25	36.00	D3-1	30 X 6	METAL PIPE	STREET SIGN "S. DALLAS ST"				2.7		1										REMOVE
			D3-1	34 X 6		STREET SIGN "W. MADISON ST"																REMOVE
26	387+15.53	40.62	R1-1	24 X 24	WOOD POST	STOP SIGN																REMAIN IN PLACE
27	387+68.46	26.52	R1-1	30 X 30	WOOD POST	STOP SIGN	6.3					1	387+63	30' RT	R1-1	30 X 30	6.3				14.5	NEW SIGN PANEL AND WOOD POST
28	390+61.84	36.77	N/A	5' X 3'	2 STEEL SUPPORT'S	MILLSTADT CARPET BILLBOARD																REMAIN IN PLACE
29	391+17.24	22.90	N/A	24 X 24	METAL POST	CITY PARK LEFT				6.4		1	391+17	30' RT	N/A	24 X 24			6.4		13.5	REMOVE AND RELOCATE
			N/A	21 X 30		MOUNT EVERGREEN CEMETERY LEFT									N/A	21 X 30						REMOVE AND RELOCATE
30	391+18.20	25.71	D3-1	22 X 6	METAL PIPE	STREET SIGN "S. POLK ST"				2.7		1										REMOVE
			D3-1	42 X 6		STREET SIGN "W. WASHINGTON AVE"																REMOVE
31	391+61.63	40.00	R1-1	30 X 30	METAL POST	STOP SIGN	6.3					1	391+68	30' RT	R1-1	30 X 30	6.3				15	NEW SIGN PANEL AND WOOD POST
32	392+76.11	19.47	R2-1	24 X 30	TEL. STEEL W/BASE	SPEED LIMIT 30																REMAIN IN PLACE
33	393+88.99	19.25	S4-1100	24 X 48	WOOD POST	SCHOOL SPEED LIMIT 20 ON SCHOOL DAYS WHEN CHILDREN ARE PRESENT																REMAIN IN PLACE
34	394+02.84	27.62	N/A	50 X 25	2 WOOD POST'S	PHILIP M. ACHER, D.D.S. FAMILY DENTISTRY																REMAIN IN PLACE
35	394+31.82	23.90	D3-1	26 X 6	METAL PIPE	STREET SIGN "S. TYLER ST"																REMAIN IN PLACE
			D3-1	42 X 6		STREET SIGN "W. WASHINGTON AVE"																REMAIN IN PLACE
36	394+66.33	29.85	R1-1	30 X 30	METAL POST	STOP SIGN																REMAIN IN PLACE
37	394+71.56	24.01	N/A	18 X 24	METAL POST	DRUG FREE GUN FREE SCHOOL ZONE																REMAIN IN PLACE
38	394+83.18	19.25	S1-1	30 X 30	METAL POST	PEDESTRIAN CROSSING																REMAIN IN PLACE
39	395+26.12	24.33	D9-1	18 X 18	POWER POLE	PHONE SIGN																REMAIN IN PLACE
40	396+53.13	19.53	S4-1100	24 X 48	WOOD POST	SCHOOL SPEED LIMIT 20 ON SCHOOL DAYS WHEN CHILDREN ARE PRESENT																REMAIN IN PLACE
			N/A	12 X 18		THIS IS A D.A.R.E. DRUG FREE SCHOOL ZONE																REMAIN IN PLACE
			W14-3	36 X 48 X 48		NO PASSING ZONE																REMAIN IN PLACE
41	396+87.21	34.00	N/A	8' X 4'-4"	BRICK FOUNDATION	ST. JAMES CHANGEABLE MESSAGE SIGN																REMAIN IN PLACE
42	398+39.11	28.65	R1-1	30 X 30	METAL POST	STOP SIGN																REMAIN IN PLACE
43	398+39.41	24.95	D3-1	36 X 6	METAL PIPE	STREET SIGN "S LAFAYETTE ST"																REMAIN IN PLACE
			D3-1	42 X 6		STREET SIGN "W. WASHINGTON AVE"																REMAIN IN PLACE
44	399+37.67	25.68	N/A	18 X 24	METAL POST	DRUG FREE GUN FREE SCHOOL ZONE																REMAIN IN PLACE

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 809
SECTION (133,134)RS-5, 135RS-6
ST. CLAIR COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 9/15/2009
FILE NAME = c:\pw_work\PWIDOT\KARLASPA\dms51269\sche809020a.dgn
PLOT SCALE = 52.9412 ' / IN.
REFERENCE = REF