CONTRACT NO. 76A47

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	58
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SIGN SCHEDULE

LOCATION	EXISTING STATION	EXISTING OFFSET	EXISTING SIGN	EXISTING SIZE	EXISTING POST	EXISTING DESCRIPTION	REMOVE SIGN PANEL TYPE 1 SQ FT	REMOVE SIGN PANEL TYPE 2 SQ FT	REMOVE SIGN PANEL TYPE 3 SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE A SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE B SQ FT	REMOVE GROUND MOUNTED SIGN SUPPORT EACH	PROPOSED STATION	PROPOSED OFFSET	PROPOSED SIGN	PROPOSED SIZE	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT	RELOCATE SIGN PANEL ASSEMBLY TYPE A SQ FT	RELOCATE SIGN PANEL ASSEMBLY TYPE B SQ FT	WOOD SIGN SUPPORT FT	ACTION
90	442+90.37	28.02	W1-4R	30 X 30	TEL. STEEL WO/SLEEVE	ROAD CURVES RIGHT THEN LEFT AHEAD					10.8	1	442+90	40' RT	W1-4R	30 X 30	6.3			20.3	17	NEW SIGN PANEL AND WOOD POST
			XM-1	18 X 18		ST. CLAIR COUNTY HIGHWAY MILE MARKER									XM-1	18 X 18	2.3					NEW SIGN PANEL AND WOOD POST
			XM-1	18 X 18		ST. CLAIR COUNTY HIGHWAY MILE MARKER									XM-1	18 X 18	2.3					NEW SIGN PANEL AND WOOD POST
91	445+65.43	28.77	N/A	30 X 36	WOOD POST	LOVE THE LAND OF LINCOLN					20.3	1	445+65		N/A	30 X 36					17	REMOVE AND RELOCATE
			N/A	30 X 18		ADOPT A HIGHWAY ST JAMES CATHOLIC SCHOOL									N/A	30 X 18						REMOVE AND RELOCATE
			N/A	36 X 36		CLEANUP CREW WORKING/KEEP ILLINOIS CLEAN CHANGEABLE SIGN									N/A	36 X 36						REMOVE AND RELOCATE
91A	450+94.05	38.79	N/A	14 X 10	GAS VALVE PIPE	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
92	452+26.88	33.55	D3-1	24 X 6	METAL POST	STREET SIGN "GEMSTONE DR"				2.3		1										REMOVE
			D3-1	30 X 6		STREET SIGN "E WASHINGTON"																REMOVE
93	452+14.01	41.78	N/A	48 X 59	2 VYNAL POST'S	OFFICE SPACE FOR LEASE																REMAIN IN PLACE
94	452+85.45	55.43	R1-1	30 X 30	METAL POST	STOP SIGN	6.3					1	452+88	40' RT	R1-1	30 X 30	6.3				15.5	NEW SIGN PANEL AND WOOD POST
95	453+07.75	71.38	N/A	16' X 7'	STONE FOUNDATION	STONE BRIDGE ESTATES																REMAIN IN PLACE
96	464+60.68	23.40	W2-2	30 X 30	WOOD POST	INTERSECTION SIDE ROAD LEFT				8.8		1	464+61	35' RT	W2-2	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
			W16-8	30 X 12		SPRING LAKE ROAD									W16-8	36 X 12	3				15.5	NEW SIGN PANEL AND WOOD POST
97	473+51.42	26.50	S3-1	30 X 30	WOOD POST	SCHOOL BUS STOP AHEAD					15.4	1	473+50	35' RT	W14-3	48 X 60 X 60		9.2			19	REMOVE
			W14-3	48 X 60 X 60		NO PASSING ZONE																NEW SIGN PANEL AND WOOD POST
98	484+16.00	24.88	D3-1	30 X 6	METAL POST	STREET SIGN "UNION CEMT. LN"				2.5		1										REMOVE
			D3-1	30 X 6		STREET SIGN "UNION CEMT. LN"																REMOVE
99	490+29.88	44.89	N/A	8' X 4'	2 WOOD POST'S	CEDAR CREEK BILLBOARD																REMAIN IN PLACE
100	494+70.25	29.41	XM-1	18 X 18	TEL. STEEL WO/SLEEVE	ST. CLAIR COUNTY HIGHWAY MILE MARKER				4.5		1	494+70	35' RT	XM-1	18 X 18	2.3				14.5	NEW SIGN PANEL AND WOOD POST
			XM-1	18 X 18		ST. CLAIR COUNTY HIGHWAY MILE MARKER									XM-1	18 X 18	2.3					NEW SIGN PANEL AND WOOD POST
101	496+07.85	32.88	W14-3	48 X 60 X 60	2 METAL POST'S	NO PASSING ZONE		9.2				2	496+08	40' RT	W14-3	48 X 60 X 60		9.2			18	NEW SIGN PANEL AND WOOD POST
102	496+24.68	35.75	D3-1	24 X 6	METAL POST	STREET SIGN "BEIL RD"	1					1										REMOVE
103	496+78.02	20.89	R1-1	30 X 30	WOOD POST	STOP SIGN	6.3					1	496+72	35' RT	R1-1	30 X 30	6.3				19	NEW SIGN PANEL AND WOOD POST
104	497+27.46	49.11	N/A	8' X 5'	2 WOOD POST'S	CEDAR CREEK BILLBOARD																REMAIN IN PLACE
105	515+57.89	45.79	N/A	8' X 4'	2 WOOD POST'S	CEDAR CREEK BILLBOARD																REMAIN IN PLACE
106	515+80.53	46.33	N/A	34 X 20	2 METAL POST'S	PRIVATE DR NO CONSTRUCTION VEHICLES																REMAIN IN PLACE
107	516+12.22	46.57	R1-1	30 X 30	TEL. STEEL WO/SLEEVE	STOP SIGN																REMAIN IN PLACE
108	516+13.60	49.68	N/A	36 X 36	2 METAL POST'S	HORSES BOARDED, LESSONS, FREE MANURE																REMAIN IN PLACE
109	516+15.67	39.56	D3-1	36 X 6	METAL POST	STREET SIGN "RED BARD FARMS LN"	1.5					1										REMOVE
110	524+59.87	41.27	N/A	48 X 14	3 WOOD POST'S	6' PRIVACY FENCE BLOWOUT SALE!																REMAIN IN PLACE
			N/A	48 X 48		LANDSCAPE & FENCE SOLUTIONS BILLBOARD																REMAIN IN PLACE
			N/A	48 X 14		6' PRIVACY FENCE BLOWOUT SALE!																REMAIN IN PLACE
			N/A	48 X 48		LANDSCAPE & FENCE SOLUTIONS BILLBOARD																REMAIN IN PLACE
111	526+90.79	43.47	N/A	94 X 41	2 WOOD POST'S	PRARIE HILLS GARDEN CENTER BILLBOARD																REMAIN IN PLACE
			N/A	49 X 20		CHANGEABLE MESSAGE SIGN																REMAIN IN PLACE
112	527+66.45	29.10	R15-I100	30 X 18	TEL. STEEL WO/SLEEVE	PENALTY FOR DUMPING ON PUBLIC HIGHWAYS	3.8					1	527+86	30' RT							15.5	NEW SIGN PANEL AND WOOD POST
113	540+42.06	29.41	W2-2	30 X 30	TEL. STEEL WO/SLEEVE	INTERSECTION SIDE ROAD LEFT				7.8		1	540+42	35' RT	W2-2	30 X 30	6.3				18	NEW SIGN PANEL AND WOOD POST
			W16-8	18 X 12		EYMAN ROAD									W16-8	24 X 12	2					NEW SIGN PANEL AND WOOD POST
114	547+35.07	28.38	XM-1	18 X 18	METAL POST	ST. CLAIR COUNTY HIGHWAY MILE MARKER				4.5		1	547+35	35' RT	XM-1	18 X 18	2.3				15.5	NEW SIGN PANEL AND WOOD POST
			XM-1	18 X 18		ST. CLAIR COUNTY HIGHWAY MILE MARKER									XM-1	18 X 18	2.3					NEW SIGN PANEL AND WOOD POST
115	548+19.79	52.98	N/A	48 X 32	2 WOOD POST'S	KNYSAK SIGNS BILLBOARD																REMAIN IN PLACE
			N/A	48 X 32		KNYSAK SIGNS BILLBOARD																REMAIN IN PLACE
116	560+16.04	32.32	W2-2	30 X 30	TEL. STEEL W/SLEEVE	INTERSECTION SIDE ROAD RIGHT				8.8		1	560+16	35' RT	W2-2	30 X 30	6.3				17	NEW SIGN PANEL AND WOOD POST
			W16-8	30 X 12		ROACHTOWN ROAD									W16-8	36 X 12	3					NEW SIGN PANEL AND WOOD POST
117	567+97.95	37.06	D3-1	30 X 6	WOOD POST	STREET SIGN "ROACHTOWN RD"																REMAIN IN PLACE
			R1-1	36 X 36		STOP SIGN																REMAIN IN PLACE
			R1-I100	30 X 18		CROSS TRAFFIC DOES NOT STOP																REMAIN IN PLACE
118	569+01.25	29.82	M1-I100	30 X 24	WOOD POST	ILLINOIS 158																REMAIN IN PLACE
119	578+26.49	33.07	W1-2L	30 X 30	WOOD POST	ROAD CURVES LEFT AHEAD	6.3					1	578+26	35' RT	W1-2L	30 X 30	6.3				15.5	NEW SIGN PANEL AND WOOD POST
120	580+80.89	32.50	W2-2	30 X 30	WOOD POST	INTERSECTION SIDE ROAD LEFT					11.5	1	580+81	35' RT	W2-2	30 X 30	6.3				16.5	NEW SIGN PANEL AND WOOD POST
			W16-8	42 X 18		FRANK SCOTT PARKWAY									W16-8	42 X 12	3.6					NEW SIGN PANEL AND WOOD POST
						NOTE. FLASHING LIGHT ATTACHED																
120A	585+94.82	69.79	N/A	14 X 10	GAS VALVE PROTECTION BOLLARD'S	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
121	587+38.60	35.08	D1-1	48 X 18	WOOD POST	FRANK SCOTT PARKWAY W LEFT	6					1										REMOVE
122	588+66.73	32.73	R1-1	30 X 30	WOOD POST	STOP SIGN WITH BLINDERS				8.3		1			R1-1	30 X 30			6.3		15.5	REMOVE AND RELOCATE
			D3-1	24 X 6		STREET SIGN "OLD OAK LANE"																REMOVE
			D3-1	24 X 6		STREET SIGN "OLD OAK LANE"																REMOVE
123	590+09.39	22.62	M1-I100	30 X 18	METAL POST	ILLINOIS 158	3.8					1	590+09	35' RT	M1-I100	30 X 18	3.8				16	NEW SIGN PANEL AND WOOD POST
124	597+36.98	29.75	W14-3	48 X 60 X 60	2 METAL POST'S	NO PASSING ZONE		9.2				2	597+37	30' RT	W14-3	48 X 60 X 60		9.2			18	NEW SIGN PANEL AND WOOD POST
125	598+51.56	25.01	R1-1	30 X 30	TEL. STEEL WO/SLEEVE	STOP SIGN WITH BLINDERS				6.3		1			R1-1	30 X 30			6.3		15.5	REMOVE AND RELOCATE
126	599+78.76	22.07	XM-1	18 X 18	TEL. STEEL WO/SLEEVE	ST. CLAIR COUNTY HIGHWAY MILE MARKER				4.5		1	599+79	35' RT	XM-1	18 X 18	2.3				16.5	NEW SIGN PANEL AND WOOD POST
			XM-1	18 X 18		ST. CLAIR COUNTY HIGHWAY MILE MARKER									XM-1	18 X 18	2.3					NEW SIGN PANEL AND WOOD POST
127	601+86.06	31.15	N/A	30 X 30	TEL. STEEL WO/SLEEVE	MUD ON PAVEMENT																REMOVE
127A	602+23.02	50.10	N/A	14 X 10	GAS VALVE PROTECTION BOLLARD'S	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
128	604+09.18	29.00	W2-1	30 X 30	TEL. STEEL W/SLEEVE	4 WAY INTERSECTION AHEAD					11.5	1	604+09	30' RT	W2-2	30 X 30	6.3				18.5	NEW SIGN PANEL AND WOOD POST
			W16-8	42 X 18		MINE HAUL RD									W16-8	30 X 12	2.5					NEW SIGN PANEL AND WOOD POST
						NOTE. FLASHING LIGHT ATTACHED																
129	605+08.22	43.19	D3-1	24 X 6	TEL. STEEL WO/SLEEVE	STREET SIGN "WYNDROS DR"	1					1										REMOVE

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 809
SECTION (133,134)RS-5, 135RS-6
ST. CLAIR COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 9/15/2009
FILE NAME = c:\pw_work\PWIDOT\KARLASAL\d0ms51269\sch0019026.dgn
PLOT SCALE = 52.9412 ' / IN.
REFERENCE = REF