CONTRACT NO. 76A47

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	59
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SIGN SCHEDULE

LOCATION	EXISTING STATION	EXISTING OFFSET	EXISTING SIGN	EXISTING SIZE	EXISTING POST	EXISTING DESCRIPTION	REMOVE SIGN PANEL TYPE 1 SQ FT	REMOVE SIGN PANEL TYPE 2 SQ FT	REMOVE SIGN PANEL TYPE 3 SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE A SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE B SQ FT	REMOVE GROUND MOUNTED SIGN SUPPORT EACH	PROPOSED STATION	PROPOSED OFFSET	PROPOSED SIGN	PROPOSED SIZE	PROPOSED SIGN PANEL TYPE 1 SQ FT	PROPOSED SIGN PANEL TYPE 2 SQ FT	PROPOSED RELOCATE SIGN PANEL ASSEMBLY TYPE A SQ FT	PROPOSED RELOCATE SIGN PANEL ASSEMBLY TYPE B SQ FT	PROPOSED WOOD SIGN SUPPORT FT	ACTION
130	605+46.75	42.70	R1-1	24 X 24	METAL POST	STOP SIGN	6.3					1			R1-1	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
131	606+22.70	66.63	N/A	8' X 9'	2 WOOD POST'S	WYNDROSE ESTARES BILLBOARD																REMAIN IN PLACE
132	606+29.90	66.62	N/A	8' X 9'	2 WOOD POST'S	WYNDROSE ESTARES BILLBOARD																REMAIN IN PLACE
133	604+80.49	61.30	N/A	7'-8" X 3'-4"	BRICK FOUNDATION	WYNDROSE ESTARES							AA									REMAIN IN PLACE
134	605+75.50	61.33	N/A	7'-8" X 3'-4"	BRICK FOUNDATION	WYNDROSE ESTARES																REMAIN IN PLACE
135	609+72.61	32.26	N/A	36 X 30	WOOD POST	YMCA OUTDOOR CENTER RIGHT	7.5					1	609+73	40' RT	N/A	48 X 42		14			17.5	NEW SIGN PANEL AND WOOD POST
136	611+15.46	45.20	R1-1	30 X 30	WOOD POST	STOP SIGN	6.3					1			R1-1	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
137	612+51.27	66.23	N/A	20' X 10'	2 STEEL SUPPORT'S	BELLEVILLE ENDURO TEAM BILLBOARD																REMAIN IN PLACE
138	611+21.48	52.53	N/A	N/A	METAL POST	EMPTY SIGN SUPPORT						1										REMOVE
139	616+93.25	22.09	W14-3	48 X 60 X 60	WOOD POST	NO PASSING ZONE		9.3				1	616+93	35' RT	W14-3	48 X 60 X 60		9.3			18	NEW SIGN PANEL AND WOOD POST
140	638+10.59	30.78	W1-2L	36 X 36	WOOD POST	ROAD CURVES LEFT AHEAD	9					1	638+11	35' RT	W1-2L	36 X 36	9				18.5	NEW SIGN PANEL AND WOOD POST
141	639+36.97	27.73	N/A	48 X 48	WOOD POST	BE ALERT FOR STOPPED VEHICLES		16				1	639+37	35' RT	N/A	48 X 48		16			20	BE ALERT FOR STOPPED VEHICLES
142	641+76.83	27.79	R2-1	30 X 36	TEL. STEEL WO/SLEEVE	SPEED LIMIT 50	7.5					1	641+77	35' RT	R2-1	30 X 36	7.5				17	NEW SIGN PANEL AND WOOD POST
143	643+73.49	21.34	W1-8L	18 X 24	TEL. STEEL WO/SLEEVE	CHEVRON LEFT				6		1	643+74	35' RT	W1-8L	18 X 24	3				17	NEW SIGN PANEL AND WOOD POST
			W1-8R	18 X 24		CHEVRON RIGHT									W1-8R	18 X 24	3					NEW SIGN PANEL AND WOOD POST
144	644+73.05	23.46	N/A	48 X 24	WOOD POST	SOCCER FIELDS RIGHT	8					1	644+73	30' RT	N/A	54 X 24	9				17	NEW SIGN PANEL AND WOOD POST
145	645+72.16	23.94	W1-8L	18 X 24	TEL. STEEL WO/SLEEVE	CHEVRON LEFT				6		1	645+72	30' RT	W1-8L	18 X 24	3				17	NEW SIGN PANEL AND WOOD POST
			W1-8R	18 X 24		CHEVRON RIGHT									W1-8R	18 X 24	3					NEW SIGN PANEL AND WOOD POST
146	647+61.41	27.18	W1-8L	18 X 24	TEL. STEEL WO/SLEEVE	CHEVRON LEFT				6		1	647+61	35' RT	W1-8L	18 X 24	3				17	NEW SIGN PANEL AND WOOD POST
			W1-8R	18 X 24		CHEVRON RIGHT									W1-8R	18 X 24	3					NEW SIGN PANEL AND WOOD POST
147	648+42.76	87.19	N/A	9 X 5	3 STEEL SUPPORT'S	BELLE CLAIR SOCCER PARK																REMAIN IN PLACE
			N/A	8 X 2		LEAGUE OFFICE AND WEBSITE																REMAIN IN PLACE
			N/A	9 X 5		BELLE CLAIR SOCCER PARK																REMAIN IN PLACE
			N/A	8 X 2		LEAGUE OFFICE AND WEBSITE																REMAIN IN PLACE
148	648+56.79	28.06	R1-1	30 X 30	TEL. STEEL WO/SLEEVE	STOP SIGN	6.3					1	648+57		R1-1	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
149	648+80.86	28.08	W1-8L	18 X 24	TEL. STEEL WO/SLEEVE	CHEVRON LEFT				6		1	648+81	35' RT	W1-8L	18 X 24	3				16.5	NEW SIGN PANEL AND WOOD POST
			W1-8R	18 X 24		CHEVRON RIGHT									W1-8R	18 X 24	3					NEW SIGN PANEL AND WOOD POST
150	650+24.71	28.76	W1-8L	18 X 24	TEL. STEEL WO/SLEEVE	CHEVRON LEFT				6		1	650+25	35' RT	W1-8L	18 X 24	3				17	NEW SIGN PANEL AND WOOD POST
			W1-8R	18 X 24		CHEVRON RIGHT									W1-8R	18 X 24	3					NEW SIGN PANEL AND WOOD POST
151	651+75.03	29.72	W1-8L	18 X 24	TEL. STEEL WO/SLEEVE	CHEVRON LEFT				6		1	651+75	35' RT	W1-8L	18 X 24	3				15.5	NEW SIGN PANEL AND WOOD POST
			W1-8R	18 X 24		CHEVRON RIGHT									W1-8R	18 X 24	3					NEW SIGN PANEL AND WOOD POST
152	652+76.25	29.57	XM-1	18 X 18	TEL. STEEL WO/SLEEVE	ST. CLAIR COUNTY HIGHWAY MILE MARKER				4.5		1	652+76	35' RT	XM-1	18 X 18	2.3				14.5	NEW SIGN PANEL AND WOOD POST
			XM-1	18 X 18		ST. CLAIR COUNTY HIGHWAY MILE MARKER									XM-1	18 X 18	2.3					NEW SIGN PANEL AND WOOD POST
153	654+64.43	33.02	N/A	N/A	METAL POST	HANGING SIGN SUPPORT, NO SIGN PRESENT						1										REMOVE
154	655+82.61	27.55	W1-2R	36 X 36	WOOD POST	ROAD CURVES RIGHT AHEAD					11.3	1										REMOVE
			W13-1	18 X 18		40 M.P.H																REMOVE
155	670+19.66	20.73	I1-I100	42 X 30	WOOD POST	BELLEVILLE POPULATION SIGN					16.3	1	670+20	45' RT	I1-I100	54 X 24	9				17	NEW SIGN PANEL AND WOOD POST
			R2-1	30 X 36		SPEED LIMIT 45									R2-1	30 X 36	7.5					NEW SIGN PANEL AND WOOD POST
156	678+61.06	29.04	R2-1	30 X 36	WOOD POST	SPEED LIMIT 45	7.5					1	678+61	35' RT	R2-1	30 X 36	7.5				20	NEW SIGN PANEL AND WOOD POST
157	680+78.74	35.02	N/A	48 X 48	2 WOOD POST'S	BARBER MURPHY BILLBOARD		16				2										REMOVE
158	681+21.00	29.28	W1-2L	36 X 36	WOOD POST	ROAD CURVES LEFT AHEAD					13	1	681+21	35' RT	W1-2L	36 X 36	9				21	NEW SIGN PANEL AND WOOD POST
			W13-1	24 X 24		40 M.P.H									W13-1	24 X 24	4					NEW SIGN PANEL AND WOOD POST
158A	689+45.03	58.79	N/A	14 X 10	METAL PIPE	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
159	690+46.81	84.87	N/A	16 X 6	3 WOOD POST'S	WOOD RIDGE ESTATES BILLBOARD																REMAIN IN PLACE
159A	690+94.13	52.15	N/A	14 X 10	METAL POST	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
160	691+76.46	49.70	N/A	70 X 32	BRICK FOUNDATION	WOOD RIDGE ESTATES																REMAIN IN PLACE
161	691+95.24	59.78	D3-1	36 X 6	METAL POST	STREET SIGN "MEADOWLARK LAND"																REMAIN IN PLACE
			D3-1	36 X 6		STREET SIGN "MEADOWLARK LAND"																REMAIN IN PLACE
162	692+00.51	47.25	R1-1	30 X 30	TEL. STEEL WO/SLEEVE	STOP SIGN																REMAIN IN PLACE
163	694+97.78	43.46	N/A	11' X 4'	2 METAL POST'S	DINTELMANN NURSERY AND GARDEN CENTER																REMAIN IN PLACE
			N/A	6' X 4'		CHANGEABLE MESSAGE SIGN																REMAIN IN PLACE
164	696+96.75	29.15	R2-1	24 X 30	TEL. STEEL WO/SLEEVE	SPEED LIMIT 40																REMAIN IN PLACE
165	698+01.13	35.19	N/A	36 X 24	2 METAL POST'S	BELLEVILLE, IL. & PADERBORN, GERMANY SISTER CITIES																REMAIN IN PLACE
166	699+06.05	40.82	N/A	18 X 12	METAL POST	PRIVATE DRIVE																REMAIN IN PLACE
167	699+25.89	32.86	D3-1	24 X 6	WOOD POST	STREET SIGN "KECK ACRES"																REMAIN IN PLACE
			D3-1	24 X 6		STREET SIGN "KECK ACRES"																REMAIN IN PLACE
			R1-1	30 X 30		STOP SIGN																REMAIN IN PLACE
168	700+09.27	43.52	N/A	7' X 7'	STEEL SUPPORT	DENNY HAMANN SIGNS BILLBOARD																REMAIN IN PLACE
169	700+13.03	31.65	N/A	36 X 36	WOOD POST	POLICE IN BELLEVILLE ARREST DRUNK DRIVERS																REMAIN IN PLACE
			R14-3	48 X 60 X 60		NO PASSING ZONE																REMAIN IN PLACE
170	700+34.44	46.32	N/A	N/A	2 METAL POST'S	SIGN IS MISSING																REMAIN IN PLACE
171	701+90.75	31.99	N/A	4' X 5'	2 WOOD POST'S	FOR SALE STRAND & ASSOCIATES COMMERCIAL																REMAIN IN PLACE
			N/A	4' X 5'		FOR SALE STRAND & ASSOCIATES COMMERCIAL																REMAIN IN PLACE
172	704+59.48	42.54	N/A	8' X 4'	2 WOOD POST'S	SPRENGEL'S INNOVATIVE KUSTOMS BILLBOARD																REMAIN IN PLACE
			N/A	8' X 4'		SPRENGEL'S INNOVATIVE KUSTOMS BILLBOARD																REMAIN IN PLACE
173	705+07.64	47.21	N/A	11' X 5'	STEEL SUPPORT	BEST ROYAL INN BILLBOARD																REMAIN IN PLACE
174	705+13.06	33.22	R2-1	24 X 30	TEL. STEEL WO/SLEEVE	SPEED LIMIT 40																REMAIN IN PLACE
175	705+40.64	25.12	N/A	18 X 18	METAL POST	ST. CLAIR COUNTY HIGHWAY MILE MARKER																REMAIN IN PLACE
			N/A	18 X 18		ST. CLAIR COUNTY HIGHWAY MILE MARKER																REMAIN IN PLACE
176	705+83.12	49.27	N/A	10'-3" X 6'-1"	STEEL SUPPORT	CONOCO PHILLIPS BILLBOARD																REMAIN IN PLACE
177	706+40.99	30.41	N/A	8' X 4'-0"	4 METAL LEG'S	MOVEABLE AND CHANGEABLE MESSAGE SIGN																REMAIN IN PLACE
178	709+56.23	41.37	N/A	6' X 3'	STEEL SUPPORT	VEILE CONSTRUCTION BILLBOARD																REMAIN IN PLACE

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 809
SECTION (133,134)RS-5, 135RS-6
ST. CLAIR COUNTY

SCALE: VERT. HORIZ. DRAWN BY
DATE CHECKED BY

PLOT DATE = 9/15/2009
FILE NAME = c:\pw_work\PWIDOT\KORLASAL\dms61269\sch081902a.dgn
PLOT SCALE = 52.5412 ' / IN.
REFERENCE = REF