

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	133,134RS-5,135RS-6	ST. CLAIR	762	61
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIGN SCHEDULE

LOCATION	STATION	OFFSET	SIGN	SIZE	POST	EXISTING						STATION	OFFSET	SIGN	SIZE	PROPOSED				ACTION			
						REMOVE SIGN PANEL			REMOVE SIGN PANEL ASSEMBLY		REMOVE GROUND MOUNTED SIGN SUPPORT EACH					SIGN PANEL		RELOCATE SIGN PANEL ASSEMBLY			WOOD SIGN SUPPORT FT		
						TYPE 1 SQ FT	TYPE 2 SQ FT	TYPE 3 SQ FT	TYPE A SQ FT	TYPE B SQ FT						TYPE 1 SQ FT	TYPE 2 SQ FT	TYPE A SQ FT	TYPE B SQ FT				
233	666+02.15	-194.93	R1-1	30 X 30	TEL. STEEL W/SLEEVE																REMOVE		
234	665+98.13	-183.35	W1-BL	18 X 24	TEL. STEEL WO/SLEEVE																REMOVE		
			W1-8R	18 X 24																		REMOVE	
235	664+92.54	-201.68	W1-BL	18 X 24	TEL. STEEL WO/SLEEVE																REMOVE		
			W1-8R	18 X 24																		REMOVE	
236	663+89.94	-201.60	W1-BL	18 X 24	TEL. STEEL WO/SLEEVE																REMOVE		
			W1-8R	18 X 24																		REMOVE	
237	662+87.99	-179.82	W1-BL	18 X 24	TEL. STEEL WO/SLEEVE																REMOVE		
			W1-8R	18 X 24																		REMOVE	
238	662+77.88	-186.11	R1-1	30 X 30	TEL. STEEL WO/SLEEVE																REMOVE		
239	661+60.66	-137.62	W1-BL	18 X 24	TEL. STEEL WO/SLEEVE																REMOVE		
			W1-8R	18 X 24																		REMOVE	
240	660+56.39	-104.35	R2-1	30 X 36	WOOD POST																REMOVE		
241	658+87.69	-46.95	N/A	48 X 48	WOOD POST			16													REMOVE		
242	655+86.79	-30.00	W1-2R	36 X 36	TEL. STEEL WO/SLEEVE			9													REMOVE		
243	653+60.12	-30.20	N/A	N/A	TEL. STEEL WO/SLEEVE																REMOVE		
244	650+89.41	-29.96	N/A	48 X 24	WOOD POST			8													REMOVE		
245	638+06.16	-28.12	R2-1	30 X 36	TEL. STEEL WO/SLEEVE			7.5			650+89	30' LT	N/A	54 X 24	9			16.5		NEW SIGN PANEL AND WOOD POST			
245A	636+26.57	-50.60	N/A	14 X 10	METAL POST						638+06	30' LT	R2-1	30 X 36	7.5			16		NEW SIGN PANEL AND WOOD POST			
245B	634+46.88	-37.69	N/A	14 X 10	GAS VALVE PROTECTION BOLLARD'S															REMAIN IN PLACE			
246	624+69.98	-48.41	N/A	48 X 48	4 WOOD POST'S																REMAIN IN PLACE		
			N/A	48 X 12																	REMAIN IN PLACE		
			N/A	48 X 18																		REMAIN IN PLACE	
			N/A	48 X 18																		REMAIN IN PLACE	
247	620+26.35	-32.61	N/A	30 X 30	TEL. STEEL WO/SLEEVE			6.3													REMOVE		
			W2-1	30 X 30																	REMOVE		
248	619+03.76	-30.54	W16-8	42 X 18	TEL. STEEL WO/SLEEVE																REMOVE		
			N/A	N/A																		REMOVE	
249	617+01.18	-27.78	W11-10	30 X 30	WOOD POST			6.3													REMOVE		
249A	616+31.03	-42.46	N/A	14 X 10	METAL POST																REMOVE		
250	612+99.15	-74.05	N/A	16' X 8'	4 WOOD POST'S																REMAIN IN PLACE		
			N/A	16' X 18'																	REMAIN IN PLACE		
			N/A	16' X 8'																		REMAIN IN PLACE	
			N/A	16' X 18'																		REMAIN IN PLACE	
250A	612+99.97	-42.64	N/A	14 X 10	METAL POST																REMAIN IN PLACE		
251	611+77.85	-31.66	N/A	36 X 30	WOOD POST			7.5													REMOVE		
252	610+49.89	-30.98	R1-1	30 X 30	WOOD POST			6.3			611+78	35' LT	N/A	48 X 42	14			16.5		NEW SIGN PANEL AND WOOD POST			
253	610+44.39	-31.65	D3-1	30 X 6	METAL POST			1.3													REMOVE		
253A	608+75.45	-51.32	N/A	14 X 10	METAL PIPE																REMOVE		
253B	608+15.34	-50.29	N/A	14 X 10	GAS VALVE PROTECTION BOLLARD'S																REMAIN IN PLACE		
254	598+55.68	-29.79	W1-2R	30 X 30	TEL. STEEL W/SLEEVE			6.3													REMOVE		
254A	595+55.44	-51.08	N/A	14 X 10	METAL POST																REMOVE		
254B	592+65.32	-54.13	N/A	14 X 10	METAL POST																REMOVE		
			W2-2	30 X 30																	REMOVE		
255	592+25.79	-31.95	W16-8	42 X 18	WOOD POST																REMOVE		
			N/A	N/A																		REMOVE	
256	590+93.93	-41.79	D1-1	48 X 18	2 METAL POST'S			6													REMOVE		
			R1-1	36 X 36																		REMOVE	
257	588+84.93	-51.08	D3-1	36 X 6	TEL. STEEL W/SLEEVE																REMOVE		
			D3-1	36 X 6																		REMOVE	
258	587+60.17	-31.46	M1-1100	30 X 24	WOOD POST																REMOVE		
259	581+24.15	-44.58	D3-1	24 X 12	METAL POST			2													REMOVE		
260	574+73.47	-33.34	W2-2	30 X 30	TEL. STEEL WO/SLEEVE																REMOVE		
			W16-8	30 X 12																	REMOVE		
260A	571+89.88	-51.74	N/A	14 X 10	METAL PIPE																REMOVE		
261	566+38.06	-31.62	M1-1100	30 X 24	TEL. STEEL W/SLEEVE																REMOVE		
262	556+68.43	-20.80	W14-3	48 X 60 X 60	WOOD POST			14.2													REMOVE		
263	549+38.44	-32.74	W2-2	30 X 30	TEL. STEEL WO/SLEEVE																REMOVE		
			W16-8	18 X 12																		REMOVE	
264	544+87.26	-35.85	R1-1	30 X 30	TEL. STEEL WO/SLEEVE			6.3													REMOVE		
			D3-1	24 X 9																		REMOVE	
265	544+84.98	-30.09	D3-1	24 X 9	METAL POST																REMOVE		
			D3-1	24 X 9																	REMOVE		
			D3-1	24 X 9																			REMOVE
			D3-1	24 X 9																			REMOVE
266	542+83.42	-32.70	N/A	30 X 36	WOOD POST																REMOVE		
			N/A	30 X 18																		REMOVE	
267	539+70.61	-44.50	N/A	36 X 36	2 WOOD POST'S																REMOVE		
			N/A	48 X 45																			REMOVE

REVISIONS		DATE
NAME		

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

FAP ROUTE 809  
SECTION (133,134)RS-5, 135RS-6  
ST. CLAIR COUNTY

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_

DATE: \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_