

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	162	762A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

EARTHWORK CROSS-SECTION SUMMARY

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
367+50.00	6.54	0.24
368+00	10.17	0.00
369+00	12.60	0.60
369+50	9.37	1.03
370+00	10.82	2.53
371+00	38.76	0.17
371+50	45.39	0.01
372+00	41.99	0.10
372+25	41.99	0.31
372+50	42.88	0.22
373+00	51.81	0.12
374+00	35.96	2.87
374+50	56.24	0.00
374+99	63.46	0.00
375+00	63.89	0.00
375+50	60.11	0.00
376+00	61.27	0.00
376+29	68.23	0.00
376+50	62.91	0.00
377+00	42.44	0.32
377+15.45	42.97	0.21
377+50	52.37	0.33
378+00	50.69	0.98
378+50	42.35	1.39
379+00	36.35	2.02
380+00	42.23	2.23
380+50	29.09	0.66
381+00	21.16	4.24
381+50	12.03	0.23
382+00	8.16	6.35
383+00	17.10	7.17
383+30.47	26.00	0.00
383+50	40.16	0.00
384+00	16.53	5.64
384+50	18.08	6.44

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
385+00	33.10	10.40
385+50	40.47	9.82
386+00	81.10	2.24
386+32.04	52.03	1.92
387+00	16.62	20.24
388+00	9.15	43.30
388+46.79	27.23	23.55
389+25	0.64	2.63
390+50	41.02	0.76
391+00	5.79	0.85
391+50.80	65.33	0.00
392+00	18.59	0.00
392+50	17.95	0.00
393+00	17.62	0.00
393+15	14.11	0.00
419+00	36.74	0.68
420+00	19.10	3.36
420+70.19	52.79	0.38
421+50	29.43	5.10
422+00	27.99	0.97
422+30.66	27.15	3.93
422+66	25.09	0.80
423+00	20.93	6.75
423+40.79	30.28	0.68
423+50	32.95	8.18
424+00	16.62	29.95
424+50	15.55	72.20
425+50	20.08	20.64
426+00	16.86	62.58
426+50	30.19	50.74
427+00	17.89	28.28
428+00	17.54	40.85
428+50	26.63	15.53
429+00	17.72	37.79
429+50	18.75	25.79

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
430+00	20.18	21.22
430+50	19.60	26.67
431+00	18.57	32.71
431+50	18.47	32.13
432+00	18.77	35.74
432+50	18.74	42.81
433+50	19.15	56.94
434+00	15.56	90.41
434+50	17.77	69.78
435+50	25.01	78.74
436+00	28.15	76.75
436+50	24.59	75.71
437+00	18.81	43.92
438+00	70.29	51.23
439+00	28.49	5.14
440+00	37.91	1.74
440+09	38.94	1.89
440+50	27.83	3.38
441+00	30.94	4.51
441+50	41.40	4.08
442+00	59.23	2.70
442+50	82.78	2.57
443+00	100.93	1.97
443+50	103.02	1.83
444+00	85.70	2.00
444+50	55.53	3.65
445+50	50.22	3.45
445+73	59.24	0.20
446+00	50.84	9.34
446+50	56.33	11.30
447+00	63.14	14.32
447+50	58.92	17.65
448+00	57.03	18.73
448+50	65.69	19.94
449+00	73.04	17.81

CONT NEXT SHEET

PLOT DATE = 10/21/2009
 PLOT SCALE = 1/8" = 100'
 PLOT REFERENCE = SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF CUT/FILL END AREAS
 FAP ROUTE 809
 SECTION (133,134)RS-5, 135RS-6
 ST. CLAIR COUNTY
 SCALE: VERT. _____
 DATE _____ HORIZ. _____
 DRAWN BY _____
 CHECKED BY _____