

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	762B
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
449+50	72.82	14.46
450+21.03	53.35	19.52
450+27	61.73	17.57
450+50	61.20	22.84
451+00	28.97	31.16
451+50	32.19	25.71
452+00	39.58	23.88
452+50	63.27	31.97
452+62.16	76.71	30.85
453+00	87.45	26.68
453+50	66.42	22.42
454+00	42.83	13.53
454+50	22.73	28.22
455+00	16.30	57.48
455+50	27.97	120.33
456+00	12.73	190.42
456+20.97	28.76	181.76
456+50	11.97	247.80
456+93.93	169.45	307.73
457+00	10.29	836.84
457+50	14.56	235.66
458+00	26.16	17.65
458+27.34	108.27	0.99
458+50	134.08	0.00
459+00	237.39	0.00
459+09	252.06	0.02
459+50	372.01	0.00
460+00	79.25	0.00
460+14.30	143.56	0.00
460+50	238.46	0.00
460+71.70	339.78	0.00
461+00	397.23	0.00
461+50	191.78	0.00
461+87	238.25	0.00
462+00	219.28	0.00

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
462+50	234.65	0.00
462+84.85	101.68	0.00
463+00	84.64	0.00
463+50	69.54	0.00
464+00	64.13	0.00
464+18.72	73.50	0.00
464+50	57.27	4.54
465+00	55.23	7.15
465+50	51.30	14.52
465+59.71	67.18	14.19
465+83.88	155.74	0.00
466+50	107.72	11.84
467+00	82.23	11.21
467+50	182.79	0.00
468+00	48.25	7.16
468+50	20.48	65.89
468+96.82	130.33	69.03
469+52.17	137.95	1.56
470+00	53.76	0.92
470+50	89.46	2.15
471+00	62.49	4.80
471+50	50.79	6.84
472+00	18.28	20.67
472+50	17.62	24.22
473+00	32.89	15.42
473+50	29.65	12.18
474+00	21.77	20.16
474+50	95.22	12.80
474+54.94	64.76	4.23
475+00	43.73	6.67
475+51.87	70.41	5.56
476+00	112.54	0.71
476+50	210.84	3.95
477+00	49.03	7.09
477+58	32.07	60.19

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
478+00	1.49	221.49
478+50	11.23	162.93
479+00	10.49	121.41
479+40.49	43.20	57.34
479+50	16.22	61.44
480+00	20.81	71.17
480+50	54.41	39.33
481+00	142.01	6.38
481+50	237.34	0.08
482+00	254.60	0.17
482+50	171.65	0.14
483+00	130.29	0.17
483+50	62.71	0.16
484+09.31	68.44	0.11
484+50	35.44	0.00
484+64	33.44	0.00
485+00	24.05	0.47
485+46.92	38.18	1.89
486+00	11.21	0.99
486+50	11.77	0.00
487+00	25.02	0.00
487+50	63.87	0.00
488+00	83.72	0.00
488+50	104.93	0.00
489+00	90.06	0.00
489+43	63.83	0.00
489+50	61.27	0.00
490+00	43.62	0.10
490+50	33.20	0.81
491+00	38.23	2.35
491+50	36.80	4.20
492+00	45.15	4.60
492+50	53.96	4.89
493+00	48.47	7.38
493+54.20	62.78	3.73

CONT NEXT SHEET

DATE = 10/27/2009
 PLOT SCALE = 1/8" = 50.000'
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF CUT/FILL END AREAS
 FAP ROUTE 809
 SECTION (133,134)RS-5, 135RS-6
 ST. CLAIR COUNTY
 SCALE: VERT. _____
 DATE _____ HORIZ. _____
 DRAWN BY _____
 CHECKED BY _____