

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	762C
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

EARTHWORK CROSS-SECTION SUMMARY (CONT)

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
494+00	59.81	8.62
494+50	75.90	6.19
495+00	88.48	6.29
495+50	79.70	6.06
496+00	56.71	8.12
497+00	73.85	11.42
497+50	66.70	14.40
497+95.93	79.61	5.29
498+50	63.85	9.96
499+00	60.60	7.83
499+50	79.23	6.00
500+00	89.99	5.31
500+50	98.73	4.83
501+00	101.64	3.71
501+50	93.43	3.08
502+00	77.89	2.82
502+50	43.30	13.12
503+00	35.34	15.98
503+45.16	68.10	21.91
503+61	42.19	10.42
504+00	18.91	10.19
504+50	31.86	8.85
505+00	32.10	4.52
505+50	47.91	3.23
506+00	52.48	1.34
506+50	83.29	1.83
507+00	52.76	16.56
507+50	39.18	22.38
508+00	26.32	21.97
508+50	11.28	17.75
509+00.96	35.55	0.00
509+50	8.40	2.85
510+00	10.42	0.63
510+50	12.47	2.36
511+00	14.99	3.32

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
511+50	18.87	3.63
512+00	21.84	4.02
512+50	24.18	3.38
513+00	24.14	4.26
513+50	21.14	5.14
514+00	15.88	8.78
514+50	16.33	9.56
515+00	15.06	5.38
515+50	28.20	3.74
516+06.36	57.45	1.75
516+50	62.74	1.77
517+00	58.88	3.32
517+50	44.55	3.95
518+00	38.77	4.42
518+50	44.15	3.95
519+00	57.87	1.71
519+50	65.54	1.84
520+00	65.04	3.12
520+50	37.63	4.12
521+00	24.58	1.96
521+50	26.32	0.49
522+00	20.56	1.28
522+50	20.94	1.56
523+00	22.91	0.37
523+50	27.21	0.38
524+00	29.88	0.24
524+50	30.32	0.19
525+00	37.05	0.00
525+50	51.70	0.00
526+00	53.86	0.00
526+44.44	64.03	0.00
527+00	57.51	0.00
527+50	51.31	0.01
528+00	45.05	0.00
528+75.92	48.93	0.00

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
529+00	45.05	0.00
529+50	35.06	0.00
530+00	46.40	0.00
530+50	68.39	0.00
530+70.96	76.77	0.00
531+00	40.83	0.00
531+50	40.59	0.00
532+00	38.28	0.51
532+50	42.65	0.29
533+0	39.46	0.60
533+50	39.84	0.07
534+00	45.70	0.19
534+50	53.65	0.01
535+00	56.84	0.48
535+50	62.05	0.75
535+66.82	76.61	0.72
536+00	67.92	1.65
536+59.59	84.00	0.00
537+00	60.63	0.78
537+50	58.39	1.65
538+00	55.23	2.03
538+50	50.65	0.98
539+00	49.84	0.84
539+50	53.60	0.72
540+00	48.82	1.17
540+50	62.16	1.49
541+00	79.06	0.97
541+50	95.69	0.21
542+00	88.27	0.11
542+50	74.93	0.00
543+00	65.38	0.05
543+43.10	78.96	0.00
544+00	51.45	1.54
544+50	48.35	0.79
544+89.14	83.96	0.00

CONT NEXT SHEET

PLT DATE = 10/29/2009
 PLOT SCALE = 1"=100'
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF CUT/FILL END AREAS
 FAP ROUTE 809
 SECTION (133,134)RS-5, 135RS-6
 ST. CLAIR COUNTY
 SCALE: VERT. _____
 DATE _____ HORIZ. _____
 DRAWN BY _____
 CHECKED BY _____