

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	762E
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
613+50	21.29	8.54
614+00	19.04	12.33
614+50	17.90	16.78
615+00	16.36	17.60
615+50	16.62	15.40
616+00	17.80	15.44
616+50	18.17	17.84
617+00	21.28	14.59
617+33.74	56.94	0.00
617+50	27.40	9.40
618+00	26.20	10.18
618+34	25.05	8.62
618+50	20.53	7.13
619+00	17.69	6.14
619+50	17.38	6.14
620+00	16.52	6.03
620+50	17.75	4.69
621+00	20.84	4.12
621+50	27.87	4.77
622+00	20.22	5.19
622+50	16.86	5.76
623+00	14.92	6.99
623+50	11.13	7.64
624+00	9.30	8.50
624+50	7.52	10.63
625+00	6.97	13.30
625+50	7.29	11.31
626+00	7.13	10.75
626+50	6.95	11.98
627+00	14.97	11.14
627+50	5.38	10.08
628+00	5.32	8.02
628+50	5.17	7.50
629+00	8.98	8.27
629+50	10.25	5.46

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
629+97.73	38.00	4.20
630+50	30.70	3.77
631+00	30.14	1.31
631+50	31.96	1.87
632+00	33.09	2.27
632+50	28.58	0.63
633+00	28.79	0.68
633+50	36.66	0.55
634+00	26.99	0.92
634+50	21.54	1.19
635+00	19.45	0.73
635+50	22.19	1.37
636+00	21.59	1.34
636+50	32.63	2.08
637+00	30.26	0.00
637+50	60.09	0.99
638+00	53.61	2.47
638+50	38.74	2.91
639+00	30.06	2.79
639+50	26.32	2.90
640+00	22.71	5.26
640+50	21.45	6.10
641+00	21.16	5.87
641+50	21.02	6.22
642+00	19.85	6.28
642+50	21.08	6.44
643+00	18.90	4.68
643+50	15.52	3.49
644+00	12.47	4.64
644+09	11.53	4.86
644+50	12.85	7.70
645+00	10.37	6.17
645+50	13.67	4.19
646+00	14.80	3.42
646+50	17.62	7.45

EARTHWORK CROSS-SECTION SUMMARY (CONT)

STATION	END AREA	
	CUT SQ FT	FILL SQ FT
IL 158		
647+00	18.69	6.24
647+48.58	13.48	8.25
647+50	42.30	5.78
648+25.92	41.88	3.51
649+00	29.47	5.78
649+50	38.90	5.95
650+00	33.74	4.99
650+50	33.11	3.64
651+00	34.91	3.44
651+50	26.65	2.32
652+00	33.60	1.62
652+50	44.94	4.71
653+00	63.87	4.76
653+50	82.88	6.53
654+00	102.74	2.66
655+00	151.65	16.60
655+11	143.43	22.26
655+50	104.03	21.53
656+00	43.27	53.41
656+50	10.10	91.16
656+90	285.64	68.54
657+00	69.76	125.19
657+50	93.60	65.61
658+00	69.50	28.96
658+50	58.61	6.34
659+00	128.37	0.85
659+50	132.30	1.28
660+00	223.98	1.47
660+50	252.03	2.43
661+00	288.51	9.65
661+50	228.64	60.96
662+00	187.23	114.13
662+50	185.85	144.28
663+00	173.88	171.06
663+50	112.09	248.55

PLOT DATE = 10/21/2009
 PLOT SCALE = 1"=50.000'
 REFERENCE = *REF*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF CUT/FILL END AREAS
 FAP ROUTE 809
 SECTION (133,134)RS-5, 135RS-6
 ST. CLAIR COUNTY
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____